214 TOTAL UNITS
14.26 ACRES
15 UNITS/ ACRE
21 ADA UNITS
~~1 SECURITY TRAILER~~
1 RENOVATED STRUCTURE TO HOUSE SECURITY, LAUNDRY, AND ADMIN.
6 DUMPSTERS
1 2 GUARD SHACKS
1 RENOVATED STRUCTURE FOR MAINTENANCE

ZACHARY TAYLOR SITE

169 TOTAL UNITS
10.25 ACRES
16.49 UNITS/ ACRE
16 ADA UNITS
1 SECURITY TRAILER
2 ADMINISTRATION TRAILERS
1 MAINTENANCE SHED
4 DUMPSTERS
3 LAUNDRY TRAILERS
1 GUARD SHACK

MARCONI MEADOWS SITE

0 100 200 300

NORTH

CITY PARK NEW ORLEANS

SCHEMATIC DESIGN
January 17, 2005

Zachary Taylor Site:

Dead Tree Removal
Utility Infrastructure for future soccer complex including underground water, power and sewer distribution.
Renovation of existing structures for future soccer complex.
Improve site drainage and more uniform site topography.

Shaw®

WOODROW WILSON CONSTRUCTION CO., INC.
345 HIGHLANDIA DRIVE
BATON ROUGE, LA 70810

CASHIO · COCHRAN
a limited liability company
LANDSCAPE ARCHITECTURE · ARCHITECTURE · PLANNING
900 DUMAIN ST. NEW ORLEANS, LA 70116 504-944-0882/945-0

JOHN C WILLIAMS ARCHITECTS LLC

New Orleans City Park Temporary Trailer Site