

Wind Retrofit Guide for Residential Buildings

FEMA P-804 / December 2010

Any opinions, findings, conclusions, or recommendations expressed in this publication do not necessarily reflect the views of FEMA. Additionally, neither FEMA nor any of its employees makes any warranty, expressed or implied, or assumes any legal liability or responsibility for the accuracy, completeness, or usefulness of any information, product, or process included in this publication. Users of information contained in this publication assume all liability arising from such use.



FEMA

Acknowledgements

Authors

Omar Kapur, URS Corporation
Amit Mahadevia, URS Corporation
Jae Park, URS Corporation
Samantha Passman, URS Corporation
Manny Perotin, PBS&J
Adam Reeder, PBS&J
Laura Seitz, URS Corporation
Adrienne Sheldon, URS Corporation
Scott Tezak, URS Corporation

FEMA Reviewers and Contributors

Katy Brown, FEMA Region IV
Brooke Buchanan, FEMA Region VIII
Franki Coons, FEMA HQ
Robin Danforth, FEMA Region III
John Ingargiola, FEMA HQ
Stephen Juszczyk, FEMA Mississippi Recovery Office
Dennis Kizziah, FEMA Mississippi Recovery Office
Ed Laatsch, FEMA HQ
John LaBrune, FEMA Mississippi Recovery Office
John Plisich, FEMA Region IV
Shabbar Saiffee, FEMA HQ
Ed Smith, FEMA HQ
Jody Springer, FEMA HQ
Paul Tertell, FEMA HQ
Joyce Wells, FEMA Region IV
Charles Williams, FEMA Region IV
Brian Willsey, FEMA HQ

Reviewers and Contributors

Miles Anderson, Florida Division of Emergency Management
Brett Bowen, URS Corporation
Bill Coulbourne, Applied Technology Council
Frank Lavelle, Applied Research Associates
Philip Line, URS Corporation
Dave Low, DK Low and Associates
Lee-Ann Lyons, URS Corporation
Fred Malik, Institute for Business and Home Safety
Shane Parson, URS Corporation
Susan Patton, URS Corporation
Tim Reinhold, Institute for Business and Home Safety
Tom Reynolds, URS Corporation
Mike Rimoldi, Federal Alliance for Safe Homes
Billy Ruppert, URS Corporation
Randy Schackleford, Simpson Strong-Tie
Amy Siegel, URS Corporation
Tom Smith, TlSmith Consulting
Jeff Suhr, URS Corporation
Scott Sundberg, Category X Coastal Consulting
William H. York, Institute for Business and Home Safety
Michael Young, RMS

Table of Contents

CHAPTER 1: Introduction	1-1
1.1 Need for Technical Guidance	1-2
1.2 Wind Retrofit Project Type	1-2
1.3 Using This Guide.....	1-3
CHAPTER 2: Identifying the Risks and Desired Level of Protection.....	2-1
2.1 Wind Hazards in the Hurricane-Prone Region	2-1
2.2 Levels of Protection.....	2-3
2.2.1 Wind Hazards and Building Codes.....	2-4
2.2.2 Recommended Protection and Best Practices.....	2-5
CHAPTER 3: Evaluating Existing Homes	3-1
3.1 Evaluating a Home	3-1
3.1.1 Basic and Intermediate Package Evaluations.....	3-3
3.1.2 Advanced Package Evaluations.....	3-4
3.2 Determining Whether a Home Is a Good Candidate for a Wind Retrofit Project	3-5
3.3 Deciding What Level of Protection to Achieve	3-7
Costs.....	3-8
Benefits	3-8
CHAPTER 4: Technical Design and Construction Methods	4-1
4.1 Basic Mitigation Package	4-2
4.1.1 Option 1 – Improvements with Roof Covering Replacement	4-2
4.1.2 Option 2 – Improvements without Roof Covering Replacement	4-10
4.1.3 Strengthening Vents and Soffits	4-11
4.1.4 Strengthening Overhangs at Gable End Walls	4-12
4.2 Intermediate Mitigation Package.....	4-14
4.2.1 Protecting Openings	4-14
4.2.2 Bracing Gable End Walls Over 4 Feet Tall.....	4-18
4.2.3 Strengthening Connections of Attached Structures	4-18
4.3 Advanced Mitigation Package	4-21
4.3.1 Developing a Continuous Load Path	4-21
4.3.2 Protecting Openings.....	4-27
4.4 Additional Mitigation Measures	4-28
4.4.1 Exterior Wall Coverings	4-28
4.4.2 Tree Fall	4-29
4.4.3 Exterior Equipment.....	4-30

CHAPTER 5: Implementing Mitigation Projects.....	5-1
5.1 Wind Retrofit Programs.....	5-1
5.1.1 Federal Emergency Management Agency.....	5-1
5.1.2 State Programs.....	5-6
5.1.3 Federal Alliance for Safe Homes Program.....	5-6
5.1.4 FORTIFIED for Existing Homes™ Program.....	5-7
5.2 Factors to Consider When Implementing Wind Retrofit Projects.....	5-7
5.2.1 Code Compliance Check.....	5-7
5.2.2 Permitting and Inspections.....	5-8
5.2.3 Construction Challenges.....	5-12
5.3 Addressing Other Hazards.....	5-13
APPENDIX A: FORTIFIED for Existing Homes™.....	A-1
APPENDIX B: Evaluation Guidance.....	B-1
APPENDIX C: Using the Hurricane Wind Module for Determining Cost Effectiveness of Retrofit Projects.....	C-1
APPENDIX D: References, Resources, and Links.....	D-1
APPENDIX E: Acronyms and Abbreviations.....	E-1

List of Figures

Figure 1-1: HMA grant process.....	1-3
Figure 2-1: Illustration of the hurricane-prone region of the United States.....	2-2
Figure 2-2: Roof structure failure on a house (Galveston, TX, 2008).....	2-3
Figure 2-3: Building built to the 2001 Florida Building Code (FBC) standards with no structural damage after Hurricane Charley (North Captiva Island, 2004).....	2-4
Figure 3-1: Example of a window product label.....	3-4
Figure 3-2: Continuous load path for wind uplift of a residential, wood-frame building.....	3-5
Figure 4-1: Mitigation Packages for wind retrofit projects.....	4-1
Figure 4-2: FEMA 499 Technical Fact Sheet No. 7.1, <i>Roof Sheathing Installation</i>	4-3
Figure 4-3: 4-foot end zones on gable and hip roofs.....	4-5
Figure 4-4: FEMA 499 Technical Fact Sheet No. 7.2, <i>Roof Underlayment for Asphalt Shingle Roofs</i> ...	4-6
Figure 4-5: FEMA 499 Technical Fact Sheet No. 5.2, <i>Roof-to-Wall and Deck-to-Wall Flashing</i>	4-8
Figure 4-6: FEMA 499 Technical Fact Sheet No. 7.3, <i>Asphalt Shingle Roofing for High Wind Regions</i>	4-8
Figure 4-7: FEMA 499 Technical Fact Sheet No. 7.6, <i>Metal Roof Systems in High -Wind Regions</i>	4-9
Figure 4-8: FEMA 499 Technical Fact Sheet No. 7.4, <i>Tile Roofing for High Wind Regions</i>	4-9
Figure 4-9: Example of SPF adhesive application to secure roof deck panels.....	4-10

Figure 4-10: FEMA 499 Technical Fact Sheet No. 9.2, <i>Repairs, Remodeling, Additions, and Retrofitting—Wind</i>	4-11
Figure 4-11: FEMA 499 Technical Fact Sheet No. 7.5, <i>Minimizing Water Intrusion through Roof Vents in High-Wind Regions</i>	4-11
Figure 4-12: Typical soffit retrofit using wood supports.....	4-12
Figure 4-13: Bracing gable end overhangs.....	4-13
Figure 4-14: FEMA 499 Technical Fact Sheets No. 6.1, <i>Window and Door Installation</i> , and No. 6.2, <i>Protection of Openings—Shutters and Glazing</i>	4-15
Figure 4-15: Conceptual gable end retrofit without overhangs.....	4-19
Figure 4-16: Conceptual gable end retrofit with overhangs.....	4-20
Figure 4-17: Roof structure that was poorly connected to the house (Jefferson Parish, LA)	4-22
Figure 4-18: FEMA 499 Technical Fact Sheets No. 4.1, <i>Load Paths</i> and No. 4.3, <i>Use of Connectors and Brackets</i>	4-23
Figure 4-19: Load path connections of a roof system.....	4-24
Figure 4-20: Load path connections of a wall system.....	4-25
Figure 4-21: Load path connections of a foundation.....	4-26
Figure 4-22: FEMA 499 Technical Fact Sheets No. 5.3, <i>Siding Installation in High-Wind Regions</i> and No. 5.4, <i>Attachment of Brick Veneer in High-Wind Regions</i>	4-29
Figure 4-23: A home damaged by fallen trees during Hurricane Katrina (Diamondhead, MS).....	4-30
Figure 5-1: HMA grants cycle process showing roles and responsibilities of each stakeholder ...	5-2
Figure 5-2: FEMA 499 Technical Fact Sheet No. 9.2, <i>Repairs, Remodeling, Additions, and Retrofitting—Wind</i>	5-8
Figure C-1: Example wind-damage function for a wood single-family (one-story) building.....	C-4

List of Tables

Table 4-1: Fasteners Required for Wood Board Decking Attachment to Framing	4-3
Table 4-2: Fasteners Required for Structural Wood Panel Sheathing Attachment to Framing	4-4
Table 5-1: Code Compliance Checks.....	5-9
Table C-1: FEMA BCA Tool Characteristics	C-2
Table C-2: Scenarios Representing Before-Mitigation and After-Mitigation Conditions.....	C-3
Table C-3: Likelihood of Cost Effectiveness	C-5
Table C-4: Hypothetical Mitigation Project Parameters.....	C-6