

Draft Environmental Assessment

Hickory Flat Wireless Communications Tower

Hickory Flat, Benton County, Mississippi

Mississippi Interoperable Communications Grant Program

FEMA 2008-MS-MX-0001, MSWIN 30410

April 2011



FEMA

**U.S. Department of Homeland Security
Washington, DC 20472**

Document Prepared for DHS-FEMA

Prepared by:
Environmental Engineers, Inc.
11578 US Highway 411, Odenville, Alabama 35120

Phone: (205) 629-3868 • Fax: (877) 847-3060
Project No.: JSE01P1016

TABLE OF CONTENTS

1.0 INTRODUCTION 1

2.0 PURPOSE AND NEED 1

3.0 ALTERNATIVES CONSIDERED 2

 3.1 NO-ACTION ALTERNATIVE 2

 3.2 PROPOSED ACTION 2

 3.3 ALTERNATIVES CONSIDERED AND DISMISSED 2

4.0 AFFECTED ENVIRONMENT AND POTENTIAL IMPACTS 3

 4.1 PHYSICAL RESOURCES 4

 4.1.1 Geology and Soils 4

 4.1.2 Air Quality 5

 4.2 WATER RESOURCES 6

 4.2.1 Wild and Scenic Rivers 6

 4.2.2 Water Quality 6

 4.2.3 Wetlands 7

 4.2.4 Floodplain Information 7

 4.3 COASTAL RESOURCES 8

 4.4 BIOLOGICAL RESOURCES 8

 4.4.1 Threatened and Endangered Species 8

 4.4.2 Migratory Birds 9

 4.4.3 Wildlife and Fish 11

 4.4.4 General Vegetation 12

 4.5 CULTURAL RESOURCES 12

 4.5.1 ACHP Program Comment 12

 4.5.2 FCC Nationwide Programmatic Agreement 13

 4.5.3 FCC Tower Construction Notification System 13

 4.5.4 State Historic Preservation Officer 14

 4.5.5 Indian Tribal Consultation 15

 4.5.6 Inadvertent Discovery 16

 4.6 SOCIOECONOMIC CONCERNS 17

 4.6.1 Human Health and Safety 17

 4.6.2 Environmental Justice 17

 4.6.3 Noise 18

 4.6.4 Infrastructure, Utilities, Transportation, and Waste Management 18

 4.6.5 Aesthetics and Visual Impacts 18

 4.7 CUMULATIVE IMPACTS 19

5.0 AGENCY COORDINATION, PUBLIC INVOLVEMENT AND PERMITS	21
6.0 LIST OF PREPARERS	21
7.0 INFORMATION SOURCES	21

FIGURES

Figure 1	Site Locator Map - State
Figure 2	Site Locator Map - County
Figure 3	Site Location Map
Figure 4	2009 Aerial Photograph
Figure 5 through 9	Site Photographs
Figure 10	National Wetland Inventory Map
Figure 11	Flood Insurance Rate Map

APPENDICES

Appendix A	Site Survey
Appendix B	Correspondence to and from the USDA NRCS
Appendix C	Correspondence to and from the U.S. Army Corps of Engineers
Appendix D	Correspondence to and from the U.S. Fish and Wildlife Service
Appendix E	USFWS Interim Guidelines
Appendix F	Avian Mitigation Plan
Appendix G	TCNS Notice of Organizations Which Were Sent Proposed TCN Information
Appendix H	FCC Form 620
Appendix I	Correspondence to and from the Mississippi Department of Archives and History
Appendix J	Correspondence to and from Native American Indian Tribes/Organizations
Appendix K	Phase I ESA
Appendix L	Local Government/Public Notice

1.0 INTRODUCTION

The State of Mississippi created the Mississippi Wireless Communication Commission (MWCC) by statute in 2005 to oversee the construction and operation of the Mississippi Wireless Integrated Network (MSWIN) project. MSWIN is wireless voice and data capable infrastructure, providing all users with a public-safety grade, statewide, interoperable, seamless roaming radio system. This 700 MHz Public Safety System is intended to provide highly reliable, fast access, private (within groups and individuals) communications to a wide variety of government and first-responder users within the State of Mississippi. MSWIN is funded largely by federal funds administered through the Department of Homeland Security and the Federal Emergency Management Agency.

This project is being funded using a FEMA grant (2008-MS-MX-0001) and the State of Mississippi's expenditures at this site would include construction of a telecommunications facility, purchase and installation of 700 MHz RF equipment and microwave telecommunication backbone network, equipment shelter, network integration, acceptance testing, communication hardware optimization and system exercising and piloting of interoperability capabilities of the network. As part of the MSWIN network, this tower would support a myriad of equipment that would provide emergency response communications for the population within approximately fifteen miles surrounding this proposed site.

2.0 PURPOSE AND NEED

This Environmental Assessment has been prepared in accordance with the National Environmental Policy Act (NEPA) of 1969, the President's Council on Environmental Quality regulations implementing NEPA (40 Code of Federal Regulations (CFR) Parts 1500-1508), and FEMA's regulations implementing NEPA (44 CFR Part 10). FEMA is required to consider potential environmental impacts before funding or approving actions and projects. The purpose of this EA is to analyze the potential environmental impacts of the proposed construction of a communications tower facility. FEMA will use the findings in this EA to determine whether to prepare an Environmental Impact Statement (EIS) or a Finding of No Significant Impact (FONSI).

The purpose of the MSWIN is to establish a better communications network for State system users, varying from public safety to governmental executive and administrative personnel to road maintenance crews. The MSWIN network would also be used extensively during life threatening conditions and emergency situations. Flooding, hurricanes, earthquakes, tornadoes, and other natural or man-made catastrophes often require effective wide-area, interoperable communications. Following Hurricane Katrina, there was a significant lack of communication or communication delays between government agencies due to inadequate coverage or inadequate capacity-handling capabilities. A high degree of redundancy and fail-safe design is essential to the success of this project since communications within the State of Mississippi are most critical when they are most susceptible to failure.

3.0 ALTERNATIVES CONSIDERED

The State of Mississippi considered six alternatives to meet the purpose and need stated in Section 2.0. These alternatives included the Proposed Action, No-Action Alternative, and four alternatives that were considered but dismissed for reasons discussed in greater detail below. Two alternatives, the No Action and Proposed Action, are evaluated in this EA.

3.1 NO-ACTION ALTERNATIVE

Under the No-Action Alternative the proposed project would not be constructed. The No-Action alternative is being included to provide a baseline for comparison purposes.

3.2 PROPOSED ACTION

The Proposed Action would consist of construction of a 450-foot guyed communications tower and associated equipment compound to facilitate installation and operation of wireless communications antennae to provide integrated emergency communications between federal, state, and local agencies. These antennae would include microwave dishes that are to be used to send and receive information over long distances without the limitations associated with connection to land lines/cables (primarily interruptions in service due to damage to land lines/cables during emergencies or natural disasters).

3.3 ALTERNATIVES CONSIDERED AND DISMISSED

The State of Mississippi considered four additional alternatives to meet the purpose and need. These alternatives were collocation, satellite communications, commercial cellular communications, and use of the existing State operated networks; all were dismissed from further consideration for the reasons described below.

Collocation opportunities were considered as an alternative to the proposed action. However, the technical loading requirements for this project are for all used structures to be engineered and constructed to the latest tower standards of ANSI/TIA-222-G (class III supporting public safety and mission critical communications). As this is the latest engineering standard and the Class III (public safety) level is the most rigorous engineering standard in the tower industry, there are no existing towers within the coverage area for this project that can be modified to meet this standard and handle the loading requirements MSWIN would place on the tower.

Satellite communications are commercially available and are currently used as a backup communications method in the event the primary systems fail. Satellite communications are cost prohibitive for the 30,000 users who would be a part of the MSWIN radio network.

Commercial cellular communication services are available in much of the service area MSWIN would provide, but not all of the State of Mississippi is covered by a single cellular operator. MSWIN would

provide 97% radio coverage over the state, is more secure than commercial cellular service, is more survivable in the event of natural disasters, and is dedicated to public safety missions. Cellular is an adequate limited backup to the routine and emergency requirements of public safety, but is not adequate for daily operational usage and extreme emergency situations, as compared to the MSWIN system.

The existing State operated radio systems are aging and limited in their coverage reach. The field and dispatch radios are nearing obsolescence and are difficult to find new replacement parts for.

The needs of a growing Mississippi would best be met by the new technology the MSWIN network provides.

4.0 AFFECTED ENVIRONMENT AND POTENTIAL IMPACTS

The site is depicted on the United States Geological Survey 7.5-minute Topographic Quadrangle "Hickory Flat, Mississippi," dated 1982. The site is located in the southwest ¼ of the northwest ¼ of Section 33, Township 5 South, Range 1 East, Benton County, Mississippi, at latitude 34° 36' 27.350" north and longitude 89° 12' 27.761" west. The site consists of a proposed 100-foot by 100-foot lease area with three associated guy anchor easements, and an proposed access road located off of Cornersville Road in Hickory Flat, Mississippi 38633. The site consists of land covered in scrub vegetation with a few scattered hardwood saplings up to three inches in diameter at breast height (dbh), and the site slopes moderately down to the west. The proposed facility access road follows an existing gravel road and extends west from Cornersville Road for approximately 1,300 feet. Proposed activities consist of construction of a 450-foot guyed communications tower and associated compound, enclosing the compound in a fence, placement of support equipment within the compound, and covering the compound with gravel. Maps depicting the site location are included as Figures 1 through 3.

The proposed tower facility would be accessed via locked gate off of Cornersville Road. The tower would have two parking spaces at the entrance of the fenced tower compound. The compound surrounding the tower and equipment would consist of a seven-foot tall security fence with an additional foot of barbed wire surrounding the site. The tower would be built to withstand extreme weather conditions and engineered and constructed to the latest tower standards of ANSI/TIA-222-G (class III supporting public safety and mission critical communications). All radio equipment on the tower would be operated in compliance with all requirements of frequency and power output as regulated by the Federal Communications Commission. Additionally, the gates and fence would have attached no trespassing and other notice and warning signs as may be required by applicable local and federal laws.

Routine operations of the tower facility would have limited vehicular traffic excepting maintenance and routine periodic inspections. Running water or sanitary facilities would not be provided at the facility. Power facilities are available and would be routed in during construction. The tower would not interfere with local residence or the use of the surrounding properties. The increase of vehicular

traffic into the area is anticipated to be negligible. The tower and communication systems located thereon would not interfere with other communication systems in the area.

The tower is designed to allow other users on the structure to promote collocation with up to three positions suitable for cellular telephone type wireless service providers. This would potentially reduce the need for additional towers in the area. In addition, the tower is designed to accommodate additional government communications equipment as needed to provide mission critical radio infrastructure increases in the future. A copy of the portion of the 2009 aerial photograph depicting the site layout has been included as Figure 4 and site photographs have been included as Figures 5 through 9. A copy of the site survey is included as Appendix A.

A table summarizing the potential impacts of the proposed action is included at the end of Section 4.

4.1 PHYSICAL RESOURCES

4.1.1 Geology and Soils

Under the no action alternative there would be no impact to geologic resources or soils.

4.1.1.1 Geology

According to the Mississippi Geological Survey, Geologic Map of Mississippi, dated 1969 and reprinted 1985, the site is underlain by the Wilcox Formation of Tertiary Age. The Wilcox Formation consist of irregularly bedded fine to coarse sand, more or less lignitic clay, and lignite; includes bauxite bearing Fearn Springs sand member at base. Geologic resources may be minimally impacted by drilling or excavation of footings for the proposed communications tower and associated equipment. However, the proposed communications facility would have no significant or wide-spread impacts to geologic resources.

4.1.1.2 Soils

Prime farmland, unique farmland, and land of statewide or local importance is protected under the Farmland Protection Policy Act (FPPA) of 1981 (7 U.S.C. § 4201 *et seq.*). The intent of the FPPA is to minimize the impact Federal programs have on the irreversible conversion of farmland to non-agricultural uses. Prime farmland is defined as land that has the best combination of physical and chemical characteristics for producing food, feed, forage, fiber, and oilseed crops and that is available for these uses. Prime farmland cannot be areas of water or urban or built-up land. Unique farmland is defined as land other than prime farmland that is used for the production of specific high value food and fiber crops such as citrus, tree nuts, olives, cranberries, fruit, and vegetables.

According to the USDA's Soil Survey of Benton County, Mississippi issued January 1977, site soils are classified as Sweatman-Smithdale association, hilly. This association consists of well-drained soils on hilly uplands with slopes ranging from 17 to 45 percent.

Sweatman soils typically have a mixed very dark grayish-brown and brown silt loam about three inches thick. The subsurface layer is a mixture of brown and yellowish-red silt loam about two inches thick. The upper 23 inches of the subsoil is red clay. The lower part of the subsoil is red clay with shale fragments to a depth of 37 inches. The substratum is dark red clay loam with thin layers of light gray and brownish-yellow weathered shale to a depth of 47 inches and stratified light gray and red clay to a depth of 65 inches.

Smithdale soils typically have a surface layer of thin brown fine sandy loam about three inches thick that overlies a subsurface layer of yellowish-brown sandy loam about six inches thick. The subsoil extends to about 70 inches and is comprised of sandy loam and clay loam.

Based on information available at the United States Department of Agriculture Natural Resource Conservation Service (NRCS) Web Soil Survey Internet website, Sweatman-Smithdale association, hilly, is classified as “Not Prime Farmland”.

EEI submitted information regarding the proposed project to the USDA NRCS office in Jackson, Mississippi via letter dated January 5, 2011. The NRCS responded via letter dated January 18, 2011 stating “The site will not be permanently converted, therefore no FPPA prime farmland determination is required.” Copies of the correspondence to and from the NRCS are included as Appendix B.

Soil at the proposed project site is not classified as prime farmland or farmland of statewide importance. In addition, the proposed communications facility would have no significant impact on soils protected by the FPPA because the NRCS does not consider the action to be a permanent conversion of farmland to non-agricultural use.

4.1.2 Air Quality

The Clean Air Act (CAA) was established in 1970 (42 U.S.C. § 7401 *et seq.*) to reduce air pollution nationwide. The US Environmental Protection Agency (EPA) has developed primary and secondary National Ambient Air Quality Standards (NAAQS) under the provisions of the CAA. The EPA classifies the air quality within an air quality control region (AQCR) according to whether the region meets or exceeds Federal primary and secondary NAAQS. An AQCR or a portion of an AQCR may be classified as being in attainment, non-attainment, or it may be unclassified for each of the seven criteria pollutants (carbon monoxide, lead, nitrogen dioxide, coarse particulates, fine particulates, ozone, and sulfur dioxide).

Under the no action alternative there would be no short or long term impacts to air quality.

According to information available through the Mississippi Department of Environmental Quality (MDEQ) Internet website, the State of Mississippi is currently designated as attainment and meets all ambient air quality standards. Short-term impacts to air quality such as exhaust emissions from grading and equipment, and dust from grading activities may occur during site grading and construction activities. Equipment used for these activities would meet local, state, and federal

requirements for air emissions, and dust would be controlled as necessary by wetting the surface of the work areas. The only long-term air emissions anticipated at the site would be from the emergency generator. The generator would only operate briefly while being tested and during power failure events affecting the electrical power supply to the site. Therefore, the proposed communications facility would have no significant impact to air quality.

4.2 WATER RESOURCES

4.2.1 Wild and Scenic Rivers

Under the no action alternative there would be no impact to wild or scenic rivers.

A review of information available through the Rivers.gov Internet website indicates that one Wild and Scenic River is located in Mississippi. This Wild and Scenic River is a section of Black Creek located in the DeSoto National Forest in southeastern Mississippi. The County in which the site is located is more than 200 miles northwest of the DeSoto National Forest. Therefore, the proposed communications facility would have no impacts to any designated Wild and Scenic River.

4.2.2 Water Quality

The Federal Water Pollution Control Act (FWPCA), also known as the Clean Water Act (CWA) was passed by congress in 1972 (33 U.S.C. § 1251 *et seq.*) with an objective of restoring and maintaining the chemical, physical, and biological integrity of waters of the United States. The National Pollutant Discharge Elimination System (NPDES) was established under the CWA and regulates wastewater discharges from point sources. NPDES regulations require that construction sites resulting in greater than one acre of disturbance obtain a permit from the EPA, or the corresponding state agency where the permitting role has been assumed by the state. The Mississippi Department of Environmental Quality (MSDEQ) is the state agency that has assumed this responsibility for Mississippi.

Under the no action alternative there would be no short- or long-term impacts to water quality.

No water bodies are located on or immediately adjacent to the proposed tower site. Land-disturbing activities at this facility would be approximately 0.30 acres, which is below the one acre threshold requiring an NPDES permit. However, appropriate best management practices (BMPs) would be implemented during site development to minimize sediment migration from the site into nearby water bodies. Examples of BMPs that may be used during site development to further minimize any impacts to nearby water resources include, but are not limited to, silt fence, hay or straw bales, hay or straw mulch, gravel, erosion control blankets, and riprap. Therefore, the proposed communications facility would have no significant short- or long-term impacts to water quality in the area of the site.

4.2.3 Wetlands

According to Executive Order (EO) 11990, wetlands are defined as "...those areas inundated by surface or ground water with a frequency sufficient to support and under normal circumstances does or would support a prevalence of vegetative or aquatic life that requires saturated or seasonally saturated soil conditions for growth and reproduction. Wetlands generally include swamps, marshes, bogs, and similar areas such as sloughs, potholes, wet meadows, river overflows, mud flats, and natural ponds. EO 11990 requires that each federal agency take action to minimize the destruction, loss, or degradation of wetlands, and to preserve and enhance the natural and beneficial value of wetlands.

Section 404 of the CWA established a program to regulate the discharge of dredged or fill material into waters of the United States, including wetlands. Activities in waters of the United States regulated under this program include fill for development, water resource projects (such as dams and levees), infrastructure development (such as highways and airports) and mining projects. The United States Department of the Army Corps of Engineers administers the permitting process created under Section 404 of the CWA.

Under the no action alternative there would be no impacts to wetlands.

Information on the USFWS Wetlands Geodatabase website (digital NWI map) was reviewed to determine if any wetlands were delineated on or near the site. Based on a review of information available on this website, the site is not mapped within a jurisdictional wetland. A copy of a portion of the Digital National Wetlands Inventory map depicting the site location has been included as Figure 10.

A site reconnaissance which included observations to determine if the subject site or immediately adjacent property contained any jurisdictional wetlands (as defined by the United States Army Corps of Engineers) was conducted on November 9, 2010 by Environmental Engineers, Inc. No potential jurisdictional wetland indicators were noted on the site at the time of the site reconnaissance.

Information regarding the proposed project was submitted to the United States Army Corps of Engineers (USACE) for review. The USACE responded via letter dated January 12, 2011 stating "Based upon the information you provided, it appears that a Department of the Army permit, pursuant to Section 10 of the Rivers and Harbors Act of 1899 and Section 404 of the Clean Water Act, will not be required for the proposed work." Copies of the correspondence submitted to and response from the USACE are included as Appendix C. The proposed communications facility would have no impacts to wetlands.

4.2.4 Floodplain Information

According to EO 11988, the term floodplain refers to the lowland and relatively flat areas adjoining inland and coastal waters including flood prone areas of offshore islands, including at a minimum, that area subject to a one percent or greater chance of flooding in any given year. This EO requires that

each federal agency take action to reduce the risk of flood loss, to minimize the impact of floods on human safety, health and welfare, and to restore and preserve the natural and beneficial values served by floodplains.

Under the no action alternative there would be no impacts to floodplains.

According to the Federal Emergency Management Agency's (FEMA) Flood Insurance Rate Map (FIRM) "Panel 255 of 280, Benton County, Mississippi and Incorporated Areas" effective date October 2, 2008, the site is located in Zone X (no shading) which is described as areas located outside the 0.2% annual chance floodplain. Therefore, the site is not located in a floodplain. It should be noted that the towers that comprise the MSWIN system are considered critical facilities and project design requirements include that the communications equipment at each facility be elevated at least five feet above the 500-year flood elevation (where mapped). In areas where the 500-year floodplain is not mapped, the equipment will be elevated a minimum of five feet above the 100-year base flood elevation. The FIRM depicting the site location includes areas of 500-year flood. The support equipment at this facility would be elevated at least five feet above the 500-year base flood elevation. Therefore, the proposed communications facility would have no impacts to floodplains and would not be impacted by floodplains. The portion of the FEMA FIRM depicting the site is included as Figure 11.

4.3 COASTAL RESOURCES

The Coastal Zone Management Act (CZMA) was established in 1972 (16 U.S.C. § 1451 *et seq.*) to preserve, protect, and (where possible) restore or enhance the resources of the coastal zones of the United States.

Under the no action alternative there would be no impact to coastal resources.

The Coastal Zone in Mississippi includes the three counties along the coast (Hancock, Harrison, and Jackson) and the adjacent coastal waters. The site is located more than 300 miles from the Gulf of Mexico and is not located in the Mississippi Coastal Zone. Therefore, the proposed communications facility would have no impacts to coastal resources.

4.4 BIOLOGICAL RESOURCES

4.4.1 Threatened and Endangered Species

The Endangered Species Act (ESA) of 1973 (16 U.S.C. 1531 – 1544) provides for the conservation of ecosystems upon which threatened and endangered species of fish, wildlife, and plants depend. The ESA prohibits actions that may harm or jeopardize the continued existence of any threatened or endangered species, or critical habitat.

Under the no action alternative there would be no impact to threatened or endangered species.

Information regarding the proposed wireless telecommunications tower was submitted to the USFWS by Environmental Engineers, Inc. The USFWS responded via letter dated December 2, 2010 stating "There are no federally listed terrestrial species for Benton County." Therefore, the proposed communications facility would have no impact on threatened or endangered species. Copies of the correspondence to and the response from the USFWS are included as Appendix D.

4.4.2 Migratory Birds

The Migratory Bird Treaty Act (16 U.S.C. 703) established a Federal prohibition, unless permitted by regulations, to "pursue, hunt, take, capture, kill, attempt to take, capture or kill, possess, offer for sale, sell, offer to purchase, purchase, deliver for shipment, ship, cause to be shipped, deliver for transportation, transport, cause to be transported, carry, or cause to be carried by any means whatever, receive for shipment, transportation or carriage, or export, at any time, or in any manner, any migratory bird, or any part, nest, or egg of any such bird."

Under the no action alternative there would be no impact to migratory birds.

The United States Fish and Wildlife Service (USFWS) developed voluntary recommendations regarding communications tower siting, construction, operation, and decommissioning. These recommendations include collocating of antennae on existing towers or other structures, limiting the height of new towers to less than 199 feet above ground level (AGL), if taller than 199 feet use of the minimum amount of pilot warning and obstruction avoidance lighting required (preferably white strobes), use of non-guyed towers (monopoles, self-supporting towers), consideration of cumulative impacts on migratory birds, locating towers within "antenna farms" where possible, use of the minimum lighting permissible, use daytime visual markers on guy wires, minimization of the footprint of the facility to avoid habitat loss, design of new towers to accommodate additional comparable antennae for at least two additional users, and down-shielding security lighting for on-ground facilities. A copy of the USFWS communications tower siting, construction, operation, and decommissioning recommendations are included in Appendix E.

A basic principal of radio communication coverage is increasing the height extends signal range. Effective coverage is a function of height so to lower each site to less than 199 feet increases the potential tower count over 300 to accomplish the coverage requirements, resulting in roughly 3,000,000 square feet of ground disturbance, or well over twice the current footprint disturbance requirements. Such an increase in ground impact risks a much greater adversity to terrestrial based habitat such as animals and plants, plus the additional carbon footprint produced by the increased development and construction activities.

The build plan for the MSWIN project generally involves construction of one to three towers per county with a total of approximately 140 towers covering the 46,907 square miles (121,489 square kilometers) of land area in the state. This averages out to one tower for every 335 square miles (867 square kilometers) of land area in the state. No county will contain more than five MSWIN towers and

many counties will contain only one tower. It is important to note that fewer towers are to be constructed in the delta along the Mississippi River due to the flat terrain and corresponding longer transmit and receive distances achieved. This would reduce potential impacts to migratory birds utilizing the Mississippi Flyway migratory route along the Mississippi River.

The Federal Aviation Administration (FAA) has jurisdiction over all tower lighting and conducts aeronautical studies under the provisions of 49 U.S.C., Section 44718 and if applicable Title 14 of the Code of Federal Regulations, part 77, concerning the impact on arrival, departure, and en route procedures for aircraft operating under VFR/IFR conditions at existing and planned public use airports, as well as aeronautical facilities.

For purposes of MSWIN tower development, obstruction lighting may be one of three types:

- (1) Medium intensity flashing white obstruction lights (white strobes in both day and night (D-1 or D-2)); or
- (2) Dual lighting with red / medium intensity flashing white lights (white strobes in daylight and red strobes at night – E-1 or E-2); or
- (3) Marking and lighting with painted towers and red night beacons. This applies to towers over 500 feet in height (E-2 light system).

The proposed tower would be equipped with medium intensity flashing white obstruction lights (white strobes in both day and night).

Bird flight diverters will not be installed on the proposed tower. According to Towers of Mississippi, bird flight diverters are expensive and difficult to maintain over the life of the tower. Adding daytime warning devices to the remainder of the towers in this project would exceed \$5 million in additional capital requirements.

As stated in Section 1.0, the proposed tower would be designed to accommodate equipment for up to three additional wireless communications providers thereby reducing the need for additional towers in the service area of the proposed project. Security lighting at this facility would consist of motion-activated wall-mounted lights on the equipment shelter at the site.

The construction of the proposed tower would not have a significant impact on migratory birds. However, this tower is part of the MSWIN program that may have the potential for cumulative impacts to migratory birds.

FEMA has identified that the statewide MSWIN program has the potential for cumulative impacts to migratory birds, as birds could be injured or killed by colliding into guy wires and/or the tower structure, or could be disoriented by the tower lighting. FEMA has worked with MWCC and Mississippi Department of Wildlife, Fisheries, and Parks (MDWFP) to develop an Avian Mitigation

Plan (Appendix F) to address this potential for cumulative impacts. The mitigation includes monitoring the presence of deceased birds at MSWIN tower sites and providing a collection kit on site to collect the remains and record the location of any deceased bird. The remains of the bird along with the data will be delivered to MDWFP and included in the state's Avian Mortality database. USFWS will also be given access to this database. If an injured bird is found, all efforts will be made to help the bird recover so that it can be released back into the wild. In addition, MDWFP and USFWS (Jackson, MS Ecological Services office) will be given access to the MSWIN tower sites for monitoring. If a particular tower is found to have adverse effects to migratory birds (greater than 10 kills per night) the towers will be reported to MDWFP, USFWS, and FEMA. MWCC will also provide an annual report documenting the number of avian deaths and provide that report to MDWFP, FEMA, and USFWS for five years after all towers have been constructed. This mitigation plan will contribute scientific data that can be used by MDWFP and USFWS in determining the significance of potential impacts of towers on migratory birds. The implementation of the Avian Mitigation Plan will lower the potential for the MSWIN program to have adverse cumulative impacts on migratory birds.

4.4.3 Wildlife and Fish

The Wilderness Act (16 U.S. C. 1131-1136) established the National Wilderness Preservation System to be composed of federally owned areas designated by Congress as "wilderness areas."

Under the no action alternative there would be no impact to wilderness areas.

The proposed communications facility would not adversely affect wilderness areas. Based on a review of information available through the Wilderness.net Internet website, two wilderness areas are located in Mississippi – Black Creek Wilderness and Leaf Wilderness. The site is not located within the boundaries of, or adjacent to either wilderness area. Therefore, the proposed communications facility would have no impact on wilderness areas.

On October 9, 1997, President Clinton signed the National Wildlife Refuge System Improvement Act of 1997 (P.L. 105-57) into law. This new law amended and built upon the National Wildlife Refuge System Administration Act of 1966 to ensure that the National Wildlife Refuge System is managed as a national system of related lands, waters, and interests for the protection and conservation of the Nation's wildlife resources.

The 1966 Act provides guidelines and directives for administration and management of all areas in the system, including "wildlife refuges, areas for the protection and conservation of fish and wildlife that are threatened with extinction, wildlife ranges, game ranges, wildlife management areas, or waterfowl production areas."

Under the no action alternative there would be no impact to wildlife refuges.

Based on a review of information available at the USFWS Internet website and at the Nationalatlas.gov Internet website, the site is not located within the boundaries of, or adjacent to, any wildlife refuges. Therefore, the proposed communications facility is expected to have no impacts to wildlife refuges.

4.4.4 General Vegetation

Impacts to general vegetation are anticipated to be limited to the areas that are to be excavated and/or graded in preparation of the site for construction of the proposed communications tower and access road. The site consists of grassed land. The total area of vegetation to be impacted at this site is approximately 1.11 acres. Therefore, the proposed communications facility would have no significant impact on general vegetation.

4.5 CULTURAL RESOURCES

Under Section 106 of the National Historic Preservation Act (NHPA), Federal agencies are required to consider the impacts of their actions on historic properties. Historic properties are those that are listed on or eligible for listing on the National Register of Historic Places, and are defined as districts, sites, buildings, structures, and objects significant in American history, architecture, archeology, engineering, and culture. The goal of the NHPA is to have federal agencies act as responsible stewards of the nation's resources when their actions affect historic properties. The historic preservation review process mandated by Section 106 is outlined in regulations issued by the Advisory Council on Historic Preservation (ACHP) (36 CFR Part 800). The ACHP is an independent federal agency that promotes the preservation, enhancement, and productive use of the nation's historic resources, and advises the President and Congress on national historic preservation policy. The ACHP is the only agency with the legal responsibility to encourage federal agencies to integrate historic preservation compliance considerations into their project requirements.

4.5.1 ACHP Program Comment

FEMA is required under Section 106 of NHPA to consider the impacts of its grant-funded projects on historic properties. Similarly, the Federal Communications Commission (FCC) is required under NHPA to consider the impacts to historic properties of communications facilities that receive an FCC license to operate. The FCC has executed two nationwide Programmatic Agreements (PA) under NHPA that streamline the Section 106 review process for new tower construction and collocation projects. On October 23, 2009, the ACHP issued a Program Comment for "Streamlining the Section 106 Review for Wireless Communication Facilities Construction and Modification Subject to Review Under the FCC Nationwide Programmatic Agreement and/or the Nationwide Programmatic Agreement for the Collocation of Wireless Antennas." Under the ACHP's Program Comment, FEMA is not required to conduct its own Section 106 review with regard to the effects of communication facilities construction or modification projects that have undergone Section 106 review by the FCC or that are exempt from Section 106 review by the FCC under the FCC Nationwide PA or the FCC Collocation PA. Therefore, the Section 106 review conducted for the proposed project to meet FCC requirements is described in this EA, but no separate 106 review was required for FEMA.

4.5.2 FCC Nationwide Programmatic Agreement

On March 7, 2005 the FCC implemented a Nationwide Programmatic Agreement (NPA) regarding Section 106 reviews (State Historic Preservation Officer and Indian tribal consultation) for wireless telecommunications tower sites. In summary, the NPA set forth rules regarding consultation with the State Historic Preservation Officer (SHPO) in each state where a proposed wireless telecommunications tower is to be constructed; consultation with Indian tribes and Native Hawaiian Organizations (NHOs) that would have been historically located in the area of the proposed wireless telecommunications tower or had indicated an interest in the geographical area containing the proposed wireless telecommunications tower; and involvement of the public and/or local government. As part of the process associated with the NPA the FCC developed the Tower Construction Notification System (TCNS) and FCC Form 620. The TCNS is described in Section 4.5.3 and FCC Form 620 is described in Section 4.5.4.

The NPA requires that a response be received from each Indian tribe or NHO that has indicated an interest in the state or geographical area containing the proposed tower. If no response is received from a particular Indian tribe or NHO within a reasonable time (typically 30 days), the NPA requires that the non-responding Indian tribe or NHO be contacted a second time in an effort to obtain a response. If the Indian tribe or NHO continues to be unresponsive to the initial or follow-up inquiries, the FCC must be contacted to consult with the non-responding Indian tribe or NHO.

4.5.3 FCC Tower Construction Notification System

The TCNS is an Internet-based notification system developed by the FCC that allows input of basic information regarding the proposed location, type, and height of a new wireless telecommunications tower. This information is then made available to Indian tribes and NHOs that have expressed an interest in the state or geographical location containing the proposed wireless telecommunications tower via electronic or regular mail. According to the FCC the TCNS can be used as the initial contact to Indian tribes or NHOs.

Information regarding the proposed wireless telecommunications tower was submitted to Indian tribes, NHOs, and SHPOs via the TCNS on January 5, 2011. The FCC assigned Notification I.D. #72320 to the notification submitted for this proposed wireless telecommunications tower. The FCC sent an electronic mail notification to our office on January 14, 2011 listing the Indian tribes, NHOs, and SHPOs that were contacted through the TCNS regarding the proposed tower. As noted in Section 4.5.2, the NPA requires a response be obtained from each Indian tribe or NHO that has indicated an interest in the geographical area or state containing the site.

Environmental Engineers, Inc. used the list of Indian tribes that had defined their area of geographical interest on the FCC Internet web site, conversations with Tribal Historic Preservation Officers (THPOs), Internet web sites for many of the Indian tribes and Alaskan villages, and the *Encyclopedia of North American Indians* by Frederick E. Hoxie (published in 1996 by Houghton Mifflin) to

determine which Indian tribes included in the TCNS list would be interested in this wireless telecommunications tower site. This review indicated that the following Indian tribes would have a potential interest in this wireless telecommunications tower site: Alabama-Coushatta Tribe of Texas, Chickasaw Nation, Choctaw Nation of Oklahoma, Kialegee Tribal Town, and the Tunica-Biloxi Indians of Louisiana. A description of the follow-ups to and responses from each of these Indian tribes are included in Sections 4.5.5.1 through 4.5.5.5. Copies of the TCNS notifications and list of Indian tribes and SHPOs are included in Appendix G.

4.5.4 State Historic Preservation Officer

MRS Consultants, LLC and Environmental Engineers, Inc. completed the FCC Form 620 required for submittal to the SHPO and to those Indian tribes requesting additional information regarding the proposed wireless telecommunications tower. MRS Consultants, LLC personnel satisfy the United States Secretary of the Interior's Professional Qualification Standards. A copy of the FCC Form 620 prepared for this site is included in Appendix H.

The MDAH site files contained two identified resources in the area surrounding Hickory Flat: Jones Plantation House and Potts (Johnson) Cemetery. The Jones Plantation House is located approximately 1.25 miles northwest of the tower site and was not evaluated. It is unlikely that the tower will have a visual impact on the resource due to the nature of the intermediate distance, topography, and vegetation. The Potts (Johnson) Cemetery is located outside of the APE approximately 1.6 miles northwest of the tower site and was not evaluated. It is unlikely that the tower will have a visual impact on the resource due to the nature of the intermediate distance, topography, and vegetation.

The town of Hickory Flat is located approximately 1.1 miles northeast of the tower site. Due to the relative height of the tower and its proximity to the town, a historic resource assessment was made of the town of Hickory Flat and of the potential visual impact of the proposed tower on identified resources. A reconnaissance level survey was completed of the entire town and did not indicate the presence of a National Register-eligible district. The congested area of Hickory flat consists of several scattered historic resources interspersed with modern buildings and numerous intrusive industrial metal buildings. There is a small commercial core along the railroad. At the east end of the core is a small strip of three commercial buildings. Of three, the westernmost building is relatively intact, the center building has been extensively altered, and the eastern building has a remodeled storefront. Two relatively intact commercial buildings are located at the west end of the core. Of these, the easternmost building is a two-story commercial building dating from circa 1925 that is relatively intact. While this resource is the largest and most prominent building within the commercial district, it does not appear to be individually eligible for the National Register. Immediately west of that building is a small one-story stone veneer commercial building that is been altered with replacement windows at its facade. Between these two groupings of historic commercial buildings, sits a modern industrial metal building that is currently in use as city hall. There is also a small modern frame commercial building to its west and another industrial metal building that serves the fire station to its rear. These intrusive modern buildings destroy any visual continuity that may have existed in the commercial core and result in a collection of buildings that does not appear to be eligible for the National Register as a historic district.

Of the five historic commercial buildings, only two survive without significant alteration. The remainder of the congested portion of town is primarily residential with scattered church buildings. There are a few scattered historic resources, but no intact grouping that would form the basis for a potential historic district. Of the historic residential buildings that remain, most of have been altered with replacement windows, synthetic siding, and other similar alterations. The railroad tracks forms in the southern boundary of the congested portion of town. South of the railroad tracks are three historic residences. Of the three, two have been altered with replacement siding. The third has been altered by the addition of an oversized dormer. Modern residences and manufactured houses are scattered between these three historic houses. None of historic houses appear to be individually eligible for the National Register. The grouping is not visually cohesive and, coupled with the modern buildings and distances between the historic resources, does not appear to be eligible for the National Register.

The FCC Form 620 was submitted to the Mississippi Department of Archives and History (MDAH) for review. Based on the review of this report, the MDAH responded via letter dated January 31, 2011 stating "...we concur that no cultural resources listed or eligible for listing in the National Register of Historic Places will be directly or visually affected. Therefore, we have no reservations with the undertaking." Copies of the correspondence to and from the MDAH are included in Appendix I.

4.5.5 Indian Tribal Consultation

Environmental Engineers, Inc. followed up with each of the Indian tribes identified (as necessary) through a review of the TCNS listing provided by the FCC for this site. Sections 4.5.5.1 through 4.5.5.5 describe follow-up contacts to each of these Indian tribes and their responses.

4.5.5.1 Alabama-Coushatta Tribe of Texas

Mr. Bryant J. Celestine of the Alabama-Coushatta Tribe of Texas provided comment via electronic mail dated January 26, 2011 regarding TCNS #72320 stating that "On behalf of Mikko Oscola Clayton Sylestine and the Alabama-Coushatta Tribe, our appreciation is expressed on your efforts to consult us regarding TCNS #72320 (JSE01P1016) in Benton County...Upon review of your January 5, 2011 submission, no immediately known impacts to religious, cultural, or historical assets of the Alabama-Coushatta Tribe of Texas are anticipated in conjunction with this proposal. In the event of inadvertent discovery of human remains and/or archaeological artifacts, activity in proximity to the location must cease and appropriate authorities, including our office, notified without delay for additional consultation." Copies of the correspondence to and from the Alabama-Coushatta Tribe of Texas are included in Appendix J.

4.5.5.2 Chickasaw Nation

Ms. Virginia Nail of the Chickasaw Nation provided comment via TCNS on March 3, 2011 regarding TCNS #72320 stating "We are unaware of any specific historic properties or traditional cultural, religious and/or sacred sites at this time. However, in the event of inadvertent discoveries, we expect

all construction activities to cease and we be notified according to all applicable state and federal laws.” A copy of the correspondence from the Chickasaw Nation is included in Appendix J.

4.5.5.3 Choctaw Nation of Oklahoma

Ms. Caren Johnson of the Choctaw Nation of Oklahoma provided comment via electronic mail on January 13, 2011 stating that “The Choctaw Nation of Oklahoma has reviewed cell tower(s) FCC # 72320 and based on the information provided to the best of our knowledge it will have no adverse effect on any historic properties in the project’s area of potential effect. However, should construction expose buried archaeological or building materials such as chipped stone, tools, pottery, bone, historic crockery, glass or metal items, or should it uncover evidence of buried historic building materials such as rock foundations, brick, or hand poured concrete, this office should be contacted immediately.” Copies of the correspondence to and from the Choctaw Nation of Oklahoma are included in Appendix J.

4.5.5.4 Kialegee Tribal Town

The TCNS listing (Appendix G) for this site included information from the Kialegee Tribal Town that states “If the Applicant receives no response from the Kialegee Tribal Town within 30 days after notification through TCNS, the Kialegee Tribal Town has no interest in participating in pre-construction review for the site. The Applicant, however, must immediately notify the Kialegee Tribal Town in the event archaeological properties or human remains are discovered during construction.” The TCNS notification for this site is dated January 14, 2011 and the end of the 30-day period indicated by the Kialegee Tribal Town was February 13, 2011. Environmental Engineers, Inc. has not received a response from the Kialegee Tribal Town as of the date of this report. Therefore, it is our understanding that additional consultation with the Kialegee Tribal Town is not necessary.

4.5.5.5 Tunica-Biloxi Indians of Louisiana

Mr. Earl Barbry of the Tunica-Biloxi Indians of Louisiana was contacted via electronic mail on May 3, 2005 regarding submittal of wireless telecommunications projects. Mr. Barbry responded via electronic mail on May 3, 2005 and indicated that he wanted to be notified regarding cell tower requests via electronic mail and that if he had not responded within 30 days of our contacting him, the project can proceed. Mr. Barbry was contacted regarding this site via electronic mail on January 5, 2011, and the end of the 30-day response period was February 4, 2011. No response from has been received from Mr. Barbry as of the date of this draft EA. Copies of the electronic mail to and from Mr. Barbry are included in Appendix J.

Based on the information presented above, the proposed communications facility would have no impact on cultural resources.

4.5.6 Inadvertent Discovery

The personnel that would have a potential to be involved in land-disturbing activities must be instructed to stop work immediately in the event of an inadvertent discovery of human remains or cultural or archaeological materials and contact FEMA and SHPO. A copy of this information must be provided to all personnel that would have a potential to be involved in land-disturbing activities at the site.

4.6 SOCIOECONOMIC CONCERNS

Under the no action alternative there would be no impact to socioeconomic resources.

No significant adverse impacts to socioeconomic resources, economic development, demographics, demand for public housing, or public services are anticipated. The emergency communications coverage provided by this project would benefit all populations in the coverage area.

4.6.1 Human Health and Safety

Under the no action alternative, there could be adverse impacts to human health and safety because of a lack of adequate communication between emergency response personnel during an emergency event.

The results of a Phase I Environmental Site Assessment (ESA) conducted at the site by EEI for the MSWIN 30410 communications tower site in November 2010 (EEI Project No.: JSE01P1016) did not indicate the presence of hazardous materials or petroleum products at the site at that time. The equipment (including the emergency generator and associated propane/natural gas tank) that would be installed at the site would meet local, state, and federal regulations regarding hazardous materials. The Phase I ESA is included in Appendix K. The antennae and equipment that would be installed at the site would meet local, state, and federal regulations regarding radiofrequency emissions. Lastly, this project is intended to provide better communications between emergency response personnel which would have a beneficial effect on human health and safety. Therefore, the proposed communications facility would have no significant impacts to human health and safety.

4.6.2 Environmental Justice

Section 1-101 of EO 12898 states “To the greatest extent practicable and permitted by law, and consistent with the principles set forth in the report on the National Performance Review, each Federal agency shall make achieving environmental justice part of its mission by identifying and addressing, as appropriate, disproportionately high and adverse human health or environmental effects of its programs, policies, and activities on minority populations and low-income populations in the United States and its territories and possessions, the District of Columbia, the Commonwealth of Puerto Rico, and the Commonwealth of the Mariana Islands.”

Under the no action alternative there would be no impact to minority or low income populations.

No disproportionately high or adverse effects on minority or low-income populations are anticipated by development of the proposed communications facility. The proposed communications facility would benefit all populations in the project service area by providing better communications between emergency service personnel.

4.6.3 Noise

Noise is generally described as unwanted sound. Sound becomes unwanted when it either interferes with normal activities such as sleeping, conversation, or disrupts or diminishes one's quality of life.

Under the no action alternative there would be no noise generation.

Short-term noise generation is anticipated to result from grading and construction activities. Long-term noise generation is anticipated to be minimal and to result primarily from equipment used to cool electronic components and from testing or operation of an emergency generator at the site. However, the generator would only operate briefly when tested, and during power failure events affecting the electrical power supply to the site. Therefore, the proposed communications facility would not generate significant noise.

4.6.4 Infrastructure, Utilities, Transportation, and Waste Management

Under the no action alternative there would be no impact to infrastructure, utilities, transportation, or waste management.

No significant impacts are anticipated to infrastructure, utilities, transportation, or waste management from the proposed communications facility. Traffic to and from the site would be minimal and would be associated with maintenance and repair of equipment at the site. Minimal waste would be generated at the site during maintenance activities. All waste generated at the site would be disposed of in compliance with federal, state, and local regulations. The project is intended to provide enhanced communications services for emergency response personnel. This could have a beneficial effect on the ability to identify and correct problems with infrastructure, utilities, transportation, and waste management.

4.6.5 Aesthetics and Visual Impacts

Under the no action alternative there would be no aesthetic or visual impacts.

The proposed project will not impact national scenic or historic trails. There are no national scenic or historic trails located in Benton County, Mississippi.

The proposed tower would not be equipped with high intensity white lighting.

Lastly, the site is not located within the boundaries of any state or national park, national forest, or wildlife management area. No city or other community parks are depicted within 1,000 feet of the proposed project on the USGS Topographic Quadrangle “Hickory Flat, Mississippi,” (Figure 3). Therefore, the proposed communications facility would have no significant impacts to aesthetics and visual resources.

4.7 CUMULATIVE IMPACTS

Under the no action alternative there would be no cumulative impacts.

Cumulative impacts are an incremental impact on either the natural environment or human environment by an action when added to past and anticipated future actions. No ongoing or proposed actions are known for the project area. According to information available through the FCC Antenna Structure Registration (ASR) System Internet website, there are 3,313 registered towers in the state of Mississippi (generally only those towers over 200 feet in height are included in this database). Construction of the towers comprising the MSWIN network would result in an increase of approximately 4.25% in the number of towers in the state of Mississippi. As described in Section 1.0 of this document, the proposed tower is designed to allow collocation of up to three additional cellular-type service providers, thereby potentially reducing cumulative impacts as new/changing technologies and increased demand for service, both public and private, create more pressure on existing infrastructure.

The statewide MSWIN program would not have cumulative impacts on geology, air quality, noise, water resources, cultural resources, fish and wildlife, threatened or endangered species, vegetation, or socioeconomics. However, cumulative impacts to migratory birds may result from the MSWIN program, as birds could be injured or killed by colliding into guy wires and/or the tower structure, or could be disoriented by the tower lighting. FEMA has worked with MWCC and MDWFP to develop an Avian Mitigation Plan (Appendix F) to address this potential for cumulative impacts to birds.

The mitigation includes monitoring the presence of deceased birds at MSWIN tower sites and providing a collection kit on site to collect the remains and record the location of any deceased bird. The remains of the bird along with the data will be delivered to the MDWFP and included in the state’s Avian Mortality database. USFWS will also have access to this database. If an injured bird is found, all efforts will be made to help the bird recover so that it can be released back into the wild. In addition, MDWFP and USFWS (Jackson, MS Ecological Services office) will be given access to the MSWIN tower sites for monitoring. If a particular tower is found to have adverse effects to migratory birds (greater than 10 kills per night) the towers will be reported to MDWFP, USFWS, and FEMA. MWCC will also provide an annual report documenting the number of avian deaths and provide that report to FEMA, USFWS (Jackson, MS Ecological Services office), and MDWFP for five years after all towers have been constructed. This mitigation plan will contribute scientific data that can be used by MDWFP and USFWS in determining the significance of potential impacts of towers on migratory birds. The implementation of the Avian Mitigation Plan will lower the potential for the MSWIN program to have adverse cumulative impacts on migratory birds.

Table 1. Summary of Impacts				
Resource	No Impact	No Significant Impact	Significant Impact	Mitigation/Best Management Practices
Geology		X		None
Prime/unique farmland; farmland of statewide or local importance	X			None
Air Quality		X		Fugitive dust emissions from construction activities would be controlled by wetting the ground
Wild and Scenic Rivers	X			None
Water Quality		X		Examples of BMPs that may be used during construction activities include, but are not limited to, silt fence, hay or straw bales, hay or straw mulch, gravel, erosion control blankets, and riprap
Wetlands	X			None
Floodplains	X			None
Coastal Resources	X			None
Threatened and Endangered Species	X			None
Migratory Birds		X		Avian Mitigation Plan will be implemented; Tower lighting would be in accordance with USFWS recommendations; and tower design would allow for future collocation
Wildlife and Fish	X			None
General Vegetation		X		None
Cultural Resources		X		If any human remains or cultural or archaeological materials are discovered, grantee would stop work immediately and contact FEMA and SHPO.
Socioeconomic Resources		X		None
Human Health and Safety		X		None – project would improve interoperable communications
Environmental Justice	X			None – project would benefit all communities
Noise		X		None
Infrastructure, Utilities, Transportation, and Waste Management		X		None
Aesthetics and Visual Impacts		X		None

5.0 AGENCY COORDINATION, PUBLIC INVOLVEMENT AND PERMITS

The Benton County Chancery Clerk was contacted regarding the proposed wireless communications tower via letter dated November 23, 2010. No response has been received from the Benton County Chancery Clerk as of the date of this report. A public notice was published in the *Ripley Southern Sentinel* on November 11, 2010 requesting comment regarding potential impacts to historical or archaeological properties by the proposed wireless communications tower. No comments have been received as of the date of this report in response to the public notice. A copy of the correspondence submitted to the Benton County Chancery Clerk and a copy of the public notice are included in Appendix L. In addition, notice of availability of this draft Environmental Assessment will be published in *The Clarion Ledger*.

6.0 LIST OF PREPARERS

- Chad Stinnett, Environmental Engineers, Inc.
- Henry A. Fisher, Environmental Engineers, Inc.
- Jennifer Hirsch, FEMA
- Laura Shick, FEMA


7.0 INFORMATION SOURCES

Completion of this Draft Environmental Assessment included utilization of the following sources:

1. Review of the portion of the 2009 aerial photograph depicting the site location available through Maptech.
2. Review of the site survey prepared by SMW Engineering, Inc.
3. Review of information regarding National Scenic Trails and All-American Roads available on the Mississippi Department of Transportation Internet website.
4. State and county maps available through the Mississippi Department of Transportation Internet website.
5. Review of information regarding wild and scenic rivers in the vicinity of the proposed project available at Rivers.gov.
6. Review of the Nationwide Programmatic Agreement for Review of Effects on Historic Properties for Certain Undertakings Approved by the Federal Communications Commission.

7. Correspondence to and from the United States Army Corps of Engineers regarding potential impacts to jurisdictional wetlands by the proposed project.
8. Review of information available on the USFWS National Wetlands Inventory Internet website regarding potential jurisdictional wetlands on or adjacent to the site.
9. A review of information available on the USFWS Internet website, at Nationalatlas.gov, and on Wilderness.net regarding officially designated wilderness areas or wildlife refuges.
10. Correspondence from the USFWS regarding threatened and endangered species on or near the site.
11. Review of the FCC Form 620 prepared for the site by MRS Consultants, LLC and Environmental Engineers, Inc.
12. Correspondence from the Mississippi Department of Archives and History regarding historical resources and properties listed on or eligible for listing on the National Register of Historic Places on or near the site.
13. Review of the Tower Construction Notification System Notice of Organizations Which Were Sent Proposed Tower Construction Notification Information provided by the FCC.
14. Correspondence and conversations with representatives of the Alabama-Coushatta Tribe of Texas, Chickasaw Nation, Choctaw Nation of Oklahoma, Kialegee Tribal Town, and the Tunica-Biloxi Indians of Louisiana regarding wireless telecommunications projects.
15. Review of the portion of the FEMA Flood Insurance Rate Map depicting the site location regarding flood zone designations for the site.
16. Information regarding the MSWIN system provided by Towers of Mississippi.
17. Soil information from the USDA's Soil Survey of Benton County, Mississippi, issued January 1977.
18. Correspondence to and from the USDA Natural Resource Conservation Service (NRCS) office in Jackson, Mississippi regarding impacts to prime farmland, unique farmland, and land of statewide or local importance.
19. A reconnaissance of the subject property.

Figures



Environmental Engineers, Inc.

Subject:
 MSWIN 30410 C Hickory Flat Communications Facility
 Hickory Flat, Benton County, Mississippi
 Environmental Engineers, Inc. Project No.: JSE01P1016

Figure 3
 Site Location Map
 Scale: 1" ≈ 2000'





Environmental Engineers, Inc.

Subject:
MSWIN 30410 C Hickory Flat Communications Facility
Hickory Flat, Benton County, Mississippi
Environmental Engineers, Inc. Project No.: JSE01P1016

Figure 4
2009 Aerial Photograph





View from the center of the site looking toward the north.



View from the center of the site looking toward the east.

Environmental Engineers, Inc.

Subject:
MSWIN 30410 C Hickory Flat Communications Tower
Hickory Flat, Benton County, Mississippi
Project No.: JSE01P1016

Figure 5
Site Photographs





View from the center of the site looking toward the south.



View from the center of the site looking toward the west.

Environmental Engineers, Inc.

Subject:
MSWIN 30410 C Hickory Flat Communications Tower
Hickory Flat, Benton County, Mississippi
Project No.: JSE01P1016

Figure 6
Site Photographs





View from the northern guy anchor looking toward the site.



View from the southwestern guy anchor looking toward the site.

Environmental Engineers, Inc.

Subject:
MSWIN 30410 C Hickory Flat Communications Tower
Hickory Flat, Benton County, Mississippi
Project No.: JSE01P1016

Figure 7
Site Photographs





Overall view across the site looking toward the east.



View of the existing access road looking east from the site.

Environmental Engineers, Inc.

Subject:
MSWIN 30410 C Hickory Flat Communications Tower
Hickory Flat, Benton County, Mississippi
Project No.: JSE01P1016

Figure 8
Site Photographs





View of the existing access road looking west toward the site.



View of the empty 55-gallon drum on the site.

Environmental Engineers, Inc.

Subject:
MSWIN 30410 C Hickory Flat Communications Tower
Hickory Flat, Benton County, Mississippi
Project No.: JSE01P1016

Figure 9
Site Photographs





U.S. Fish and Wildlife Service

National Wetlands Inventory

MSWIN 30410 C
Hickory Flat

Mar 4, 2011



Wetlands

- Freshwater Emergent
- Freshwater Forested/Shrub
- Estuarine and Marine Deepwater
- Estuarine and Marine
- Freshwater Pond
- Lake
- Riverine
- Other

Status

- Digital
- Scan
- Non-Digital
- No Data

This map is for general reference only. The US Fish and Wildlife Service is not responsible for the accuracy or currentness of the base data shown on this map. All wetlands related data should be used in accordance with the layer metadata found on the Wetlands Mapper web site.

User Remarks:

Figure 10 - National Wetlands Inventory Map


MSWIN 30410 C Hickory Flat

Insurance Program at 1-800-638-6620.



MAP SCALE 1" = 1000'

0 500 1 000 1 500 2 000



PANEL 0255B

FIRM
FLOOD INSURANCE RATE MAP
BENTON COUNTY,
MISSISSIPPI
AND INCORPORATED AREAS

PANEL 255 OF 280
 (SEE MAP INDEX FOR FIRM PANEL LAYOUT)

CONTAINS

COMMUNITY	NUMBER	PANEL	SUFFIX
BENTON COUNTY	280004	0155	B
HICKORY FLAT TOWN OF	280010	0155	B

Notice to User: The Map Number shown below should be used when placing map orders; the Community Number shown above should be used on insurance applications for the subject community.

MAP NUMBER
28009C0255B



EFFECTIVE DATE
OCTOBER 2, 2008




Federal Emergency Management Agency

This is an official copy of a portion of the above referenced flood map. It was extracted using F-MIT On-Line. This map does not reflect changes or amendments which may have been made subsequent to the date on the title block. For the latest product information about National Flood Insurance Program flood maps check the FEMA Flood Map Store at www.msc.fema.gov

Figure 11 - Flood Insurance Rate Map

MSWIN 30410 C Hickory Flat

Appendix A



SURVEYOR'S NOTES

- The Rawland Tower Survey, made on the ground under the supervision of a Mississippi Registered Land Surveyor, Date of field survey is September 9, 2010.
- The following surveying instruments were used: Line of field work, Nikon WP-35Z, Total Station, Leica 560, and Topcon GTS-102.
- Reference to the Mississippi Code, Title 49, Chapter 27, Section 27-1-1, regarding the use of GPS observations as a part of this survey, unless otherwise shown. Triangulation stations, unless otherwise shown, are not shown on this map.
- Reference to the Mississippi Code, Title 49, Chapter 27, Section 27-1-1, regarding the use of GPS observations as a part of this survey, unless otherwise shown. Triangulation stations, unless otherwise shown, are not shown on this map.
- Attention is directed to the fact that this survey may have been reduced or enlarged in size due to the fact that the survey was made on a scale of 1" = 100'.
- The survey was conducted without the benefit of an absolute elevation datum.
- Surveyor hereby states the graphic scale and the elevation shown for the proposed easements of the survey are accurate to within +/- 15 feet, horizontally and to within +/- 3 feet vertically (FAA Accuracy Code 1A).
- Surveyor states herein conforming to the Minimum Requirements as set forth by the State Board for a Professional Surveyor, Mississippi Code, Title 49, Chapter 27, Section 27-1-1.
- Field data upon which this map or plot is based has a closure precision of not less than one-foot in 15,000 feet (1:15,000) and an angular error that does not exceed 10 seconds unless the square root of the number of angles turned. Field traverse was not adjusted.
- This survey is not valid without the original signature and the original seal of a state licensed surveyor.
- This survey does not constitute a complete boundary survey of the Parent Tract.

LINE	BEARING	DISTANCE	LINE	BEARING	DISTANCE
1	S 37°19'14" W	36.01'	10	S 60°37'52" E	29.55'
2	S 39°28'04" E	49.14'	11	N 65°36'39" E	86.63'
3	S 53°01'22" E	78.49'	12	S 81°14'26" E	54.44'
4	S 45°47'48" E	105.06'	13	S 74°02'41" E	118.01'
5	S 44°47'12" E	141.44'	14	S 75°20'11" E	132.59'
6	S 37°27'30" E	73.03'	15	S 70°02'33" E	70.83'
7	S 05°18'28" E	112.91'	16	S 62°59'20" E	85.41'
8	S 00°31'11" W	97.24'	17	S 58°00'37" E	79.35'
9	S 09°57'53" E	99.68'	18	S 53°23'18" E	113.07'



MISSISSIPPI GRID - NORTH
 GO TO TRUE NORTH
 CONVERGENCE
 TRUE NORTH TO
 MAGNETIC DECLINATION
 GPS SCALE FACTOR
 CONVERSIONS

LEGEND

- = 5/8" CORRODED REBAR SET
- = FOUND PROPERTY MARKER
- = SET BY NAME
- = POINT OF BEGINNING
- = POINT OF COMMENCEMENT
- = POINT OF ENDING
- = CALCULATED POINT
- = RECORDED INFORMATION
- = POWER POLE
- = QUIET ANCHOR
- = POWER BOX
- = TELEPHONE FEEDSTAP
- = RIGHT-OF-WAY
- = OVERHEAD POWER

HICKORY FLAT MS
 10-0731
 NW 1/4, SEC. 32, T. 1-S, R. 1-E
 BENTON COUNTY, MISSISSIPPI

SMW Engineering Group, Inc.
 1550 Woods of Riverchase Drive
 Suite 100
 Hoover, Alabama 35244
 Ph: 205-252-8865
 www.smweng.com

RAWLAND TOWER SURVEY
ENVIRONMENTAL ENGINEERS
 11578 U.S. HIGHWAY 411
 ODESSA, AL 35220

NO.	REVISION	DATE	BY

DRAWN BY: CE
 CHECKED BY: ANK
 FIELD CREW: MS
 APPROVED BY: ANK
 DATE: 11/05/2010
 SCALE: AS SHOWN
 SHEET 2 OF 3

Appendix B



ENVIRONMENTAL ENGINEERS, INC.

11578 US Highway 411, Odenville, Alabama 35120

Environmental, Remediation, and Geological Consultants

January 5, 2011

Dr. Homer L. Wilkes, State Conservationist
U.S. Department of Agriculture, Natural Resources Conservation Service
100 W. Capital Street
Suite 1321 Federal Building
Jackson, MS 39269

Subject:

Request for Project Review
Proposed MSWIN 30410 C Telecommunications Tower
Hickory Flat, Benton County, Mississippi
Environmental Engineers, Inc. Project No.: JSE01P1016

Dear Dr. Wilkes:

Environmental Engineers, Inc. is requesting comment on behalf of Towers of Mississippi, the State of Mississippi, and the Federal Emergency Management Agency (FEMA) regarding construction of a wireless communications tower in Benton County, Mississippi. This project is being funded using a FEMA grant (2008-MS-MX-0001) and the State of Mississippi's expenditures at this site will include construction of a telecommunications facility, purchase and installation of 700 MHz RF equipment and microwave telecommunication backbone network, equipment shelter, network integration, acceptance testing, communication hardware optimization and system exercising and piloting of interoperability capabilities of the network.

The site is depicted on the United States Geological Survey 7.5-minute Topographic Quadrangle "Hickory Flat, Mississippi," dated 1982. The site is located in the southwest $\frac{1}{4}$ of the northwest $\frac{1}{4}$ of Section 33, Township 5 South, Range 1 East, Benton County, Mississippi, at latitude $34^{\circ} 36' 27.350''$ north and longitude $89^{\circ} 12' 27.761''$ west (Figure 1). The site consists of a proposed 100-foot by 100-foot lease area with three associated guy anchor easements, and a proposed access road located off of Cornersville Road in Hickory Flat, Mississippi 38633. The site consists of land covered in scrub vegetation with a few scattered hardwood saplings up to three inches in diameter at breast height (dbh), and the site slopes moderately down to the west. The proposed facility access road follows an existing gravel road and extends west from Cornersville Road for approximately 1,300 feet. Proposed activities consist of construction of a 450-foot guyed communications tower and associated compound, enclosing the compound in a fence, placement of support equipment within the compound, improving the access road, and covering the compound and access road with gravel. The proposed project is depicted on the Flood Insurance Rate Map No. 28009C0255B which bears an effective date of October 2, 2008 and is not in a special flood hazard area. I have included a site location map, site photographs, and the portion of the 2009 aerial photograph depicting the site for your review.

Phone: (205) 629-3868 • Fax: (877) 847-3060

Environmental Engineers, Inc. has been retained by Towers of Mississippi and the State of Mississippi to prepare an Environmental Assessment (EA) for the proposed project. Please reference the Environmental Engineers, Inc. project number (JSE01P1016) in correspondence regarding this site. Thank you for your time and assistance and we look forward to your response. Please contact me by telephone at (205) 629-3868, electronic mail at hfisher@envciv.com, or U.S. mail at the letterhead address if you have any questions or comments.

Sincerely,

ENVIRONMENTAL ENGINEERS, INC.

A handwritten signature in black ink, appearing to read 'H. Fisher', with a horizontal line extending to the right.

Henry A. Fisher, P.E.
Principal Engineer

Attachments Site Location Map, Site Photographs, Aerial Photograph



[Home](#) | [Help](#) | [Sign In](#)

[Track & Confirm](#)

[FAQs](#)

Track & Confirm

Search Results

Label/Receipt Number: **7010 0290 0003 5707 9596**
Service(s): **Certified Mail™**
Status: **Delivered**

[Track & Confirm](#)

Enter Label/Receipt Number.

Your item was delivered at 9:02 am on January 11, 2011 in JACKSON, MS 39269.

[Go >](#)

Detailed Results:

- Delivered, January 11, 2011, 9:02 am, JACKSON, MS 39269
- Notice Left, January 11, 2011, 9:01 am, JACKSON, MS 39269
- Arrival at Unit, January 11, 2011, 9:00 am, JACKSON, MS 39269

Notification Options

Track & Confirm by email

Get current event information or updates for your item sent to you or others by email.

[Go >](#)

[Site Map](#) | [Customer Service](#) | [Forms](#) | [Gov't Services](#) | [Careers](#) | [Privacy Policy](#) | [Terms of Use](#) | [Business Customer Gateway](#)

Copyright© 2010 USPS. All Rights Reserved. No FEAR Act EEO Data FOIA



U.S. Postal Service
1100 Pennsylvania Avenue, N.W.
Washington, D.C. 20503



U.S. Postal Service
1100 Pennsylvania Avenue, N.W.
Washington, D.C. 20503

7010 0290 0003 5707 9596

U.S. Postal Service
CERTIFIED MAIL RECEIPT
(Domestic Mail Only; No Insurance Coverage Provided)

For delivery information visit our website at www.usps.com

OFFICIAL USE

Postage	\$	1/6/11 Postmark Here
Certified Fee		
Return Receipt Fee (Endorsement Required)		
Restricted Delivery Fee (Endorsement Required)		
Total Postage & Fees	\$6.32	JSE01P016

Sent to: Dr. Herman A. Wilkes,
Street, Apt. No., or PO Box No. _____
City, State, ZIP+4 _____

US Form 3800, August 2006 See Reverse for Instructions

United States Department of Agriculture



Natural Resources Conservation Service
Suite 1321, Federal Building
100 West Capitol Street
Jackson, MS 39269

JSE01P1016

January 18, 2011

Environmental Engineers Inc.

JAN 27 2011

RECEIVED

Henry A. Fisher, P.E.
Principal Engineer
Environmental Engineers, Inc.
11578 US Highway 411
Odenville, AL 35120

Dear Mr. Fisher:

This is in response to your letter dated January 5, 2011, regarding the Request for Project Review Proposed MSWIN 30410 C Telecommunications Tower in Hickory Flat in Benton County, Mississippi.

The site will not be permanently converted, therefore no FPPA prime farmland determination is required.

Sincerely,

A handwritten signature in black ink, appearing to read "Delaney B. Johnson".

Delaney B. Johnson
State Soil Scientist

Appendix C



ENVIRONMENTAL ENGINEERS, INC.

11578 US Highway 411, Odenville, Alabama 35120

Environmental, Remediation, and Geological Consultants

January 5, 2011

Mr. David Lofton
U.S. Army Corps of Engineers/Regulatory Division
Vicksburg District
4155 East Clay Street
Vicksburg, MS 39183

Subject:

Request for Project Review
Proposed MSWIN 30410 C Communications Tower
Hickory Flat, Benton County, Mississippi
Environmental Engineers, Inc. Project No.: JSE01P1016

Dear Mr. Lofton:

Environmental Engineers, Inc. is requesting comment on behalf of Towers of Mississippi, the State of Mississippi, and the Federal Emergency Management Agency (FEMA) regarding construction of a wireless communications tower in Benton County, Mississippi. This project is being funded using a FEMA grant (2008-MS-MX-0001) and the State of Mississippi's expenditures at this site will include construction of a telecommunications facility, purchase and installation of 700 MHz RF equipment and microwave telecommunication backbone network, equipment shelter, network integration, acceptance testing, communication hardware optimization and system exercising and piloting of interoperability capabilities of the network.

The site is depicted on the United States Geological Survey 7.5-minute Topographic Quadrangle "Hickory Flat, Mississippi," dated 1982. The site is located in the southwest $\frac{1}{4}$ of the northwest $\frac{1}{4}$ of Section 33, Township 5 South, Range 1 East, Benton County, Mississippi, at latitude $34^{\circ} 36' 27.350''$ north and longitude $89^{\circ} 12' 27.761''$ west (Figure 1). The site consists of a proposed 100-foot by 100-foot lease area with three associated guy anchor easements, and a proposed access road located off of Cornersville Road in Hickory Flat, Mississippi 38633. The site consists of land covered in scrub vegetation with a few scattered hardwood saplings up to three inches in diameter at breast height (dbh), and the site slopes moderately down to the west. The proposed facility access road follows an existing gravel road and extends west from Cornersville Road for approximately 1,300 feet. Proposed activities consist of construction of a 450-foot guyed communications tower and associated compound, enclosing the compound in a fence, placement of support equipment within the compound, improving the access road, and covering the compound and access road with gravel. The proposed project is depicted on the Flood Insurance Rate Map No. 28009C0255B which bears an effective date of October 2, 2008 and is not in a special flood hazard area. I have included a site location map, site photographs, and the portion of the 2009 aerial photograph depicting the site for your review.

Phone: (205) 629-3868 • Fax: (877) 847-3060

Environmental Engineers, Inc. has been retained by Towers of Mississippi and the State of Mississippi to prepare an Environmental Assessment (EA) for the proposed project. Please reference the Environmental Engineers, Inc. project number (JSE01P1016) in correspondence regarding this site. Thank you for your time and assistance and we look forward to your response. Please contact me by telephone at (205) 629-3868, electronic mail at hfisher@envciv.com, or U.S. mail at the letterhead address if you have any questions or comments.

Sincerely,

ENVIRONMENTAL ENGINEERS, INC.

A handwritten signature in black ink, appearing to read 'H. Fisher', with a long horizontal stroke extending to the right.

Henry A. Fisher, P.E.
Principal Engineer

Attachments Site Location Map, Site Photographs, Aerial Photograph

7010 0290 0003 5707 9602

U.S. Postal Service
CERTIFIED MAIL RECEIPT
(Domestic Mail Only. No Insurance Coverage Provided)

For delivery information visit our website at www.usps.com

OFFICIAL USE

Postage	\$	1/6/11 Postmark Here
Certified Fee		
Return Receipt Fee (Endorsement Required)		
Restricted Delivery Fee (Endorsement Required)		
Total Postage & Fees	\$10.32	JSE01P1016

Sent To: Mr. David Lofton
 Street, Apt. No., or PO Box No.
 City, State, ZIP+4

PS Form 3800, August 2005 See Reverse for Instructions

SENDER: COMPLETE THIS SECTION	COMPLETE THIS SECTION ON DELIVERY
<ul style="list-style-type: none"> Complete items 1, 2, and 3. Also complete item 4 if Restricted Delivery is desired. Print your name and address on the reverse so that we can return the card to you. Attach this card to the back of the mailpiece, or on the front if space permits. 	<p>A. Signature x Brenda Clack <input checked="" type="checkbox"/> Agent <input type="checkbox"/> Addressee</p> <p>B. Received by (Printed Name) B. CLACK</p> <p>C. Date of Delivery 1/10/11</p> <p>D. Is delivery address different from item 1? <input type="checkbox"/> Yes If YES, enter delivery address below: <input type="checkbox"/> No</p>
<p>1. Article Addressed to: Mr. David Lofton U.S. Army Corps of Engineers Regulatory Division/Vicksburg 4155 Reacht Clay Street Vicksburg, MS 39183</p>	<p>3. Service Type <input checked="" type="checkbox"/> Certified Mail <input type="checkbox"/> Express Mail <input type="checkbox"/> Registered <input type="checkbox"/> Return Receipt for Merchandise <input type="checkbox"/> Insured Mail <input type="checkbox"/> C.O.D.</p> <p>4. Restricted Delivery? (Extra Fee) <input type="checkbox"/> Yes</p>
<p>2. Article Number (Transfer from service label)</p>	<p>7010 0290 0003 5707 9602</p>



DEPARTMENT OF THE ARMY

VICKSBURG DISTRICT, CORPS OF ENGINEERS

4155 CLAY STREET

VICKSBURG, MISSISSIPPI 39183-3435

REPLY TO
ATTENTION OF:

January 12, 2011

Operations Division

SUBJECT: Towers of Mississippi, Request for Project Review for Proposed MSWIN 30410 C Communications Tower in Section 33, Township 5 South, Range 1 East, Benton County, Mississippi

Mr. Taylor Robinson
Towers of Mississippi
31560 Blakely Way
Spanish Fort, Alabama 36532

Dear Mr. Robinson:

This is in response to the January 5, 2011 letter from Mr. Henry A. Fisher, P.E., of Environmental Engineers, Incorporated, concerning possible regulatory requirements for the proposed construction of a telecommunications facility and associated equipment and access road adjacent to Cornersville Road in Hickory Flat, Benton County, Mississippi.

Based upon the information provided (enclosure 1), it appears that a Department of the Army permit, pursuant to Section 10 of the Rivers and Harbors Act of 1899 and Section 404 of the Clean Water Act, will not be required for the proposed work. In the event that project plans are changed, or if you anticipate any additional construction, please contact this office for a reevaluation of permit requirements and refer to identification no. MVK-2011-42 when submitting the information.

This determination of Department of the Army regulatory requirements was based upon a preliminary jurisdictional determination that there are no jurisdictional areas being impacted by the proposed work on the property subject to regulation pursuant to Section 10 of the Rivers and Harbors Act of 1899 and/or to Section 404 of the Clean Water Act. An appeals form for this preliminary jurisdictional determination has been enclosed for your review (enclosure 2).


This determination of Department of the Army regulatory requirements does not convey any property rights, either in real estate or material or any exclusive privileges, and does not authorize any injury to property or invasion of rights or local laws or regulations, or obviate the requirement to obtain State or local assent required by law for the activity discussed herein.

The Vicksburg District Regulatory Branch is committed to providing quality and timely service to our customers. In an effort to improve customer service, please take a moment to complete the Customer Service Survey found on our web site at <http://per2.nwp.usace.army.mil/survey.html>. If it is more convenient for you, please complete and return the enclosed postage-paid postcard (enclosure 3).

If we may be of any further assistance in this matter, please contact Ms. Jana Guynes of this office, telephone (601) 631-7136, fax (601) 631-5459, or e-mail address: regulatory@usace.army.mil.

I am forwarding a copy of this letter to Mr. Henry Fisher, P.E., Environmental Engineers, Incorporated, 11578 US Highway 411 Odenville, Alabama 35120.

Sincerely,



David Lofton
Chief, Permit Section
Regulatory Branch

Enclosures

Appendix D



ENVIRONMENTAL ENGINEERS, INC.

11578 US Highway 411, Odenville, Alabama 35120

Environmental, Remediation, and Geological Consultants

November 23, 2010

Mr. Stephen Ricks
United States Fish and Wildlife Service
6578 Dogwood View Parkway
Jackson, Mississippi 39213

Subject:

Proposed MSWIN 30410 C Hickory Flat Communications Facility

Hickory Flat, Benton County, Mississippi

Environmental Engineers, Inc. Project No.: JSE01P1016

Dear Mr. Ricks:

Environmental Engineers, Inc. is requesting comment from the U.S. Fish and Wildlife Service on behalf of Towers of Mississippi, the State of Mississippi, and the Federal Emergency Management Agency regarding impact to threatened or endangered species by construction of a wireless communications tower in Benton County, Mississippi.

The site is depicted on the United States Geological Survey 7.5-minute Topographic Quadrangle "Hickory Flat, Mississippi," dated 1982. The site is located in the southwest $\frac{1}{4}$ of the northwest $\frac{1}{4}$ of Section 33, Township 5 South, Range 1 East, Benton County, Mississippi, at latitude $34^{\circ} 36' 27.350''$ north and longitude $89^{\circ} 12' 27.761''$ west (Figure 1). The site consists of a proposed 100-foot by 100-foot lease area with three associated guy anchor easements, and a proposed access road located off of Cornersville Road in Hickory Flat, Mississippi 38633. The site consists of land covered in scrub vegetation with a few scattered hardwood saplings up to three inches in diameter at breast height (dbh), and the site slopes moderately down to the west. The proposed facility access road follows an existing gravel road and extends west from Cornersville Road for approximately 1,300 feet. Proposed activities consist of construction of a 450-foot guyed communications tower and associated compound, enclosing the compound in a fence, placement of support equipment within the compound, and covering the compound with gravel. I have included a site location map, site photographs, and the portion of the 2009 aerial photograph depicting the site for your review.

Environmental Engineers, Inc. appreciates the opportunity to provide this information. Please reference the Environmental Engineers, Inc. project number (JSE01P1016) in correspondence regarding this site. Thank you for your time and assistance and we look forward to your response. Please call us at (205) 629-3868 if you have any questions or comments.

Sincerely,

ENVIRONMENTAL ENGINEERS, INC.

Chad Stinnett
Senior Project Scientist

Attachments Site Location Map, Site Photographs, and 2009 Aerial Photograph

Phone: (205) 629-3868 • Fax: (877) 847-3060

7010 0290 0003 5707 7776

U.S. Postal Service
CERTIFIED MAIL RECEIPT
(Domestic Mail Only; No Insurance Coverage Provided)

For delivery information visit our website at www.usps.com

OFFICIAL USE

Postage	\$	11/23/10 Postmark Here JSEAIP1A11K JSEAIP1A136
Certified Fee		
Return Receipt Fee (Endorsement Required)		
Restricted Delivery Fee (Endorsement Required)		
Total Postage & Fees	\$6.49	

Sent To Mr. Stephen Ricks
 Street, Apt. No., or PO Box No.
 City, State, ZIP+4

PS Form 3811, August 2006 See Reverse for Instructions

SENDER: COMPLETE THIS SECTION

- Complete Items 1, 2, and 3. Also complete item 4 if Restricted Delivery is desired.
- Print your name and address on the reverse so that we can return the card to you.
- Attach this card to the back of the mailpiece, or on the front if space permits.

1. Article Addressed to:
Mr. Stephen Ricks
USF&NS
6578 Dogwood View Place
Jackson, MS 39213

2. Article Number
 (Transfer from service label)

COMPLETE THIS SECTION ON DELIVERY

A. Signature D. Davis Agent
 Addressee

B. Received by (Printed Name) D. Davis C. Date of Delivery 11/29/10

D. Is delivery address different from item 1? Yes
 If YES, enter delivery address below: No

3. Service Type
 Certified Mail Express Mail
 Registered Return Receipt for Merchandise
 Insured Mail C.O.D.

4. Restricted Delivery? (Extra Fee) Yes

7010 0290 0003 5707 7776



United States Department of the Interior

FISH AND WILDLIFE SERVICE
Mississippi Field Office
6578 Dogwood View Parkway, Suite A
Jackson, MS 39213



December 2, 2010

Mr. Chad Stinnett
Environmental Engineers, Inc.
11578 US Highway 411
Odenville, Alabama 35120

Environmental Engineers Inc.

DEC 06 2010

RECEIVED

RE: Tower Proposal in Benton County, Mississippi, Project No: JSE01P1016

Dear Mr. Stinnett:

The U.S. Fish and Wildlife Service (Service) received your letter dated November 23, 2010, regarding the construction of a 450-foot guyed wire telecommunications tower and fenced tower compound located off of Cornersville Road in Hickory Flats, Mississippi. Our comments are submitted in accordance with the Endangered Species Act (87 Stat. 884, as amended; 16 U.S.C. 1531 et seq.) and the Migratory Bird Treaty Act (16 U.S.C. 703-711).

There are no federally listed species for Benton County. However, due to the adverse impact these towers can have on migratory birds, we have included our Service recommendations as an attachment.

Thank you for the opportunity to comment on this project. Please contact Terri Jacobson at (601) 321-1129 if your project plans change or if you have any questions. For our most up-to-date species list, please visit our web site at <http://www.fws.gov/mississippi/endsp.html>

Sincerely,


Stephen Ricks
Field Office Supervisor

Appendix E

U.S. Fish and Wildlife Service Tower Guidance

Communications Tower Siting, Construction, Operation, and Decommissioning

The Migratory Bird Treaty Act (16 U.S.C. 703-712) prohibits the taking, killing, possession, transportation, and importation of migratory birds, their eggs, parts, and nests, except when specifically authorized by the Department of the Interior. While the Act has no provision for allowing an unauthorized take, it must be recognized that some birds may be killed at structures such as communications towers even if all reasonable measures to avoid it are implemented. The Service's Division of Law Enforcement carries out its mission to protect migratory birds not only through investigations and enforcement, but also through fostering relationships with individuals and industries that proactively seek to eliminate their impacts on migratory birds. While it is not possible under the Act to absolve individuals or companies from liability if they follow these recommended guidelines, the Division of Law Enforcement and Department of Justice have used enforcement and prosecutorial discretion in the past regarding individuals or companies who have made good faith efforts to avoid the take of migratory birds. Due to the adverse impact telecommunications towers can have on migratory birds, we would like to make the following recommendations:

1. Co-locate communications equipment on an existing communication tower or other structure (*e.g.*, billboard, water tower, or building mount). Depending on tower load factors, from 6 to 10 providers may collocate on an existing tower.
2. If co-location is not feasible and a new tower or towers are to be constructed, towers should be no more than 199 feet above ground level (AGL), use construction techniques which do not require guy wires (*e.g.*, use a lattice structure, monopole, etc.). Towers should be unlighted if Federal Aviation Administration regulations permit.
3. If constructing multiple towers, consider the cumulative impacts of all towers to migratory birds and threatened and endangered species as well as the impacts of each individual tower.
4. If at all possible, new towers should be sited within existing "antenna farms" (clusters of towers). Towers should not be sited in or near wetlands, other known bird concentration areas (*e.g.*, state or Federal refuges, staging areas, rookeries), in known migratory or daily movement flyways, or in habitat of threatened or endangered species. Towers should not be sited in areas with a high incidence of fog, mist, and low ceilings.
5. If taller (>199 feet AGL) towers requiring lights for aviation safety must be constructed, the minimum amount of pilot warning and obstruction avoidance lighting required by the FAA should be used. Unless otherwise required by the FAA, only white (preferable) or red strobe lights should be used at night, and these should be the minimum number, minimum intensity, and minimum number of flashes per minute (longest duration between flashes) allowable by the FAA. The use of solid red or pulsating red warning lights at night should be avoided. Current research indicates that solid or pulsating (beacon) red lights attract night-migrating birds at a much higher rate than white strobe lights. Red strobe lights have not yet been studied.

6. Tower designs using guy wires for support which are proposed to be located in known raptor or waterbird concentration areas or daily movement routes, or in major diurnal migratory bird movement routes or stopover sites, should have daytime visual markers on the wires to prevent collisions by these diurnally moving species. (For guidance on markers, see *Suggested Practices for Avian Protection on Power Lines: The State of the Art in 2006* - a profile of the research and safeguards available to remedy the issue of avian electrocutions. Copies can be obtained from Edison Electric Institute by calling 1-800-334-5453 or via the Internet at http://www.eei.org/products_and_services/descriptions_and_access/index.htm.)
7. Towers and appendant facilities should be sited, designed and constructed so as to avoid or minimize habitat loss within and adjacent to the tower "footprint". However, a larger tower footprint is preferable to the use of guy wires in construction. Road access and fencing should be minimized to reduce or prevent habitat fragmentation and disturbance, and to reduce above ground obstacles to birds in flight.
8. If significant numbers of breeding, feeding, or roosting birds are known to habitually use the proposed tower construction area, relocation to an alternate site is recommended.
9. In order to reduce the number of towers needed in the future, new towers should be designed structurally and electrically to accommodate comparable antennas for at least two additional users (minimum of three users for each tower structure), unless this design would require the addition of lights or guy wires to an otherwise unlighted and/or unguyed tower.
10. Security lighting for on-ground facilities and equipment should be down-shielded to keep light within the boundaries of the site.
11. Service personnel or researchers from the Communication Tower Working Group should be allowed, if asked, access to the site to evaluate bird use, conduct dead-bird searches, to place net catchments below the towers but above the ground, and to place radar, Global Positioning System, infrared, thermal imagery, and acoustical monitoring equipment as necessary to assess and verify bird movements and to gain information on the impacts of various tower sizes, configurations, and lighting systems.
12. Towers no longer in use or determined to be obsolete should be removed within twelve months of cessation of use.

These voluntary recommendations are based on the Service's Guidance on the Siting, Construction, Operation and Decommissioning of Communications Towers which can be found at <http://www.fws.gov/migratorybirds/issues/towers/comtow.html>

In order to obtain information on the usefulness of these guidelines in preventing bird strikes, and to identify any recurring problems with their implementation which may necessitate modifications, please advise us of the final location and specifications of the proposed tower. In your response please explain which of the recommended measures were implemented and if the recommended measures could not be implemented, please explain why they were not feasible.

Appendix F

**Avian Mitigation Plan
Mississippi Wireless Integrated Network
Mississippi Interoperable Communications Grant 2008-MS-MX-0001
February 3, 2011**

The Department of Homeland Security (DHS) Federal Emergency Management Agency (FEMA) Grant Programs Directorate (GPD) is providing funding through its Mississippi Interoperable Communications Grant 2008-MS-MX-0001 to the Mississippi Wireless Communication Commission (MWCC) to construct a statewide public safety radio system known as the Mississippi Wireless Integrated Network (MSWIN). The MSWIN program will result in the construction of approximately 140 communication towers (see attached map) throughout the state of Mississippi.

In accordance with the National Environmental Policy Act (NEPA) of 1969, the President's Council on Environmental Quality regulations implementing NEPA (40 Code of Federal Regulations (CFR) Parts 1500-1508), and FEMA's regulations implementing NEPA (44 CFR Part 10), Environmental Assessments (EA) were prepared for several proposed towers to be constructed under the MSWIN program. The purpose of the EAs is to evaluate the potential impacts of the proposed towers on the environment. Through the preparation of these EAs, FEMA identified a potential for cumulative impacts to migratory birds as a result of the MSWIN project as birds could be injured or killed by colliding in to guy wires and/or the tower structure, or could be disoriented by tower lighting. This Avian Mitigation Plan was developed by FEMA, MWCC and the Mississippi Department of Wildlife, Fisheries, and Parks (MDWFP) to address these potential cumulative impacts. The U.S. Fish and Wildlife Service (USFWS) Jackson, MS Ecological Services Office reviewed this Avian Mitigation Plan. MWCC is responsible for the cost of implementing the Avian Mitigation Plan.

Background

Following Hurricane Katrina in 2005, the Mississippi Legislature created the MWCC with the mission of implementing a statewide reliable, survivable, interoperable voice and data communication system for public safety and first responders. Congress appropriated \$140 million toward this effort. The MWCC has completed implementation of MSWIN on 71 sites in the southern half of the State and anticipates completion of the entire system (approximately 140 sites) in early 2012.

The MSWIN radio system is reliant on communication towers in order to operate. While MSWIN is vitally important to the first responders, the State recognizes the importance of building towers that will avoid possible harm to migratory birds. The conservation of birds will help sustain ecological integrity and ecosystem services, including insect control, pollination, and seed dispersal. Migratory bird conservation also meets the growing public interest in outdoor education and recreation.

In building MSWIN and using Federal funding, the State must be compliant with Federal, State and local regulations and guidelines pertinent to the project. These regulations include those of the Federal Communications Commission (FCC), the U. S. Fish and Wildlife Service (USFWS) and the Federal Aviation Administration (FAA) relative to

FEMA
Avian Mitigation Plan
Mississippi Wireless Integrated Network

frequency licensing and tower construction, as well as the NEPA requirements previously discussed.

The FCC maintains jurisdiction over tower sites and its rules, 47 C.F.R. §1.1307(a)(3), require applicants, licensees, and tower owners (Applicants) to consider the impact of proposed facilities under the Endangered Species Act (ESA), 16 U.S.C. s. 1531 et seq. Applicants must determine whether any proposed facilities may affect listed, threatened or endangered species or designated critical habitats, or are likely to jeopardize the continued existence of any proposed threatened or endangered species or designated critical habitats. In addition, USFWS has formulated and published voluntary guidelines for the siting and operation of towers intended to address potential effects on migratory birds. These guidelines and an accompanying tower site evaluation form are posted on the USFWS website (<http://www.fws.gov/migratorybirds/CurrentBirdIssues/Hazards/towers/towers.htm>). According to USFWS, the guidelines reflect USFWS' judgment of "the most prudent and effective measures for avoiding bird strikes at towers."

The documented avian collision risk is primarily towers taller than 1000' that use steady burning red lights at night. Towers of this height are always supported with guyed wire cables. Steady burning red lights are part of the FAA's A-2 lighting system where a tower is painted aviation orange for daytime obstruction avoidance and red lights at night.

The MSWIN towers which have an average height of 425 feet, generally use two types of lighting systems, the white mid intensity strobes, FAA designation as D1 or D2 and the A1 or A2 system which uses orange and white paint in seven alternating bands for day time obstruction avoidance along with red lights at night for night time obstruction avoidance. Towers 500 feet or less use white mid intensity strobes and towers 500 to 600 feet use orange paint and red lights.

The MSWIN system uses the most avian friendly lights possible for tower sites, however the FAA does not approve the use of white lights in all geographic areas and on numerous occasions has denied such request, based primarily on the premise that white lights are more difficult to distinguish at night than red lights and are more problematic in areas where emergency medical helicopters and other low flying aircraft such as military may be present

Mitigation, Monitoring and Reporting of Avian Injuries and Deaths at MSWIN Tower Sites

MWCC has in the past and will continue to include the following mitigation measures in the design and deployment of MSWIN.

1. White tower lights are used where allowed by the FAA. Where red lights are required, halogen strobes are used instead of pulsing incandescent beacons.

**FEMA
Avian Mitigation Plan
Mississippi Wireless Integrated Network**

2. Site construction incorporates limited road improvements and site fencing to reduce land disturbance.
3. Tower locations are placed to avoid known bird rookeries and nesting grounds, and inspection of tower sites post-construction will help identify instances of avian injuries and deaths.
4. Towers are designed to allow for future use of other radio systems to reduce the number of towers required in the area. The average height of MSWIN towers is 425 feet allowing MSWIN to provide coverage of 97% of Mississippi's land area with only 135 RF sites.
5. Security lighting for on ground equipment is designed to focus in the secure compound to minimize disturbance of surrounding areas.

Additionally, the State of Mississippi will monitor avian mortality around its tower sites by providing a collection kit at each site along with a process to record the location of the deceased bird and deliver its remains to the MDWFP for inclusion of the deceased avian into a central state data system. Over time, this practice will contribute scientific data that can be used by MDWFP and USFWS in determining the significance of potential impacts of towers on migratory birds. Where possible, attempts will be made to determine the cause of the bird's death (e.g., from a predator, virus, hunter or tower strike).

Each site will have a weather-proof enclosure containing rubber gloves, sealable containers of sufficient size to collect, contain and transport the deceased bird, and a form to document the circumstances of the bird's death. The carcasses will be collected in a manner to preserve the integrity of the find and transported to the MDWFP office in Jackson, MS for examination and documentation into the Avian Mortality database. USFWS will also be given access to the MDWFP's Avian Mortality database. If possible, the bird will be photographed in the field and at MDWFP.

In the unlikely event field technicians encounter an injured and living bird, all efforts will be made to recover, rehabilitate and release back to the wild. MWCC will work closely with the MDWFP to request assistance in those situations.

MDWFP and USFWS, upon request, will be allowed access to tower sites to document avian mortalities and injuries, monitor bird behavior, assess lighting impacts on migratory birds, and conduct similar research. If a tower is discovered to have adverse affects to migratory bird populations (i.e., greater than 10 bird kills per night), these towers will be reported immediately to the MDWFP, USFWS, and FEMA.


An annual report documenting the number of avian deaths recorded at MSWIN sites will be prepared for five consecutive years following conclusion of the construction of the towers comprising the MSWIN system. The reporting period will begin a year from the execution of this mitigation plan and extend until 5 years after the last FEMA funded tower is constructed. The report will be submitted to FEMA's Office of Environmental

FEMA
Avian Mitigation Plan
Mississippi Wireless Integrated Network

Planning and Historic Preservation and the Grant Program Directorate. The report will also be submitted to the USFWS in Jackson, MS (Ecological Services Office) and MDWFP.

Approved

 02/15/11
Elizabeth M. Harman Date
Assistant Administrator, Grant Program Directorate
Federal Emergency Management Agency

 2/8/2011
Jonar Maldonado Date
Environmental Officer
Federal Emergency Management Agency

 02/8/2011
Bill Roach Date
Executive Officer
Mississippi Wireless Communication Commission

Appendix G

Henry Fisher

From: towernotifyinfo@fcc.gov
Sent: Wednesday, January 05, 2011 4:03 PM
To: towerinfo@envciv.com
Subject: Proposed Tower Structure Info - Email ID #2697790

Dear Henry A Fisher,

Thank you for submitting a notification regarding your proposed construction via the Tower Construction Notification System. Note that the system has assigned a unique Notification ID number for this proposed construction. You will need to reference this Notification ID number when you update your project's Status with us.

Below are the details you provided for the construction you have proposed:

Notification Received: 01/05/2011

Notification ID: 72320

Tower Owner Individual or Entity Name: Towers of Mississippi II/State of Mississippi

Consultant Name: Henry A Fisher

Street Address: 11578 U.S. Highway 411

City: Odenville

State: ALABAMA

Zip Code: 35120

Phone: 205-629-3868

Email: towerinfo@envciv.com

Structure Type: GTOWER - Guyed Tower

Latitude: 34 deg 36 min 27.4 sec N

Longitude: 89 deg 12 min 27.8 sec W

Location Description: Cornersville Road

City: Hickory Flat

State: MISSISSIPPI

County: BENTON

Ground Elevation: 139.3 meters

Support Structure: 137.2 meters above ground level

Overall Structure: 137.2 meters above ground level

Overall Height AMSL: 276.5 meters above mean sea level

72320

TOM

Henry Fisher

From: towernotifyinfo@fcc.gov
Sent: Friday, January 14, 2011 2:01 AM
To: towerinfo@envciv.com
Cc: kim.pristello@fcc.gov; diane.dupert@fcc.gov
Subject: NOTICE OF ORGANIZATION(S) WHICH WERE SENT PROPOSED TOWER CONSTRUCTION NOTIFICATION INFORMATION - Email ID #2699769

Dear Sir or Madam:

Thank you for using the Federal Communications Commission's (FCC) Tower Construction Notification System (TCNS). The purpose of this electronic mail message is to inform you that the following authorized persons were sent the information you provided through TCNS, which relates to your proposed antenna structure. The information was forwarded by the FCC to authorized TCNS users by electronic mail and/or regular mail (letter).

Persons who have received the information that you provided include leaders or their designees of federally-recognized American Indian Tribes, including Alaska Native Villages (collectively "Tribes"), Native Hawaiian Organizations (NHOs), and State Historic Preservation Officers (SHPOs). For your convenience in identifying the referenced Tribes and in making further contacts, the City and State of the Seat of Government for each Tribe and NHO, as well as the designated contact person, is included in the listing below. We note that Tribes may have Section 106 cultural interests in ancestral homelands or other locations that are far removed from their current Seat of Government. Pursuant to the Commission's rules as set forth in the Nationwide Programmatic Agreement for Review of Effects on Historic Properties for Certain Undertakings Approved by the Federal Communications Commission (NPA), all Tribes and NHOs listed below must be afforded a reasonable opportunity to respond to this notification, consistent with the procedures set forth below, unless the proposed construction falls within an exclusion designated by the Tribe or NHO. (NPA, Section IV.F.4).

The information you provided was forwarded to the following Tribes and NHOs who have set their geographic preferences on TCNS. If the information you provided relates to a proposed antenna structure in the State of Alaska, the following list also includes Tribes located in the State of Alaska that have not specified their geographic preferences. For these Tribes and NHOs, if the Tribe or NHO does not respond within a reasonable time, you should make a reasonable effort at follow-up contact, unless the Tribe or NHO has agreed to different procedures (NPA, Section IV.F.5). In the event such a Tribe or NHO does not respond to a follow-up inquiry, or if a substantive or procedural disagreement arises between you and a Tribe or NHO, you must seek guidance from the Commission (NPA, Section IV.G). These procedures are further set forth in the FCC's Declaratory Ruling released on October 6, 2005 (FCC 05-176).

1. Historic Preservation Officer Bryant J Celestine - Alabama-Coushatta Tribe of Texas - Livingston, TX - electronic mail

Details: Please consider this notification as our interest for consultation regarding your proposal. The Alabama-Coushatta Tribe of Texas requests an administrative fee of \$300.00 for our services including internal file searches, elder consultations, and if necessary, travel expenses for a site visit to complete our determination regarding your proposal. TAKE NOTE of the following procedures as this will assist our efforts to provide your firm with the most efficient process in returning our determinations:

1. Submit your Form 620 or 621 by email to celestine.bryant@actribe.org. Each submission is logged and within 10 days of receipt, an invoice will be returned to the email account we

receive your supplemental information. IF YOU HAVE NOT RECEIVED THIS BY 15DAYS, PLEASE INQUIRE.

2. INCLUDE your invoice number on your payment and submit according to the Invoice instructions. We cannot track your payment by project number so please do not submit without an invoice number.
3. Within 20 days of your original submission, you will receive an email response from our Office relating to our determinations for your proposal. This may occur despite a delay in fee payment. If you have not received our determination within 25 days, PLEASE INQUIRE.
4. IN THE EVENT OF AN OUTSTANDING BALANCE, a detailed invoice will be submitted in place of our determination. In this manner, your Section 106 obligations without Tribe ARE NOT complete until we have forwarded our written response indicating our determination.
5. If the applicant/tower builder decides to withdraw a proposal, please advise our office as soon as possible to avoid an outstanding balance in the future and any unnecessary research by our office.

Thank you, Bryant J. Celestine - Historic Preservation Officer

2. Historic Preservation Officer Virginia Nail - Chickasaw Nation - Ada, OK - electronic mail

3. Director of Cultural Resources & THPO Terry D Cole - Choctaw Nation of Oklahoma - Durant, OK - electronic mail and regular mail

Details: The Applicant may conclude that the Choctaw Nation of Oklahoma has no interest in a site if there is existing disturbance wherein the depth of the previous disturbance exceeds the proposed construction depth (excluding footing and other anchoring mechanisms) by at least 2 feet (Applying VI - D(2)(c)(i) of the Nationwide Programmatic Agreement concerning Field Surveys; 'In the Matter of Nationwide Programmatic Agreement Regarding the Section 106 National Historic Preservation Act Review Process,' Report and Order, 20 FCC Rcd. 1073, WT Docket No. 03-128, October 5, 2004).

Furthermore, the Choctaw Nation of Oklahoma does not have an interest in a Tower that will be constructed on an existing structure, developed land, or within city limits. However, any of the above mentioned criteria should be communicated to us if not evident in the initial Notification Details. For all other towers, we request a signed field survey report that meets the Federal guidelines set forth by the Department of the Interior and a site location map along with pictures for each project.

Additionally, the Choctaw Nation of Oklahoma has informed FCC Staff that if the Applicant does not receive a response from the Tribe within 30 days of a TCNS notification, then the Applicant SHOULD MAKE A GOOD FAITH EFFORT WITH A FOLLOW-UP PHONE CALL to make sure that the tribe is aware of the proposed tower project. However, should construction expose buried archaeological or building materials such as chipped stone, tools, pottery, bone, historical crockery, glass or metal items, this office should be contacted immediately @ 1-800-522-6170 ext. 2137. [n.b. Please reference the TCNS number in all communications that follow the initial notification.]

4. MEKKO and Acting Tribal Administrator Jennie Lillard - Kialegee Tribal Town - Wetumka, OK - regular mail

Details: If the Applicant receives no response from the Kialegee Tribal Town within 30 days after notification through TCNS, the Kialegee Tribal Town has no interest in participating in pre-construction review for the site. The Applicant, however, must immediately notify the

Kialagee Tribal Town in the event archaeological properties or human remains are discovered during construction.

5. THPO Earl J Barbry Jr - Tunica-Biloxi Indians of Louisiana - Marksville, LA - regular mail

The information you provided was also forwarded to the additional Tribes and NHOs listed below. These Tribes and NHOs have NOT set their geographic preferences on TCNS, and therefore they are currently receiving tower notifications for the entire United States. For these Tribes and NHOs, you are required to use reasonable and good faith efforts to determine if the Tribe or NHO may attach religious and cultural significance to historic properties that may be affected by its proposed undertaking. Such efforts may include, but are not limited to, seeking information from the relevant SHPO or THPO, Indian Tribes, state agencies, the U.S. Bureau of Indian Affairs, or, where applicable, any federal agency with land holdings within the state (NPA, Section IV.B). If after such reasonable and good faith efforts, you determine that a Tribe or NHO may attach religious and cultural significance to historic properties in the area and the Tribe or NHO does not respond to TCNS notification within a reasonable time, you should make a reasonable effort to follow up, and must seek guidance from the Commission in the event of continued non-response or in the event of a procedural or substantive disagreement. If you determine that the Tribe or NHO is unlikely to attach religious and cultural significance to historic properties within the area, you do not need to take further action unless the Tribe or NHO indicates an interest in the proposed construction or other evidence of potential interest comes to your attention.

None

The information you provided was also forwarded to the following SHPOs in the State in which you propose to construct and neighboring States. The information was provided to these SHPOs as a courtesy for their information and planning. You need make no effort at this time to follow up with any SHPO that does not respond to this notification. Prior to construction, you must provide the SHPO of the State in which you propose to construct (or the Tribal Historic Preservation Officer, if the project will be located on certain Tribal lands), with a Submission Packet pursuant to Section VII.A of the NPA.

6. SHPO Lee Warner - Alabama Historical Commission - Montgomery, AL - electronic mail

7. Deputy SHPO Elizabeth Ann Brown - Alabama Historical Commission - Montgomery, AL - electronic mail

8. SHPO Cathie Matthews - Department of Arkansas Heritage - Little Rock, AR - electronic mail

9. Deputy SHPO Ken Grunewald - Department of Arkansas Heritage - Little Rock, AR - electronic mail

10. SHPO Elbert Hilliard - Mississippi Dept of Archives & History - Jackson, MS - regular mail

11. Deputy SHPO Kenneth H P'Pool - Division of Historic Preservation - Jackson, MS - electronic mail

If you are proposing to construct a facility in the State of Alaska, you should contact Commission staff for guidance regarding your obligations in the event that Tribes do not respond to this notification within a reasonable time.

Please be advised that the FCC cannot guarantee that the contact(s) listed above opened and reviewed an electronic or regular mail notification. The following information relating to the proposed tower was forwarded to the person(s) listed above:

Notification Received: 01/05/2011
Notification ID: 72320
Tower Owner Individual or Entity Name: Towers of Mississippi II/State of Mississippi
Consultant Name: Henry A Fisher
Street Address: 11578 U.S. Highway 411
City: Odenville
State: ALABAMA
Zip Code: 35120
Phone: 205-629-3868
Email: towerinfo@envciv.com

Structure Type: GTOWER - Guyed Tower
Latitude: 34 deg 36 min 27.4 sec N
Longitude: 89 deg 12 min 27.8 sec W
Location Description: Cornersville Road
City: Hickory Flat
State: MISSISSIPPI
County: BENTON
Ground Elevation: 139.3 meters
Support Structure: 137.2 meters above ground level
Overall Structure: 137.2 meters above ground level
Overall Height AMSL: 276.5 meters above mean sea level

If you have any questions or comments regarding this notice, please contact the FCC using the electronic mail form located on the FCC's website at:

<http://wireless.fcc.gov/outreach/notification/contact-fcc.html>.

You may also call the FCC Support Center at (877) 480-3201 (TTY 717-338-2824). Hours are from 8 a.m. to 7:00 p.m. Eastern Time, Monday through Friday (except Federal holidays). To provide quality service and ensure security, all telephone calls are recorded.

Thank you,
Federal Communications Commission

Appendix H

General Information

1) (Select only one) (NE) NE – New UA – Update of Application WD – Withdrawal of Application	
2) If this application is for an Update or Withdrawal, enter the file number of the pending application currently on file.	File Number:

Applicant Information

3) FCC Registration Number (FRN):
4) Name: Towers of Mississippi II/State of Mississippi

Contact Name

5) First Name: Taylor	6) MI:	7) Last Name: Robinson	8) Suffix:
9) Title:			

Contact Information

10) P.O. Box:	And /Or	11) Street Address: 31560 Blakeley Way	
12) City: Spanish Fort		13) State: AL	14) Zip Code: 36527
15) Telephone Number: (205) 266-4466		16) Fax Number: ()	
17) E-mail Address: trobinson@vucancompany.com			

Consultant Information

18) FCC Registration Number (FRN): 0019057413
19) Name: MRS Consultants, LLC.

Principal Investigator

20) First Name: Beth	21) MI: A	22) Last Name: Ryba	23) Suffix:
24) Title: Cultural Resource Specialist			

Principal Investigator Contact Information

25) P.O. Box: 3146	And /Or	26) Street Address:	
27) City: Tuscaloosa		28) State: AL	29) Zip Code: 35403
30) Telephone Number: (205) 759-1621		31) Fax Number: (205) 759-1621	
32) E-mail Address: earyba@earthlink.net			

Professional Qualification

33) Does the Principal Investigator satisfy the Secretary of the Interior's Professional Qualification Standards?	<input checked="" type="checkbox"/> Yes <input type="checkbox"/> No
34) Areas of Professional Qualification: <input checked="" type="checkbox"/> Archaeologist <input type="checkbox"/> Architectural Historian <input type="checkbox"/> Historian <input type="checkbox"/> Architect <input type="checkbox"/> Other (Specify) _____	

Additional Staff

35) Are there other staff involved who meet the Professional Qualification Standards of the Secretary of the Interior?	<input checked="" type="checkbox"/> Yes <input type="checkbox"/> No
--	---

If "Yes", complete the following:

36) First Name: David	37) MI: B.	38) Last Name: Schneider	39) Suffix:
40) Title: Architectural Historian, Scheider Historic Preservation, LLC.			
41) Areas of Professional Qualification: <input type="checkbox"/> Archaeologist <input checked="" type="checkbox"/> Architectural Historian <input type="checkbox"/> Historian <input type="checkbox"/> Architect <input type="checkbox"/> Other (Specify) _____			

This page may be copied to include additional staff.**Consultant Information Attachments required – See instructions for details.**

Site Information

Tower Construction Notification System

1) TCNS Notification Number: 72320

Site Information

2) Site Name: Hickory Flat (MSWIN 30410-C)

3) Site Address: Cornersville Road

4) City: Hickory Flat

5) State: MS

6) Zip Code: 38633

7) County/Borough/Parish: Benton

8) Nearest Crossroads: Cornersville Road and Lagoon Road

9) NAD 83 Latitude (DD-MM-SS.S): 34-36-27.35

() N or () S

10) NAD 83 Longitude (DD-MM-SS.S): 89-12-27.76

() E or () W

Tower Information

11) Tower height above ground level (include top-mounted attachments such as lightning rods): 450 () Feet () Meters

12) Tower Type (Select One):

() Guyed lattice tower

() Self-supporting lattice

() Monopole

() Other (Describe):

Project Status

13) Current Project Status (Select One):

() Construction has not yet commenced

() Construction has commenced, but is not completed

Construction commenced on: ___/___/___

() Construction has been completed

Construction commenced on: ___/___/___

Construction completed on: ___/___/___

Site Information Attachments required – See instructions for details.

Determination of Effect

14) Direct Effects (Select One):

- No Historic Properties in Area of Potential Effects (APE)
- No Effect on Historic Properties in APE
- No Adverse Effect on Historic Properties in APE
- Adverse Effect on one or more Historic Properties in APE

15) Visual Effects (Select One):

- No Historic Properties in Area of Potential Effects (APE)
- No Effect on Historic Properties in APE
- No Adverse Effect on Historic Properties in APE
- Adverse Effect on one or more Historic Properties in APE

Determination of Effect Attachments required – See instructions for details.

Tribal/NHO Involvement

1) Have Indian Tribes or Native Hawaiian Organizations (NHOs) been identified that may attach religious and cultural significance to historic properties which may be affected by the undertaking within the APEs for direct and visual effects?	(<input checked="" type="checkbox"/>) <u>Yes</u> (<input type="checkbox"/>) <u>No</u>
2a) Tribes/NHOs contacted through TCNS Notification Number: <u>72320</u> Number of Tribes/NHOs: <u>5</u>	
2b) Tribes/NHOs contacted through an alternate system: <u>None</u>	Number of Tribes/NHOs: <u>None</u>

Tribe/NHO Contacted Through TCNS

3) Tribe/NHO FRN:
4) Tribe/NHO Name: <u>Alabama-Coushatta Tribe of Texas</u>

Contact Name

5) First Name: <u>Bryant</u>	6) MI: <u>J</u>	7) Last Name: <u>Celestine</u>	8) Suffix:
9) Title: <u>Historic Preservation Officer</u>			

Dates & Response

10) Date Contacted <u>1</u> / <u>5</u> / <u>11</u>	11) Date Replied _____ / _____ / _____
(<input checked="" type="checkbox"/>) No Reply	
(<input type="checkbox"/>) Replied/No interest	
(<input type="checkbox"/>) Replied/Have interest	
(<input type="checkbox"/>) Replied/Other _____	

This page may be copied to include additional Tribes/NHOs contacted.
Tribal/NHO Involvement Attachments may be required – See instructions for details.

Tribal/NHO Involvement

1) Have Indian Tribes or Native Hawaiian Organizations (NHOs) been identified that may attach religious and cultural significance to historic properties which may be affected by the undertaking within the APEs for direct and visual effects?		(<input checked="" type="checkbox"/>) Yes (<input type="checkbox"/>) No
2a) Tribes/NHOs contacted through TCNS Notification Number: <u>72320</u>	Number of Tribes/NHOs: <u>5</u>	
2b) Tribes/NHOs contacted through an alternate system: None	Number of Tribes/NHOs: <u>None</u>	

Tribe/NHO Contacted Through TCNS

3) Tribe/NHO FRN:
4) Tribe/NHO Name: Choctaw Nation of Oklahoma

Contact Name

5) First Name: Terry	6) MI: D	7) Last Name: Cole	8) Suffix:
9) Title: Director of Cultural Resources and THPO			

Dates & Response

10) Date Contacted <u>1</u> / <u>5</u> / <u>11</u>	11) Date Replied <u> </u> / <u> </u> / <u> </u>
<input checked="" type="checkbox"/> No Reply <input type="checkbox"/> Replied/No Interest <input type="checkbox"/> Replied/Have Interest <input type="checkbox"/> Replied/Other _____	

**This page may be copied to include additional Tribes/NHOs contacted.
Tribal/NHO Involvement Attachments may be required – See instructions for details.**

Tribal/NHO Involvement

1) Have Indian Tribes or Native Hawaiian Organizations (NHOs) been identified that may attach religious and cultural significance to historic properties which may be affected by the undertaking within the APEs for direct and visual effects?		(<input checked="" type="checkbox"/>) Yes (<input type="checkbox"/>) No
2a) Tribes/NHOs contacted through TCNS Notification Number: <u>72320</u>	Number of Tribes/NHOs: <u>5</u>	
2b) Tribes/NHOs contacted through an alternate system: <u>None</u>	Number of Tribes/NHOs: <u>None</u>	

Tribe/NHO Contacted Through TCNS

3) Tribe/NHO FRN:
4) Tribe/NHO Name: <u>Kialegee Tribal Town</u>

Contact Name

5) First Name: <u>Jennie</u>	6) MI:	7) Last Name: <u>Lillard</u>	8) Suffix:
9) Title: <u>MEKKO and Acting Tribal Administrator</u>			

Dates & Response

10) Date Contacted <u>1</u> / <u>5</u> / <u>11</u>	11) Date Replied <u> </u> / <u> </u> / <u> </u>
(<input checked="" type="checkbox"/>) No Reply	
(<input type="checkbox"/>) Replied/No Interest	
(<input type="checkbox"/>) Replied/Have Interest	
(<input type="checkbox"/>) Replied/Other _____	

This page may be copied to include additional Tribes/NHOs contacted.
Tribal/NHO Involvement Attachments may be required – See instructions for details.

Tribal/NHO Involvement

1) Have Indian Tribes or Native Hawaiian Organizations (NHOs) been identified that may attach religious and cultural significance to historic properties which may be affected by the undertaking within the APEs for direct and visual effects?		<input checked="" type="checkbox"/> Yes () No
2a) Tribes/NHOs contacted through TCNS Notification Number: <u>72320</u>	Number of Tribes/NHOs: <u>5</u>	
2b) Tribes/NHOs contacted through an alternate system: None	Number of Tribes/NHOs: <u>None</u>	

Tribe/NHO Contacted Through TCNS

3) Tribe/NHO FRN:
4) Tribe/NHO Name: Tunica-Biloxi Indians of Louisiana

Contact Name

5) First Name: Earl	6) MI: J	7) Last Name: Barbry	8) Suffix: Jr.
9) Title: THPO			

Dates & Response

10) Date Contacted <u>1</u> / <u>5</u> / <u>11</u>	11) Date Replied _____ / _____ / _____
<input checked="" type="checkbox"/> No Reply <input type="checkbox"/> Replied/No Interest <input type="checkbox"/> Replied/Have Interest <input type="checkbox"/> Replied/Other _____	

**This page may be copied to include additional Tribes/NHOs contacted.
Tribal/NHO Involvement Attachments may be required – See instructions for details.**

Other Tribes/NHOs Contacted

Tribes/NHO Information

1) FCC Registration Number (FRN): None
2) Name: None

Contact Name

3) First Name:	4) MI:	5) Last Name:	6) Suffix:
7) Title:			

Contact information

8) P.O. Box:	And /Or	9) Street Address:		
10) City:		11) State:	12) Zip Code:	
13) Telephone Number: ()		14) Fax Number: ()		
15) E-mail Address:				
16) Preferred means of communication: () E-mail () Letter () Both				

Dates & Response

17) Date Contacted ____/____/____	18) Date Replied ____/____/____
() No Reply	
() Replied/No Interest	
() Replied/Have Interest	
() Replied/Other _____	

This page may be copied to include additional Tribes/NHOs.

Historic Properties

Properties Identified

1) Have any historic properties been identified within the APEs for direct and visual effect?	(<input type="checkbox"/>) <u>Yes</u> (<input type="checkbox"/>) <u>No</u>
2) Has the identification process located archaeological materials that would be directly affected, or sites that are of cultural or religious significance to Tribes/NHOs?	(<input type="checkbox"/>) <u>Yes</u> (<input type="checkbox"/>) <u>No</u>
3) Are there more than 10 historic properties within the APEs for direct and visual effect? If "Yes", you are required to attach a Cultural Resources Report in lieu of adding the Historic Property below.	(<input type="checkbox"/>) <u>Yes</u> (<input type="checkbox"/>) <u>No</u>

Historic Property

4) Property Name: See attached cultural resource report and communications tower site report.
5) SHPO Site Number:

Property Address

6) Street Address:		
7) City:	8) State:	9) Zip Code:
10) County/Borough/Parish:		

Status & Eligibility

11) Is this property listed on the National Register? Source: _____	(<input type="checkbox"/>) <u>Yes</u> (<input type="checkbox"/>) <u>No</u>
12) Is this property eligible for listing on the National Register? Source: _____	(<input type="checkbox"/>) <u>Yes</u> (<input type="checkbox"/>) <u>No</u>
13) Is this property a National Historic Landmark?	(<input type="checkbox"/>) <u>Yes</u> (<input type="checkbox"/>) <u>No</u>

14) Direct Effects (Select One): <input type="checkbox"/> No Effect on this Historic Property in APE <input type="checkbox"/> No Adverse Effect on this Historic Property in APE <input type="checkbox"/> Adverse Effect on this Historic Property in APE
15) Visual Effects (Select One): <input type="checkbox"/> No Effect on this Historic Property in APE <input type="checkbox"/> No Adverse Effect on this Historic Property in APE <input type="checkbox"/> Adverse Effect on this Historic Property in APE

**This page may be copied to include additional Historic Properties.
Historic Property Attachments required – See instructions for details.**

Local Government Involvement

Local Government Agency

1) FCC Registration Number (FRN):

2) Name:

Benton County

Contact Name

3) First Name: Mark

4) MI: M

5) Last Name: Orman

6) Suffix:

7) Title: Chancery Clerk

Contact Information

8) P.O. Box: 246

And
/Or

9) Street Address:

10) City: Ashland

11) State: MS

12) Zip Code: 38603

13) Telephone Number: ()

14) Fax Number: ()

15) E-mail Address:

16) Preferred means of communication:

() E-mail

() Letter

() Both

Dates & Response

17) Date Contacted 11 / 23 / 10

18) Date Replied ____ / ____ / ____

() No Reply

() Replied/No Interest

() Replied/Have Interest

() Replied/Other _____

Additional Information

19) Information on local government's role or interest (optional):

This page may be copied to include additional local government agencies.
Local Government Attachments required – See instructions for details.

Other Consulting Parties

Other Consulting Parties Contacted

1) Has any other agency been contacted and invited to become a consulting party?	<input checked="" type="checkbox"/> Yes <input type="checkbox"/> No
--	---

Consulting Party

2) FCC Registration Number (FRN):
3) Name: Northeast Mississippi Historical and Genealogical Society

Contact Name

4) First Name:	5) MI:	6) Last Name:	7) Suffix:
8) Title:			

Contact Information

9) P.O. Box: 434	And /Or	10) Street Address:
11) City: Tupelo	12) State: MS	13) Zip Code: 38801
14) Telephone Number: ()	15) Fax Number: ()	
16) E-mail Address:		
17) Preferred means of communication: <input type="checkbox"/> E-mail <input checked="" type="checkbox"/> Letter <input type="checkbox"/> Both		

Dates & Response

18) Date Contacted 11 / 23 / 10	19) Date Replied ___ / ___ / ___
<input checked="" type="checkbox"/> No Reply <input type="checkbox"/> Replied/No Interest <input type="checkbox"/> Replied/Have Interest <input type="checkbox"/> Replied/Other _____	

Additional Information

20) Information on other consulting parties' role or interest (optional):

This page may be copied to include additional consulting parties.
Consulting Parties Attachments required - See instructions for details.

Designation of SHPO/THPO

1) Designate the Lead State Historic Preservation Officer (SHPO) or Tribal Historic Preservation Officer (THPO) based on the location of the tower.

SHPO/THPO

Name: Mr. H.T. Holmes, Mississippi Department of Archives and History

2) You may also designate up to three additional SHPOs/THPOs if the APEs include multiple states. If the APEs include other countries, enter the name of the National Historic Preservation Agency and any state and provincial Historic Preservation Agency.

SHPO/THPO Name: _____

SHPO/THPO Name: _____

SHPO/THPO Name: _____

Designation of SHPO/THPO Attachments may be required – See instructions for details.

Certification

I certify that all representations on this FCC Form 620 Submission Packet and the accompanying attachments are true, correct, and complete.

Party Authorized to Sign MRS Consultants, LLC. Principal Investigator

First Name: Beth MI: A Last Name: Ryba Suffix: _____

Signature:  Date: 12 / 17 / 10

FAILURE TO SIGN THIS APPLICATION MAY RESULT IN DISMISSAL OF THE APPLICATION AND FORFEITURE OF ANY FEES PAID.

WILLFUL FALSE STATEMENTS MADE ON THIS FORM OR ANY ATTACHMENTS ARE PUNISHABLE BY FINE AND/OR IMPRISONMENT (U.S. Code, Title 18, Section 1001) AND/OR REVOCATION OF ANY STATION LICENSE OR CONSTRUCTION PERMIT (U.S. Code, Title 47, Section 312(a)(1)), AND/OR FORFEITURE (U.S. Code, Title 47, Section 503).

ATTACHMENT 1
Vitae are On File

ATTACHMENT 2
ATTACHMENT 7
ATTACHMENT 8
ATTACHMENT 9
ATTACHMENT 10
ATTACHMENT 11
ATTACHMENT 12

See Accompanying Cultural Resource Report

Attachment 3. Tribal and NHO Involvement

Initial notification to Native American tribes/organizations was submitted through the FCC Tower Construction Notification System (TCNS). See the attached TCNS list for details.

Attachment 4. Local Government

Correspondence was submitted to the local government agency with jurisdiction over the project area for comment regarding potential impacts to historical or cultural sites by the proposed action. See the attached correspondence for more information.

Attachment 5. Public Involvement

A notice requesting comment regarding potential impacts to historical or archaeological properties by the proposed action was published. Please see the attached information for details regarding the public notice.

Attachment 6. Additional Consulting Parties (Where Applicable)

Correspondence was submitted to additional consulting parties for comment regarding potential impacts to historical or cultural sites by the proposed action. See the attached correspondence for more information. (Please note that no correspondence is included where additional consulting parties were not identified for a project.)

Henry Fisher

From: towernotifyinfo@fcc.gov
Sent: Wednesday, January 05, 2011 4:03 PM
To: towerinfo@envciv.com
Subject: Proposed Tower Structure Info - Email ID #2697790

Dear Henry A Fisher,

Thank you for submitting a notification regarding your proposed construction via the Tower Construction Notification System. Note that the system has assigned a unique Notification ID number for this proposed construction. You will need to reference this Notification ID number when you update your project's Status with us.

Below are the details you provided for the construction you have proposed:

Notification Received: 01/05/2011

Notification ID: 72320

Tower Owner Individual or Entity Name: Towers of Mississippi II/State of Mississippi

Consultant Name: Henry A Fisher

Street Address: 11578 U.S. Highway 411

City: Odenville

State: ALABAMA

Zip Code: 35120

Phone: 205-629-3868

Email: towerinfo@envciv.com

Structure Type: GTOWER - Guyed Tower

Latitude: 34 deg 36 min 27.4 sec N

Longitude: 89 deg 12 min 27.8 sec W

Location Description: Cornersville Road

City: Hickory Flat

State: MISSISSIPPI

County: BENTON

Ground Elevation: 139.3 meters

Support Structure: 137.2 meters above ground level

Overall Structure: 137.2 meters above ground level

Overall Height AMSL: 276.5 meters above mean sea level



ENVIRONMENTAL ENGINEERS, INC.

11578 US Highway 411, Odenville, Alabama 35120

Environmental, Remediation, and Geological Consultants

November 23, 2010

Mr. Mark M. Orman
Benton County Chancery Clerk
P.O. Box 246
Ashland, MS 38603

Subject:

Proposed MSWIN 30410 C Hickory Flat Communications Facility

Hickory Flat, Benton County, Mississippi

Environmental Engineers, Inc. Project No.: JSE01P1016

Dear Mr. Orman:

Pursuant to the requirements of the March 2005 Nationwide Programmatic Agreement for Review of Effects on Historic Properties for Certain Undertakings Approved by the Federal Communications Commission (NPA) and Section 106 of the National Historic Preservation Act (NHPA) we are requesting comment on behalf of Towers of Mississippi, the State of Mississippi, and the Federal Emergency Management Agency regarding impact to historical or cultural sites listed on, or eligible for listing on the National Register of Historic Places (NRHP) by construction of a wireless communications tower in Benton County, Mississippi.

The site is depicted on the United States Geological Survey 7.5-minute Topographic Quadrangle "Hickory Flat, Mississippi," dated 1982. The site is located in the southwest $\frac{1}{4}$ of the northwest $\frac{1}{4}$ of Section 33, Township 5 South, Range 1 East, Benton County, Mississippi, at latitude $34^{\circ} 36' 27.350''$ north and longitude $89^{\circ} 12' 27.761''$ west (Figure 1). The site consists of a proposed 100-foot by 100-foot lease area with three associated guy anchor easements, and a proposed access road located off of Cornersville Road in Hickory Flat, Mississippi 38633. The site consists of land covered in scrub vegetation with a few scattered hardwood saplings up to three inches in diameter at breast height (dbh), and the site slopes moderately down to the west. The proposed facility access road follows an existing gravel road and extends west from Cornersville Road for approximately 1,300 feet. Proposed activities consist of construction of a 450-foot guyed communications tower and associated compound, enclosing the compound in a fence, placement of support equipment within the compound, and covering the compound with gravel. I have included the portion of the USGS topographic map depicting the proposed site location for your review.

Environmental Engineers, Inc. appreciates the opportunity to provide this information. Please reference the Environmental Engineers, Inc. project number (JSE01P1016) in correspondence regarding this site. Please provide comment within thirty days of the date of this letter. Thank you for your time and assistance and we look forward to your response. Please call me at (205) 629-3868 or email me at cstinnett@envciv.com if you have any questions or comments. You can also send a response to us via facsimile at (877) 847-3060.

Sincerely,

ENVIRONMENTAL ENGINEERS, INC.

Chad Stinnett
Senior Project Scientist

Attachments: Site Location Map

Phone: (205) 629-3868 • Fax: (877) 847-3060

7010 0290 0003 5707 7738

U.S. Postal Service
CERTIFIED MAIL RECEIPT
(Domestic Mail Only, No Insurance Coverage Provided)

For delivery information visit our website at www.usps.com

OFFICIAL USE

Postage	\$	11/23/10 Postmark Here
Certified Fee		
Return Receipt Fee (Endorsement Required)		
Restricted Delivery Fee (Endorsement Required)		
Total Postage & Fees	\$ 5.34	

Sent To Mr. Mark M Orman
 Street, Apt. No.,
 or PO Box No.
 City, State, ZIP+4

PS Form 3811, August 2006 See Reverse for Instructions

SENDER: COMPLETE THIS SECTION

- Complete items 1, 2, and 3. Also complete item 4 if Restricted Delivery is desired.
- Print your name and address on the reverse so that we can return the card to you.
- Attach this card to the back of the mailpiece, or on the front if space permits.

1. Article Addressed to:
Mr. Mark M. Orman
Benton County Chancery Clerk
P.O. Box 246
Ashland, MS 38603

2. Article Number
 (Transfer from service label)

COMPLETE THIS SECTION ON DELIVERY

A. Signature
 Mark M. Orman Agent
 Addressee

B. Received by (Printed Name)
MARK M. ORMAN

C. Date of Delivery
11/23/10

D. Is delivery address different from item 1? Yes
 If YES, enter delivery address below: No

3. Service Type
 Certified Mail Express Mail
 Registered Return Receipt for Merchandise
 Insured Mail C.O.D.

4. Restricted Delivery? (Extra Fee) Yes

7010 0290 0003 5707 7738



ENVIRONMENTAL ENGINEERS, INC.

11578 US Highway 411, Odenville, Alabama 35120

Environmental, Remediation, and Geological Consultants

November 23, 2010

Northeast Mississippi Historical & Genealogical Society
P.O. Box 434
Tupelo, MS 38801

Subject:

**Proposed MSWIN 30410 C Hickory Flat Communications Facility
Hickory Flat, Benton County, Mississippi
Environmental Engineers, Inc. Project No.: JSE01P1016**

To Whom It May Concern:

Pursuant to the requirements of the March 2005 Nationwide Programmatic Agreement for Review of Effects on Historic Properties for Certain Undertakings Approved by the Federal Communications Commission (NPA) and Section 106 of the National Historic Preservation Act (NHPA) we are requesting comment on behalf of Towers of Mississippi, the State of Mississippi, and the Federal Emergency Management Agency regarding impact to historical or cultural sites listed on, or eligible for listing on the National Register of Historic Places (NRHP) by construction of a wireless communications tower in Benton County, Mississippi.

The site is depicted on the United States Geological Survey 7.5-minute Topographic Quadrangle "Hickory Flat, Mississippi," dated 1982. The site is located in the southwest $\frac{1}{4}$ of the northwest $\frac{1}{4}$ of Section 33, Township 5 South, Range 1 East, Benton County, Mississippi, at latitude $34^{\circ} 36' 27.350''$ north and longitude $89^{\circ} 12' 27.761''$ west (Figure 1). The site consists of a proposed 100-foot by 100-foot lease area with three associated guy anchor easements, and a proposed access road located off of Cornersville Road in Hickory Flat, Mississippi 38633. The site consists of land covered in scrub vegetation with a few scattered hardwood saplings up to three inches in diameter at breast height (dbh), and the site slopes moderately down to the west. The proposed facility access road follows an existing gravel road and extends west from Cornersville Road for approximately 1,300 feet. Proposed activities consist of construction of a 450-foot guyed communications tower and associated compound, enclosing the compound in a fence, placement of support equipment within the compound, and covering the compound with gravel. I have included the portion of the USGS topographic map depicting the proposed site location for your review.

Environmental Engineers, Inc. appreciates the opportunity to provide this information. Please reference the Environmental Engineers, Inc. project number (JSE01P1016) in correspondence regarding this site. Please provide comment within thirty days of the date of this letter. Thank you for your time and assistance and we look forward to your response. Please call me at (205) 629-3868 or email me at cstinnett@envciv.com if you have any questions or comments. You can also send a response to us via facsimile at (877) 847-3060.

Sincerely,

ENVIRONMENTAL ENGINEERS, INC.

Chad Stinnett
Senior Project Scientist

Attachments: Site Location Map

Phone: (205) 629-3868 • Fax: (877) 847-3060

Ripley Southern Sentinel, 1701 City Avenue North

Account:		Ad ID:	544023
Name:	CHERYL JOHNSON	Description:	1349 LEGAL NOTICE
Company:	ENVIROMENTAL ENGINEERS, INC.	Towers of Mississi	
Address:	11578 US HWY. 411	Run Dates:	11/11/10 to 11/11/10
Telephone:	ODENVILLE, AL 35120	Class:	1401
	(877) 852-9589	Orig User:	JLD
		Words:	156
		Lines:	47

Ad Amount Due:

\$21.72

Notes:

1349

LEGAL NOTICE


Towers of Mississippi, the State of Mississippi, and the Federal Emergency Management Agency (FEMA) are requesting comment regarding construction of a 450 guyed communications tower to be located off of Cornersville Road, Hickory Flat, Benton County, Mississippi, at latitude 34° 36' 27.4" north and longitude 89° 12' 27.8" west.

We are also requesting comment, in accordance with Section 106 of the National Historic Preservation Act (NHPA), regarding potential impacts to historical or archaeological properties listed on, or eligible for listing on the National Register of Historic Places (NRHP), by the proposed communications tower.

All comments should be submitted within 30 days of the publication of this notice referencing project JSE01P1016 and sent to the attention of Mr. Henry Fisher, Environmental Engineers, Inc., 11578 U.S. Highway 411, Odenville, AL 35120. Mr. Fisher may also be reached via email at towerinfo@envciv.com, via telephone at (205) 629-3868, or via facsimile at (877) 847-3060.

Publish dates: 11/11/10

Appendix I



ENVIRONMENTAL ENGINEERS, INC.

11578 US Highway 411, Odenville, Alabama 35120

Environmental, Remediation, and Geological Consultants

January 5, 2011

Mr. Greg Williamson
Mississippi Department of Archives and History
Charlotte Capers Archives and History Building
100 South State St.
Jackson, MS 39201

Subject:
Section 106 Review
Proposed MSWIN 30410 C Hickory Flat Communications Facility
Hickory Flat, Benton County, Mississippi
Environmental Engineers, Inc. Project No.: JSE01P1016

Dear Mr. Williamson:

Environmental Engineers, Inc. is requesting a Section 106 review, on behalf of Towers of Mississippi, the State of Mississippi, and the Federal Emergency Management Agency (FEMA) for the above referenced site. Enclosed you will find a copy of the completed FCC Form 620 for the project site, including all attachments.

Environmental Engineers, Inc. appreciates the opportunity to provide this information. Please reference the Environmental Engineers, Inc. project number (JSE01P1016) in correspondence regarding this site. If you have any questions or need additional information, please contact me at (205) 629-3868.

Sincerely,

ENVIRONMENTAL ENGINEERS, INC.

Henry A. Fisher, P.E.
Principal Engineer

Enc. FCC Form 620

Phone: (205) 629-3868 • Fax: (877) 847-3060

From: Origin ID: CZCA (205) 629-3868
HENRY FISHER
ENVIRONMENTAL ENGINEERS, INC
11578 U.S. Highway 411

Odenville, AL 35120



Ship Date: 05JAN11
ActWgt: 1.0 LB
CAD: 4760346/INET3090


Delivery Address Bar Code



Ref # JSE01P1016
Invoice #
PO #
Dept #

SHIP TO: (601) 359-6940 **BILL SENDER**
Mr. Greg Williamson
MS Dept of Archives & History
100 S STATE ST

JACKSON, MS 39201




TRK# 7966 2698 0931
0201

THU - 06 JAN A2
STANDARD OVERNIGHT

39201
MS-US
MEM

XX JANA



68AG10ET1Z78D

After printing this label:

1. Use the 'Print' button on this page to print your label to your laser or inkjet printer.
2. Fold the printed page along the horizontal line.
3. Place label in shipping pouch and affix it to your shipment so that the barcode portion of the label can be read and scanned.

Warning: Use only the printed original label for shipping. Using a photocopy of this label for shipping purposes is fraudulent and could result in additional billing charges, along with the cancellation of your FedEx account number.

Use of this system constitutes your agreement to the service conditions in the current FedEx Service Guide, available on fedex.com. FedEx will not be responsible for any claim in excess of \$100 per package, whether the result of loss, damage, delay, non-delivery, misdelivery, or misinformation, unless you declare a higher value, pay an additional charge, document your actual loss and file a timely claim. Limitations found in the current FedEx Service Guide apply. Your right to recover from FedEx for any loss, including intrinsic value of the package, loss of sales, income interest, profit, attorney's fees, costs, and other forms of damage whether direct, incidental, consequential, or special is limited to the greater of \$100 or the authorized declared value. Recovery cannot exceed actual documented loss. Maximum for items of extraordinary value is \$500, e.g. jewelry, precious metals, negotiable instruments and other items listed in our Service Guide. Written claims must be filed within strict time limits, see current FedEx Service Guide.

Cheryl Johnson

From: TrackingUpdates@fedex.com
Sent: Thursday, January 06, 2011 12:45 PM
To: cjohnson@envciv.com
Subject: FedEx Shipment 796626980931 Delivered

This tracking update has been requested by:

Company Name: ENVIRONMENTAL ENGINEERS, INC
Name: HENRY FISHER
E-mail: cjohnson@envciv.com

Our records indicate that the following shipment has been delivered:

Reference: JSE01P1016
Ship (P/U) date: Jan 5, 2011
Delivery date: Jan 6, 2011 12:38 PM
Sign for by: A.DINGVELVIH
Delivery location: RICHLAND, MS
Delivered to: Receptionist/Front Desk
Service type: FedEx Standard Overnight
Packaging type: FedEx Pak
Number of pieces: 1
Weight: 1.00 lb.
Special handling/Services: Deliver Weekday

Tracking number: 796626980931

Shipper Information	Recipient Information
HENRY FISHER	Mr. Greg Williamson
ENVIRONMENTAL ENGINEERS, INC	MS Dept of Archives & History
11578 U.S. Highway 411	100 S STATE ST
Odenville	JACKSON
AL	MS
US	US
35120	39201

Please do not respond to this message. This email was sent from an unattended mailbox. This report was generated at approximately 12:45 PM CST on 01/06/2011.

To learn more about FedEx Express, please visit our website at fedex.com.

All weights are estimated.

To track the latest status of your shipment, click on the tracking number above, or visit us at fedex.com.

This tracking update has been sent to you by FedEx on the behalf of the Requestor noted above. FedEx does not validate the authenticity of the requestor and does not validate, guarantee or warrant the authenticity of the request, the requestor's message, or the accuracy of this tracking update. For tracking results and fedex.com's terms of use, go to fedex.com.

Thank you for your business.

1/6/2011



PO Box 571, Jackson, MS 39205-0571
601-576-6850 • Fax 601-576-6975
mdah.state.ms.us
H.T. Holmes, Director

January 31, 2011

Environmental Engineers Inc.

Henry A. Fisher, P.E.
Environmental Engineers, Inc.
11578 US Highway 411
Odenville, Alabama 35120

FEB 03 2011

RECEIVED

RE: Proposed MSWIN 30410 C Telecommunications Facility in Hickory Flat
(EE Project No. JSEL01P1016), MDAH Project Log #01-024-11
(Report #11-0034), Benton County

Dear Henry:

We have reviewed your January 5, 2011, cultural resources assessment request and December 16, 2010, cultural resources survey report by Beth Ryba, Principal Investigator, received on January 6, 2011, for the above referenced undertaking, pursuant to our responsibilities under Section 106 of the National Historic Preservation Act and 36 CFR Part 800. After reviewing the information provided, we concur that no cultural resources listed in or eligible for listing in the National Register of Historic Places will be directed or visually affected. Therefore, we have no reservations with the undertaking.

There remains the possibility that unrecorded cultural resources may be encountered during the project. Should this occur, we would appreciate your contacting this office immediately in order that we may offer appropriate comments under 36 CFR 800.13.

Please provide a copy of this letter to Ms. Ryba. If you need further information, please let me know.

Sincerely,


Greg Williamson
Review and Compliance Officer

FOR: H.T. Holmes
State Historic Preservation Officer

Appendix J

Henry Fisher

From: Henry Fisher <hfisher@envciv.com>
Sent: Wednesday, January 05, 2011 4:33 PM
To: Bryant J. Celestine (celestine.bryant@actribe.org)
Subject: Proposed MSWIN 30410 C Hickory Flat Communications Facility TCNS 72320
Attachments: FCC Form 620 MSWIN 30410 TCNS 72320.pdf

Mr. Bryant Celestine
Alabama-Coushatta Tribe of Texas

Subject:
TCNS 72320
Proposed MSWIN 30410 C Hickory Flat Communications Facility
Hickory Flat, Benton County, Mississippi
Environmental Engineers, Inc. Project No.: JSE01P1016

Dear Mr. Celestine:

I am requesting comment on behalf of Towers of Mississippi, the State of Mississippi, and the Federal Emergency Management Agency (FEMA) regarding potential impacts to Native American religious or cultural sites by construction of a wireless communications tower in Benton County, Mississippi. This project was also submitted through the FCC TCNS on January 5, 2011 (TCNS ID # 72320).

The site is depicted on the United States Geological Survey 7.5-minute Topographic Quadrangle "Hickory Flat, Mississippi," dated 1982. The site is located in the southwest $\frac{1}{4}$ of the northwest $\frac{1}{4}$ of Section 33, Township 5 South, Range 1 East, Benton County, Mississippi, at latitude 34° 36' 27.350" north and longitude 89° 12' 27.761" west. The site consists of a proposed 100-foot by 100-foot lease area with three associated guy anchor easements, and a proposed access road located off of Cornersville Road in Hickory Flat, Mississippi 38633. The site consists of land covered in scrub vegetation with a few scattered hardwood saplings up to three inches in diameter at breast height (dbh), and the site slopes moderately down to the west. The proposed facility access road follows an existing gravel road and extends west from Cornersville Road for approximately 1,300 feet. Proposed activities consist of construction of a 450-foot guyed communications tower and associated compound, enclosing the compound in a fence, placement of support equipment within the compound, and covering the compound with gravel. I have attached the FCC Form 620 prepared for this project.

Environmental Engineers, Inc. appreciates the opportunity to provide this information. Please reference the Environmental Engineers, Inc. project number (JSE01P1016) in correspondence regarding this site. Thank you for your time and assistance and I look forward to your response. Please call us at (205) 629-3868 or email me at hfisher@envciv.com if you have any questions or comments. You can also send a response to us via facsimile at (877) 847-3060.

Sincerely,

Henry A. Fisher
Environmental Engineers, Inc.
11578 US Highway 411
Odenville, Alabama 35120
Tel (205) 629-3868
Fax (877) 847-3060

Henry Fisher

From: Bryant J. Celestine <celestine.bryant@actribe.org>
Sent: Wednesday, January 26, 2011 3:03 PM
To: 'Henry Fisher'
Subject: RE: Proposed MSWIN 30410 C Hickory Flat Communications Facility TCNS 72320

Dear Mr. Fisher:

On behalf of Mikko Oscola Clayton Sylestine and the Alabama-Coushatta Tribe, our appreciation is expressed on your efforts to consult us regarding TCNS #72320 (JSE01P1016) in Benton County.

Our Tribe maintains ancestral associations within the state of Mississippi despite the absence of written documentation to completely identify Tribal activities, villages, trails, or burial sites. However, it is our objective to ensure significances of Native American ancestry, especially of the Alabama-Coushatta Tribe, are administered with the utmost considerations.

Upon review of your January 5, 2010 submission, no immediately known impacts to religious, cultural, or historical assets of the Alabama-Coushatta Tribe of Texas are anticipated in conjunction with this proposal. Our review does indicate the proposed location exists in proximity to migratory routes and habitation sites utilized by ancestral members of the Alabama Tribe.

Therefore, we request the immediate notification of the inadvertent discovery of human remains and/or archaeological artifacts as well as a cease of activity in proximity to the location until all formal consultations with our office are complete. Should you require further assistance, please do not hesitate to contact us.

Sincerely,

Bryant J. Celestine
Historic Preservation Officer
Alabama-Coushatta Tribe of Texas
571 State Park Rd 56
Livingston, Texas 77351
936 - 563 - 1181
celestine.bryant@actribe.org

Henry Fisher

From: towernotifyinfo@fcc.gov
Sent: Thursday, March 03, 2011 1:34 PM
To: towerinfo@envciv.com
Cc: tcns.fccarchive@fcc.gov; gingy.nail@chickasaw.net
Subject: Reply to Proposed Tower Structure (Notification ID: 72320) - Email ID #2746066

Dear Henry A Fisher,

Thank you for using the Federal Communications Commission's (FCC) Tower Construction Notification System (TCNS). The purpose of this email is to inform you that an authorized user of the TCNS has replied to a proposed tower construction notification that you had submitted through the TCNS.

The following message has been sent to you from Historic Preservation Officer Virginia Nail of the Chickasaw Nation in reference to Notification ID #72320:

We are unaware of any specific historic properties or traditional cultural, religious and/or sacred sites at this time. However, in the event of inadvertent discoveries, we expect all construction activities to cease and we be notified according to all applicable state and federal laws.

If you have any questions, please contact Ms. Gingy Nail, historic preservation officer at (580) 559-0817, gingy.nail@chickasaw.net.

For your convenience, the information you submitted for this notification is detailed below.

Notification Received: 01/05/2011
Notification ID: 72320
Tower Owner Individual or Entity Name: Towers of Mississippi II/State of Mississippi
Consultant Name: Henry A Fisher
Street Address: 11578 U.S. Highway 411
City: Odenville
State: ALABAMA
Zip Code: 35120
Phone: 205-629-3868
Email: towerinfo@envciv.com

Structure Type: GTOWER - Guyed Tower
Latitude: 34 deg 36 min 27.4 sec N
Longitude: 89 deg 12 min 27.8 sec W
Location Description: Cornersville Road
City: Hickory Flat
State: MISSISSIPPI
County: BENTON
Ground Elevation: 139.3 meters
Support Structure: 137.2 meters above ground level
Overall Structure: 137.2 meters above ground level
Overall Height AMSL: 276.5 meters above mean sea level

Henry Fisher

From: Henry Fisher <hfisher@envciv.com>
Sent: Wednesday, January 05, 2011 4:29 PM
To: Caren Johnson (cjohnson@choctawnation.com)
Subject: Proposed MSWIN 30410 C Hickory Flat Communications Facility TCNS 72320
Attachments: FCC Form 620 MSWIN 30410 TCNS 72320.pdf

Mr. Terry Cole
Choctaw Nation of Oklahoma

Subject:
TCNS 72320
Proposed MSWIN 30410 C Hickory Flat Communications Facility
Hickory Flat, Benton County, Mississippi
Environmental Engineers, Inc. Project No.: JSE01P1016

Dear Mr. Cole:

I am requesting comment on behalf of Towers of Mississippi, the State of Mississippi, and the Federal Emergency Management Agency (FEMA) regarding potential impacts to Native American religious or cultural sites by construction of a wireless communications tower in Benton County, Mississippi. This project was also submitted through the FCC TCNS on January 5, 2011 (TCNS ID # 72320).

The site is depicted on the United States Geological Survey 7.5-minute Topographic Quadrangle "Hickory Flat, Mississippi," dated 1982. The site is located in the southwest $\frac{1}{4}$ of the northwest $\frac{1}{4}$ of Section 33, Township 5 South, Range 1 East, Benton County, Mississippi, at latitude $34^{\circ} 36' 27.350''$ north and longitude $89^{\circ} 12' 27.761''$ west. The site consists of a proposed 100-foot by 100-foot lease area with three associated guy anchor easements, and a proposed access road located off of Cornersville Road in Hickory Flat, Mississippi 38633. The site consists of land covered in scrub vegetation with a few scattered hardwood saplings up to three inches in diameter at breast height (dbh), and the site slopes moderately down to the west. The proposed facility access road follows an existing gravel road and extends west from Cornersville Road for approximately 1,300 feet. Proposed activities consist of construction of a 450-foot guyed communications tower and associated compound, enclosing the compound in a fence, placement of support equipment within the compound, and covering the compound with gravel. I have attached the FCC Form 620 prepared for this project.

Environmental Engineers, Inc. appreciates the opportunity to provide this information. Please reference the Environmental Engineers, Inc. project number (JSE01P1016) in correspondence regarding this site. Thank you for your time and assistance and I look forward to your response. Please call us at (205) 629-3868 or email me at hfisher@envciv.com if you have any questions or comments. You can also send a response to us via facsimile at (877) 847-3060.

Sincerely,

Henry A. Fisher
Environmental Engineers, Inc.
11578 US Highway 411
Odenville, Alabama 35120
Tel (205) 629-3868
Fax (877) 847-3060

Henry Fisher

From: Caren Johnson <cjohnson@choctawnation.com>
Sent: Thursday, January 13, 2011 8:25 AM
To: Henry Fisher
Subject: RE: Proposed MSWIN 30410 C Hickory Flat Communications Facility TCNS 72320

January 13, 2011

Mr. Henry Fisher:

The Choctaw Nation of Oklahoma has reviewed cell tower(s) FCC # **72320** and based on the information provided to the best of our knowledge it will have no adverse effect on any historic properties in the project's area of potential effect. However, should construction expose buried archaeological or building materials such as chipped stone, tools, pottery, bone, historic crockery, glass or metal items, or should it uncover evidence of buried historic building materials such as rock foundations, brick, or hand poured concrete, this office should be contacted immediately @ 1-800-522-6170 ext. 2137.

Sincerely,

*Caren Johnson
Administrative Assistant
Choctaw Nation of Oklahoma
P. O. Box 1210
Durant, OK 74702-1210
1-580-924-8280 Ext. 2133
Fax 1-580-920-3181*

From: Henry Fisher [mailto:hfisher@envciv.com]
Sent: Wednesday, January 05, 2011 4:29 PM
To: Caren Johnson
Subject: Proposed MSWIN 30410 C Hickory Flat Communications Facility TCNS 72320

Mr. Terry Cole
Choctaw Nation of Oklahoma

Subject:
TCNS 72320
Proposed MSWIN 30410 C Hickory Flat Communications Facility
Hickory Flat, Benton County, Mississippi
Environmental Engineers, Inc. Project No.: JSE01P1016

Dear Mr. Cole:

I am requesting comment on behalf of Towers of Mississippi, the State of Mississippi, and the Federal Emergency Management Agency (FEMA) regarding potential impacts to Native American religious or cultural sites by construction of a wireless communications tower in Benton County, Mississippi. This project was also submitted through the FCC TCNS on January 5, 2011 (TCNS ID # 72320).

The site is depicted on the United States Geological Survey 7.5-minute Topographic Quadrangle "Hickory Flat, Mississippi," dated 1982. The site is located in the southwest ¼ of the northwest ¼ of Section 33, Township 5 South, Range 1 East, Benton County, Mississippi, at latitude 34° 36' 27.350" north and longitude 89° 12' 27.761" west. The site

consists of a proposed 100-foot by 100-foot lease area with three associated guy anchor easements, and a proposed access road located off of Cornersville Road in Hickory Flat, Mississippi 38633. The site consists of land covered in scrub vegetation with a few scattered hardwood saplings up to three inches in diameter at breast height (dbh), and the site slopes moderately down to the west. The proposed facility access road follows an existing gravel road and extends west from Cornersville Road for approximately 1,300 feet. Proposed activities consist of construction of a 450-foot guyed communications tower and associated compound, enclosing the compound in a fence, placement of support equipment within the compound, and covering the compound with gravel. I have attached the FCC Form 620 prepared for this project.

Environmental Engineers, Inc. appreciates the opportunity to provide this information. Please reference the Environmental Engineers, Inc. project number (JSE01P1016) in correspondence regarding this site. Thank you for your time and assistance and I look forward to your response. Please call us at (205) 629-3868 or email me at hfisher@envciv.com if you have any questions or comments. You can also send a response to us via facsimile at (877) 847-3060.

Sincerely,

Henry A. Fisher
Environmental Engineers, Inc.
11578 US Highway 411
Odenville, Alabama 35120
Tel (205) 629-3868
Fax (877) 847-3060

This message is intended only for the use of the individual or entity to which it is addressed and may contain information that is privileged, confidential and exempt from disclosure. If you have received this message in error, you are hereby notified that we do not consent to any reading, dissemination, distribution, or copying of this message. If you have received this communication in error, please notify the sender immediately and destroy the transmitted information. Please note that any view or opinions presented in this email are solely those of the author and do not necessarily represent those of the C-Flaw Nation.

Henry Fisher

From: Earl Barbry, Jr. [earlji@tunica.org]
Sent: Tuesday, May 03, 2005 5:51 PM
To: Henry Fisher
Cc: Niki Jeter
Subject: Re: HELP! - I am stuck in FCC NPA!

Mr. Fisher,

Sorry about the delay. I would like to be notified of the cell tower requests, etc. by email. Also, should no comments be received from my department within the 30 day comment period, proceeding with the project can occur. I stand the same as the other Tribes regarding immediate work stoppage and contacting this office should inadvertent discovery occur.

Thank you for taking the time to contact me and getting my input into these matters. Let me know if this response is sufficient or if you need a letter on Tribal stationary mailed to you.

Should you need immediate assistance, and I am out of the office, speak to my Administrative Assistant, Ms. Amber (Niki) Jeter - dial the number below and hit 0 to speak to her.

Many thanks,

Earl J. Barbry, Jr., THPO
Tunica-Biloxi Tribe of Louisiana
318-253-0213 ext. 6851

Henry Fisher

From: Henry Fisher <hfisher@envciv.com>
Sent: Wednesday, January 05, 2011 4:28 PM
To: earlii@tunica.org
Subject: Proposed MSWIN 30410 C Hickory Flat Communications Facility TCNS 72320

Mr. Earl Barbry
Tunica-Biloxi Indians of Louisiana

Subject:
TCNS 72320
Proposed MSWIN 30410 C Hickory Flat Communications Facility
Hickory Flat, Benton County, Mississippi
Environmental Engineers, Inc. Project No.: JSE01P1016

Dear Mr. Barbry:

I am requesting comment on behalf of Towers of Mississippi, the State of Mississippi, and the Federal Emergency Management Agency (FEMA) regarding potential impacts to Native American religious or cultural sites by construction of a wireless communications tower in Benton County, Mississippi. This project was also submitted through the FCC TCNS on January 5, 2011 (TCNS ID # 72320).

The site is depicted on the United States Geological Survey 7.5-minute Topographic Quadrangle "Hickory Flat, Mississippi," dated 1982. The site is located in the southwest ¼ of the northwest ¼ of Section 33, Township 5 South, Range 1 East, Benton County, Mississippi, at latitude 34° 36' 27.350" north and longitude 89° 12' 27.761" west. The site consists of a proposed 100-foot by 100-foot lease area with three associated guy anchor easements, and a proposed access road located off of Cornersville Road in Hickory Flat, Mississippi 38633. The site consists of land covered in scrub vegetation with a few scattered hardwood saplings up to three inches in diameter at breast height (dbh), and the site slopes moderately down to the west. The proposed facility access road follows an existing gravel road and extends west from Cornersville Road for approximately 1,300 feet. Proposed activities consist of construction of a 450-foot guyed communications tower and associated compound, enclosing the compound in a fence, placement of support equipment within the compound, and covering the compound with gravel.

Environmental Engineers, Inc. appreciates the opportunity to provide this information. Please reference the Environmental Engineers, Inc. project number (JSE01P1016) in correspondence regarding this site. Thank you for your time and assistance. Based on the electronic mail that you sent to our office on May 3, 2005 it is my understanding that we may assume that the Tunica-Biloxi Indians of Louisiana concurs with the proposed project if we have not received a comment from your office within 30 days of submittal of project information to your office via electronic mail. Please call us at (205) 629-3868 or email me at hfisher@envciv.com if you have any questions or comments. You can also send a response to us via facsimile at (877) 847-3060.

Sincerely,

Henry A. Fisher
Environmental Engineers, Inc.
11578 US Highway 411
Odenville, Alabama 35120
Tel (205) 629-3868
Fax (877) 847-3060

Appendix K



ENVIRONMENTAL ENGINEERS, INC.

11578 US Highway 411, Odenville, Alabama 35120

Environmental, Remediation, and Geological Consultants

November 23, 2010

Mr. Slade Lindsay
Towers of Mississippi
State of Mississippi
31560 Blakely Way
Spanish Fort, Alabama 36532

Subject:

**Phase I Environmental Site Assessment
Proposed MSWIN 30410 C Hickory Flat Communications Facility
Hickory Flat, Benton County, Mississippi**
Environmental Engineers, Inc. Project No.: JSE01P1016

Dear Mr. Lindsay:

Environmental Engineers, Inc. has completed the requested Phase I Environmental Site Assessment (ESA) for the subject parcel. The enclosed report describes our study and presents our findings.

Environmental Engineers, Inc. appreciates the opportunity to provide this assessment. If you have any questions regarding this report or if we may be of further service to you, please contact us at (205) 629-3868.

Sincerely,

ENVIRONMENTAL ENGINEERS, INC.

Chad Stinnett
Senior Project Scientist

Enc. Phase I ESA Report (3 copies)

Cc w enc. Mr. Taylor Robinson, Towers of Mississippi (electronic copy)
Ms. Nancy Lindsay, Towers of Mississippi (electronic copy)

Phone: (205) 629-3868 • Fax: (877) 847-3060



ENVIRONMENTAL ENGINEERS, INC.

11578 US Highway 411, Odenville, Alabama 35120

Environmental, Remediation, and Geological Consultants

PHASE I ENVIRONMENTAL SITE ASSESSMENT
Proposed MSWIN 30410 C Hickory Flat Communications Facility
Hickory Flat, Benton County, Mississippi
Environmental Engineers, Inc. Project No.: JSE01P1016

Prepared for:
Towers of Mississippi
State of Mississippi
Spanish Fort, Alabama

November 23, 2010

Prepared by:
ENVIRONMENTAL ENGINEERS, INC.

Chad Stinnett
Senior Project Scientist

Anne B. Gilbert, P.E.
Principal Engineer

Phone: (205) 629-3868 • Fax: (877) 847-3060

TABLE OF CONTENTS

EXECUTIVE SUMMARY	I
1.0 INTRODUCTION	1
1.1 PURPOSE.....	1
1.2 CERTIFICATION	1
1.3 SITE LOCATION	1
2.0 SUMMARY OF PREVIOUS ENVIRONMENTAL SITE ASSESSMENTS	2
3.0 CURRENT SITE CHARACTERISTICS	2
3.1 SITE DESCRIPTION AND OPERATIONS	2
3.2 SITE RECONNAISSANCE.....	2
3.3 SITE UTILITIES	2
3.4 ADDITIONAL SITE INFORMATION	2
3.4.1 Hydrology	2
3.4.2 Geology	3
3.4.3 Soils.....	3
4.0 CURRENT AREA CHARACTERISTICS	3
4.1 ADJACENT PROPERTIES	3
4.2 PROPERTIES WITHIN 1,000-FOOT RADIUS	3
4.3 AREA UTILITIES.....	4
4.4 AREA GEOLOGY AND HYDROLOGY	4
5.0 SITE HISTORY – 1909 TO PRESENT	4
5.1 PROPERTY OWNERSHIP HISTORY	4
5.2 AERIAL PHOTOGRAPHS.....	5
5.3 SANBORN FIRE INSURANCE MAPS.....	5
5.4 OTHER HISTORICAL MAPS	5
5.5 SITE INTERVIEWS	5
6.0 AREA HISTORY – 1974 TO PRESENT	6
6.1 AERIAL PHOTOGRAPHS.....	6
6.2 SANBORN FIRE INSURANCE MAPS.....	6
6.3 OTHER HISTORICAL MAPS	6



7.0 ENVIRONMENTAL REGULATORY INFORMATION.....	6
7.1 SITE ENVIRONMENTAL REGULATORY INFORMATION	6
7.2 GEOCODED SITES.....	6
7.3 NON-GEOCODED SITES.....	6
7.4 REGULATORY INTERVIEWS.....	7
8.0 ASTM/AAI USER QUESTIONNAIRE	7
9.0 CONCLUSIONS AND RECOMMENDATIONS	9
10.0 REFERENCES / INFORMATION SOURCES	9
11.0 SPECIAL TERMS AND CONDITIONS.....	10

FIGURES

- Figure 1 Site Location Map
- Figures 2-9 Site Photographs

APPENDICES

- Appendix A Personnel Qualifications
- Appendix B Aerial Photographs
- Appendix C Report on Environmentally Regulated Facilities
- Appendix D General Conditions



EXECUTIVE SUMMARY

Mr. Taylor Robinson of Towers of Mississippi authorized a Phase I Environmental Site Assessment (ESA) for a proposed telecommunications facility located off of Cornersville Road in Hickory Flat, Mississippi. The Phase I study included the following services:

- a site reconnaissance to look for visual evidence of potential contamination;
- evaluation of land uses on surrounding properties which may have affected the project site;
- a general reconnaissance within a one-mile radius of the project site;
- review of specific environmental regulatory listings;
- review of available aerial photographs and historical records;
- review of published literature concerning site area geology, soils, and hydrology; and
- preparation of this report.

The site consists of a proposed 100-foot by 100-foot lease area with three associated guy anchor easements, and an access road located off of Cornersville Road in Hickory Flat, Mississippi 38633. The site consists of land covered in scrub vegetation with a few scattered hardwood saplings up to three inches in diameter at breast height (dbh), and the site slopes moderately down to the west. The proposed facility access road follows an existing gravel road and extends west from Cornersville Road for approximately 1,300 feet. Proposed activities consist of construction of a 400-foot guyed communications tower and associated compound, enclosing the compound in a fence, placement of support equipment within the compound, and covering the compound with gravel.

Environmental Engineers, Inc. performed a *Phase I Environmental Site Assessment* in conformance with the scope and limitations of ASTM Standard Practice E 1527-05 of the proposed MSWIN 30410 C Hickory Flat Communications Facility located off of Cornersville Road in Hickory Flat, Mississippi, the *property*. This assessment has revealed no evidence of on- or off-site *recognized environmental conditions* in connection with the *property*. Based on the results of this assessment, Environmental Engineers, Inc. does not recommend further assessment of site soils or groundwater at this time.

It should be noted that this section is only intended to represent a brief summary of our findings, and is not a detailed account of all the information compiled in preparation of this report. The report should be reviewed in its entirety prior to drawing any final conclusions as to potential environmental conditions associated with the site.



1.0 INTRODUCTION

1.1 PURPOSE

The purpose of this environmental assessment is to investigate and identify *recognized environmental conditions* associated with the site and/or surrounding property. *Recognized environmental conditions*, as defined in the American Society for Testing and Materials (ASTM) Standard Practice E1527-05, include the following:

“The presence or likely presence of any *hazardous substances* or *petroleum products* on a *property* under conditions that indicate an existing release, a past release, or a material threat of a release of any *hazardous substances* or *petroleum products* into structures on the *property* or into the ground, groundwater, or surface water of the *property*. The term includes *hazardous substances* or *petroleum products* even under conditions in compliance with laws. The term is not intended to include *de minimus* conditions that generally do not present a material risk of harm to public health or the environment and that generally would not be the subject of an enforcement action if brought to the attention of appropriate governmental agencies.”

1.2 CERTIFICATION

Environmental Engineers, Inc. declares that, to the best of our professional knowledge and belief, we meet the definition of Environmental Professional as defined in §312.10 of 40 CFR 312. Environmental Engineers, Inc. has the specific qualifications based on education, training, and experience to assess a property of the nature, history, and setting of the subject property. We have developed and performed all the appropriate inquiries in conformance with the standards and practices set forth in 40 CFR Part 312. We have included the qualifications for the Environmental Engineers, Inc. personnel that participated in this assessment as Appendix A.

1.3 SITE LOCATION

The site is depicted on the United States Geological Survey 7.5-minute Topographic Quadrangle “Hickory Flat, Mississippi,” dated 1982. The site is located in the southwest ¼ of the northwest ¼ of Section 33, Township 5 South, Range 1 East, Benton County, Mississippi, at latitude 34° 36’ 27.350” north and longitude 89° 12’ 27.761” west (Figure 1).

This site is referred to as the proposed MSWIN 30410 C Hickory Flat Communications Facility and is located off of Cornersville Road in Hickory Flat, Mississippi. The current property owners are listed by the Benton County Tax Assessor’s Office as Ricky and Clare Pipkin, and the tax number for the parcel containing the site is 1-0560-33-000-014.01.



2.0 SUMMARY OF PREVIOUS ENVIRONMENTAL SITE ASSESSMENTS

Environmental Engineers, Inc. is unaware of any previous environmental assessments of the site.

3.0 CURRENT SITE CHARACTERISTICS

3.1 SITE DESCRIPTION AND OPERATIONS

The site consists of a proposed 100-foot by 100-foot lease area with three associated guy anchor easements, and an proposed access road located off of Cornersville Road in Hickory Flat, Mississippi 38633. The site consists of land covered in scrub vegetation with a few scattered hardwood saplings up to three inches in diameter at breast height (dbh), and the site slopes moderately down to the west. The proposed facility access road follows an existing gravel road and extends west from Cornersville Road for approximately 1,300 feet. Proposed activities consist of construction of a 400-foot guyed communications tower and associated compound, enclosing the compound in a fence, placement of support equipment within the compound, and covering the compound with gravel.

3.2 SITE RECONNAISSANCE

Environmental Engineers, Inc. conducted a site reconnaissance on November 9, 2010. The purpose of this visit was to observe the property and adjacent properties for evidence of *recognized environmental conditions*, as stated in Section 1.1. Site photographs are included as Figures 2 through 9.

No evidence of aboveground or underground storage tanks (ASTs/USTs), buckets, transformers, stained soil, stressed vegetation, pits, ponds, lagoons, or noxious odors were noted at the site.

An empty 55-gallon drum was noted on the site, but no stained soil was noted on the ground surrounding the drum. Two metal culverts and a section of railroad tracks and railroad ties were also noted on the site.

3.3 SITE UTILITIES

No utilities were observed on the site.

3.4 ADDITIONAL SITE INFORMATION

3.4.1 Hydrology

Based on topographic interpretation, surface water runoff from the site is expected to flow generally north and west toward unnamed tributaries of Oaklimer Creek. Groundwater beneath the site is inferred to flow toward the northwest and may be present at perhaps greater than 20 feet below ground surface (bgs).



3.4.2 Geology

According to the Mississippi Geological Survey, Geologic Map of Mississippi, dated 1969 and reprinted 1985, the site is underlain by the Wilcox Formation of Tertiary Age. The Wilcox Formation consist of irregularly bedded fine to coarse sand, more or less lignitic clay, and lignite; includes bauxite bearing Fearn Springs sand member at base.

3.4.3 Soils

Based on information available in the USDA's Soil Survey of Benton County, Mississippi issued January 1977, site soils are classified as Sweatman-Smithdale association, hilly. This association consists of well-drained soils on hilly uplands with slopes ranging from 17 to 45 percent.

Sweatman soils typically have a mixed very dark grayish-brown and brown silt loam about three inches thick. The subsurface layer is a mixture of brown and yellowish-red silt loam about two inches thick. The upper 23 inches of the subsoil is red clay. The lower part of the subsoil is red clay with shale fragments to a depth of 37 inches. The substratum is dark red clay loam with thin layers of light gray and brownish-yellow weathered shale to a depth of 47 inches and stratified light gray and red clay to a depth of 65 inches.

Smithdale soils typically have a surface layer of thin brown fine sandy loam about three inches thick that overlies a subsurface layer of yellowish-brown sandy loam about six inches thick. The subsoil extends to about 70 inches and is comprised of sandy loam and clay loam.

It should be noted that information listed in Section 3.4 of this report is for the general area of the site, and is not intended as a substitute for site-specific geotechnical and/or hydrological information.

4.0 CURRENT AREA CHARACTERISTICS

4.1 ADJACENT PROPERTIES

Properties adjacent to the site were observed to determine if there was any visible evidence of off-site land uses that might adversely affect the site. The adjacent properties to the north and west contain wooded land. The adjacent property to the east contains gravel stockpiles and several types of heavy equipment utilized by Benton County Public Works. The adjacent property to the south contains an unimproved dirt access road and scrub vegetation.

4.2 PROPERTIES WITHIN 1,000-FOOT RADIUS

Properties within a 1,000-foot radius of the site were observed to determine if there was any visible evidence of off-site land uses that might adversely affect the site. The properties surrounding the site in each direction are listed below:



North: Wooded land and agricultural fields

East: Benton County Public Works equipment storage, a single family residence, and multiple equipment barns with three active ASTs

Minor amounts of petroleum staining was noted on the ASTs east of the site and on the ground surrounding the ASTs. Based on the observed stained ground limits and the distance to the proposed site, it is unlikely that these ASTs have adversely affected site soils or groundwater.

No petroleum staining or stressed vegetation were noted surrounding the inoperable fuel pumps or fuel truck south of the site.

South: Multiple storage trailers, inoperable fuel pumps, an inoperable fuel truck, and wooded land

West: Wooded land and manmade pond

4.3 AREA UTILITIES

According to Mr. Ricky Pipkin, current site owner, electrical service in the area of the site is provided by Northeast Mississippi Power and telephone service is provided by AT&T.

4.4 AREA GEOLOGY AND HYDROLOGY

According to the Mississippi Geological Survey, Geologic Map of Mississippi, dated 1969 and reprinted 1985, the area surrounding the site is underlain by the Wilcox Formation of Tertiary Age. The Wilcox Formation consist of irregularly bedded fine to coarse sand, more or less lignitic clay, and lignite; includes bauxite bearing Fearn Springs sand member at base.

Based on topographic interpretation, surface water runoff and groundwater beneath the area surrounding the site are expected to flow toward unnamed tributaries of Oaklimeter Creek.

5.0 SITE HISTORY – 1909 TO PRESENT

5.1 PROPERTY OWNERSHIP HISTORY

Property ownership information was reviewed in an effort to determine past ownership of the site. Property ownership information available at the Benton County Courthouse in Ashland, Mississippi is listed in the table on the following page. It should be noted that this information does not constitute a formal chain-of-title.



Property Ownership Information	
Years of Ownership	Property Owner
2002 - present	Ricky and Clare Pipkin
1997 - 2002	Joe and Irene Pipkin
1992 - 1997	Ricky and Clare Pipkin
1976 - 1992	Mack and Darlene Thompson
1965 - 1976	V.W. Scott
1948 - 1965	J.E. and Leon Dickerson
1948	Joseph Beachum and M.C. Simpson
1947 - 1948	C.L. Whiteside
1909 - 1947	S.A. Whaley and Heirs
Prior to 1909	S.E. Holcombe

5.2 AERIAL PHOTOGRAPHS

Aerial photographs dated 1974, 1992, 1996, 2006, and 2009 including the subject site were examined. The 1974 and 1992 aerial photographs depict the site as wooded land. The 1996 through 2009 aerial photographs depict the site as cleared and vacant with a surrounding infrastructure of unimproved access roads. Copies of the portions of the aerial photographs depicting the site are included in Appendix B.

5.3 SANBORN FIRE INSURANCE MAPS

The site is located outside the limits covered by Sanborn Fire Insurance Maps.

5.4 OTHER HISTORICAL MAPS

A review of the USGS 7.5-minute topographic quadrangle “Hickory Flat, Mississippi,” dated 1982 depicts the site as wooded land.

5.5 SITE INTERVIEWS

A telephone interview was conducted with Mr. Ricky Pipkin, current property owner, regarding ownership and past use of the site. Mr. Pipkin said that he has owned the property containing the site since 1992 and the property was wooded and undeveloped when he purchased it. Mr. Pipkin stated that the three identified ASTs were the only fuel or chemicals stored on the site and there has never been any spills related to those ASTs. Mr. Pipkin said that there have never been any structures on the site, and the adjacent gravel piles and equipment is a staging area for Benton County Public Works. Mr. Pipkin stated that the identified fuel truck has been empty since the 1960’s and the gas pumps were placed at the site after being removed from operation many years ago. According to Mr. Pipkin, the storage trailers to the south of the site contain primarily hand tools.



6.0 AREA HISTORY – 1974 TO PRESENT

6.1 AERIAL PHOTOGRAPHS

Aerial photographs dated 1974, 1992, 1996, 2006, and 2009 including properties surrounding the site were examined. The portions of the aerial photographs examined are included in Appendix B.

The 1974 and 1992 aerial photographs depict all surrounding properties to be wooded land. The 1996 aerial photograph depicts the surrounding properties as recently cleared land with an infrastructure of unimproved access roads. The 2006 and 2009 aerial photographs depict the surrounding properties to be cleared with the storage trailers present to the south and equipment present to the east with the equipment barn and single-family residence visible farther to the east.

6.2 SANBORN FIRE INSURANCE MAPS

The area surrounding the site is located outside the limits covered by Sanborn Fire Insurance Maps.

6.3 OTHER HISTORICAL MAPS

A review of the USGS 7.5-minute topographic quadrangle “Hickory Flat, Mississippi,” dated 1982 depicts the property surrounding the site as being wooded land with open fields farther to the north.

7.0 ENVIRONMENTAL REGULATORY INFORMATION

Federal and state environmental regulatory records were reviewed by Environmental Engineers, Inc. to determine the environmental regulatory status of facilities identified within specific distances of the subject site. The databases reviewed and search radii for each database are designated by the ASTM Standard Practice E1527-05. FirstSearch Technology Corporation (FirstSearch) compiled this information (Appendix C). Descriptions of the acronyms used for each database are presented in the FirstSearch report.

7.1 SITE ENVIRONMENTAL REGULATORY INFORMATION

The subject site is not listed on any existing federal or state environmental regulatory databases.

7.2 GEOCODED SITES

FirstSearch identified no facilities as being located within the search radii designated by ASTM.

7.3 NON-GEOCODED SITES

Due to inadequate address or other facility identifier information, FirstSearch could not plot some of the facilities contained within the federal and state databases on a map. However, these facilities are



identified in the list of non-geocoded sites provided by FirstSearch. This summary was reviewed by Environmental Engineers, Inc. to determine if any of the facilities on or surrounding the site was included on this list. The review indicated the facilities listed as non-geocoded were located outside the ASTM search distances of the site or were not topographically upgradient of the site.

7.4 REGULATORY INTERVIEWS

Several attempts were made to contact the Benton County Emergency Management Agency (EMA) and the Hickory Flat Volunteer Fire Department regarding information on any known hazardous material or other environmental emergency responses in the area of the site. However, no one was reached during the time frame allotted for this investigation.

8.0 ASTM/AAI USER QUESTIONNAIRE

According to the ASTM E1527-05/EPA All Appropriate Inquiry (AAI) Standard, in order to qualify for one of the Landowner Liability Protections (LLPs) offered by the Small Business Liability Relief and Brownfields Revitalization Act of 2001 (the “Brownfields Amendments”), the user must provide the following information (if available) to the environmental professional. Failure to provide this information could result in a determination that “all appropriate inquiry” is not complete.

Environmental Engineers, Inc. contacted Mr. Taylor Robinson of Towers of Mississippi to provide the required information. The ASTM/AAI user questionnaire and Mr. Robinson’s answers are summarized in the following paragraphs.

(1.) Environmental cleanup liens that are filed or recorded against the site (40 CFR 312.25).

Are you aware of any environmental cleanup liens against the *property* that are filed or recorded under federal, tribal, state or local law?

Mr. Robinson indicated that he was not aware of any such liens.

(2.) Activity and land use limitations that are in place on the site or that have been filed or recorded in a registry (40 CFR 312.26).

Are you aware of any AULS, such as *engineering controls*, land use restrictions or *institutional controls* that are in place at the site and/or have been filed or recorded in a registry under federal, tribal, state or local law?

Mr. Robinson indicated that he was not aware of any land use limitations at the site.

(3.) Specialized knowledge or experience of the person seeking to qualify for the LLP (40 CFR 312.28).

As the *user* of this *ESA* do you have any specialized knowledge or experience related to the *property* or nearby properties? For example, are you involved in the same line of business as the



current or former *occupants* of the *property* or an adjoining *property* so that you would have specialized knowledge of the chemicals and processes used by this type of business?

Mr. Robinson indicated that he did not have specialized knowledge or experience related to the property or nearby properties.

(4.) Relationship of the purchase price to the fair market value of the *property* if it were not contaminated (40 CFR 312.29).

Does the purchase price being paid for this *property* reasonably reflect the fair market value of the *property*? If you conclude that there is a difference, have you considered whether the lower purchase price is because contamination is known or believed to be present at the *property*?

Mr. Robinson indicated that there was only a leasehold interest in the property, which is at fair market value for the purposes they intend.

(5.) Commonly known or *reasonably ascertainable* information about the *property* (40 CFR 312.30).

Are you aware of commonly known or *reasonably ascertainable* information about the *property* that would help the *environmental professional* to identify conditions indicative of releases or threatened releases? For example, as *user*,

(a). Do you know the past users of the *property*?

Mr. Robinson stated that he was unaware of the past user of the property.

(b). Do you know of specific chemicals that are present or once were present at the *property*?

Mr. Robinson indicated that he was not aware of specific chemicals formerly or currently present on the property.

(c). Do you know of spills or other chemical releases that have taken place at the *property*?

Mr. Robinson indicated he was not aware of spills or other chemical releases on the property.

(d). Do you know of any environmental cleanups that have taken place at the *property*?

Mr. Robinson indicated that he was unaware if any environmental cleanup had occurred at the site in the past.

(6.) The degree of obviousness of the presence or likely presence of contamination at the property, and the ability to detect the contamination by appropriate investigation (40 CFR 312.31).



As the *user* of this *ESA*, based on your knowledge and experience related to the *property* are there any *obvious* indicators that point to the presence or likely presence of contamination at the *property*?

Mr. Robinson indicated that he was not aware of any obvious indicators that point to the presence or likely presence of contamination at the property.

9.0 CONCLUSIONS AND RECOMMENDATIONS

Environmental Engineers, Inc. performed a *Phase I Environmental Site Assessment* in conformance with the scope and limitations of ASTM Standard Practice E 1527-05 of the proposed MSWIN 30410 C Hickory Flat Communications Facility located off of Cornersville Road in Hickory Flat, Mississippi, the *property*. This assessment has revealed no evidence of on- or off-site *recognized environmental conditions* in connection with the *property*. Based on the results of this assessment, Environmental Engineers, Inc. does not recommend further assessment of site soils or groundwater at this time.

10.0 REFERENCES / INFORMATION SOURCES

Research and evaluation of the environmental conditions at the site and surrounding properties included utilization of the following sources:

1. Geologic information published by the United States Geological Survey and the Geological Survey of Mississippi.
2. USGS 7.5-minute Topographic Quadrangle "Hickory Flat, Mississippi," dated 1982.
3. Soil information and an aerial photograph available in the USDA's Soil Survey of Benton County, Mississippi issued January 1977.
4. Property ownership information and deed records available at the Benton County Courthouse in Ashland, Mississippi.
5. Aerial photographs available at Google Earth and the Mapcard.com Internet website.
6. Review of environmental regulatory report for the site prepared by FirstSearch Technology Corporation, having Project Number JSE01P1016 and dated November 12, 2010.
7. Telephone interview with Mr. Ricky Pipkin, current site owner, regarding past history and use of the site and local utility providers.
8. Review of AAI Questionnaire results provided by Mr. Taylor Robinson of Towers of Mississippi.



11.0 SPECIAL TERMS AND CONDITIONS

This Phase I ESA has been conducted in accordance with the ASTM *Standard Practice for Environmental Site Assessments: Phase I Site Assessment Process*, designation E1527-05.

Historical and environmental information pertaining to the subject site has been included in this report to the extent that such information is “publicly available” and “practically reviewable,” as defined in the above-referenced standard practice manual, within reasonable time and monetary constraints.

Conclusions stated herein are based upon publicly available information and other documented sources. Environmental Engineers, Inc. assumes no responsibility for inaccurate information that is not otherwise obvious in light of information of which Environmental Engineers, Inc. has actual knowledge.

Services not within the scope of this study include, but are not limited to, the following:


- an investigation of mining structures under the project site;
- an investigation of potential asbestos-containing materials at the site;
- an investigation for potential jurisdictional wetlands on the site;
- an investigation for potential mold in any onsite structures;
- an investigation of the likelihood of sinkhole activity around the site; and
- an investigation for the presence of unacceptable levels of radon-producing elements in surface soils on the project site.

This report may be relied upon by Towers of Mississippi, the State of Mississippi, and their lenders, subject to the terms and conditions included as Appendix D. No other person may rely on this report without written authorization from Environmental Engineers, Inc.

This assessment is intended to reduce, not eliminate, the level of environmental uncertainty associated with the site. Environmental Engineers, Inc. is not responsible for the conclusions made by others based on this assessment.



Figures



Environmental Engineers, Inc.

Subject:
 Phase I Environmental Site Assessment
 Proposed MSWIN 30410 C Hickory Flat Communications Facility
 Hickory Flat, Benton County, Mississippi
 Environmental Engineers, Inc. Project No.: JSE01P1016

Figure 1
 Site Location Map
 Scale: 1" ≈ 2000'





View from the center of the site looking toward the north.



View from the center of the site looking toward the east.

Environmental Engineers, Inc.

Subject:
Phase I Environmental Site Assessment
Proposed MSWIN 30410 C Hickory Flat Communications Tower
Hickory Flat, Benton County, Mississippi
Project No.: JSE01P1016

Figure 2
Site Photographs





View from the center of the site looking toward the south.



View from the center of the site looking toward the west.

Environmental Engineers, Inc.

Subject:
Phase I Environmental Site Assessment
Proposed MSWIN 30410 C Hickory Flat Communications Tower
Hickory Flat, Benton County, Mississippi
Project No.: JSE01P1016

Figure 3
Site Photographs





View from the northern guy anchor looking toward the site.



View from the southwestern guy anchor looking toward the site.

Environmental Engineers, Inc.

Subject:
Phase I Environmental Site Assessment
Proposed MSWIN 30410 C Hickory Flat Communications Tower
Hickory Flat, Benton County, Mississippi
Project No.: JSE01P1016

Figure 4
Site Photographs





Overall view across the site looking toward the east.



View of the existing access road looking east from the site.

Environmental Engineers, Inc.

Subject:
Phase I Environmental Site Assessment
Proposed MSWIN 30410 C Hickory Flat Communications Tower
Hickory Flat, Benton County, Mississippi
Project No.: JSE01P1016

Figure 5
Site Photographs





View of the existing access road looking west toward the site.



View of the empty 55-gallon drum on the site.

Environmental Engineers, Inc.

Subject:
Phase I Environmental Site Assessment
Proposed MSWIN 30410 C Hickory Flat Communications Tower
Hickory Flat, Benton County, Mississippi
Project No.: JSE01P1016

Figure 6
Site Photographs





View of the section of railroad tracks on the site.



View of the metal culverts on the site.

Environmental Engineers, Inc.

Subject:
Phase I Environmental Site Assessment
Proposed MSWIN 30410 C Hickory Flat Communications Tower
Hickory Flat, Benton County, Mississippi
Project No.: JSE01P1016

Figure 7
Site Photographs





Views of the inoperable fuel pumps and fuel truck south of the site.



Environmental Engineers, Inc.

Subject:
Phase I Environmental Site Assessment
Proposed MSWIN 30410 C Hickory Flat Communications Tower
Hickory Flat, Benton County, Mississippi
Project No.: JSE01P1016

Figure 8
Site Photographs





Views of the active ASTs east of the site.



Environmental Engineers, Inc.

Subject:
Phase I Environmental Site Assessment
Proposed MSWIN 30410 C Hickory Flat Communications Tower
Hickory Flat, Benton County, Mississippi
Project No.: JSE01P1016

Figure 9
Site Photographs



Appendix A

Chad Stinnett

Senior Project Scientist

EXPERTISE:

Responsible for activities related to US Army Corps of Engineers (USACE) jurisdictional areas. Extensive experience conducting USACE standard wetland delineations and forensic wetland delineations. Broad knowledge related to planning and conducting USACE permitting activities and USACE compensatory mitigation.

Experience conducting soil/groundwater sampling and site remediation activities along with many years of experience conducting NPDES inspections, permitting, and sampling.

Experience conducting Phase I Environmental Site Assessments and completing National Environmental Policy Act Assessments.

PROJECT EXPERIENCE:

- Performed wetland delineations throughout the States of Alabama, Florida, Georgia, and Mississippi.
- Conducted and managed US Army Corps of Engineers permitting for residential, commercial, and governmental projects.
- Implemented and maintained US Army Corps of Engineers compensatory stream and wetland mitigation areas throughout Alabama.
- Performed numerous protected terrestrial species surveys throughout Alabama, Florida, and Mississippi.
- Conducted and managed complete EA's for sites in Jefferson, Shelby, and St. Clair counties in Alabama.
- Performed NPDES compliance inspections, permitting, and sampling for construction sites in Chilton, Jefferson, Shelby, St. Clair, and Tuscaloosa counties in Alabama.
- Conducted and managed the efficient operation of groundwater remediation systems throughout Alabama.
- Conducted and managed Phase I Environmental Site Assessments for real estate transactions throughout Alabama, Florida, Louisiana, and Mississippi.

EMPLOYMENT HISTORY:

Staff Scientist, Spectrum Environmental, Inc. Alabaster, AL
06/2004 - 09/2007

Natural Resources Manager, Spectrum Environmental, Inc. Alabaster, Alabama
09/2007 – 03/2010

Senior Project Scientist, Environmental Engineers, Inc. Odenville, Alabama
03/2010 - Present

EDUCATION:

Bachelor of Science in Environmental Science, 2003 from Auburn University.

CERTIFICATIONS:

Qualified Credentialed Stormwater Inspector, 2005
Wetland Delineation and Management, 2005
40-Hour OSHA Training, 2004

Anne B. Gilbert, P.E.
President/Principal Engineer

EXPERTISE:

Responsible for Phase I and Phase II Environmental Site Assessments, UST Closure Assessments, UST site investigations, preparation of a Confirmatory Sampling Workplan for a RCRA facility, Confirmatory Sampling at a RCRA facility, groundwater and soil sampling, development of Best Management Practices Plans for industrial facilities and construction sites, NPDES compliance inspections and sampling for both industrial and construction sites, and management and supervision of over 40 local stormwater facilities as well as 700 locations for Jefferson County. Responsible for preparation of Asbestos Abatement Plans for schools and commercial and industrial facilities. Responsible for Asbestos Surveys at schools and commercial, industrial, and residential sites.

Geotechnical Investigations including laboratory testing and engineering analysis.

Preparation of Toxic Release Chemical Inventory Reporting Form R's, preparation of EPCRA Tier II reporting forms, compliance with local, state, and federal regulations and reporting requirements for solid waste, hazardous waste, air, groundwater, and stormwater.

PROJECT EXPERIENCE:

- Project Manager for geotechnical investigations involving shallow and deep foundations, sinkholes, and rock anchors throughout the Southeastern United States.
- Site Geotechnical engineer and Project Manager for repair of a collapsed 10' diameter sewer line in Ensley, Alabama.
- Project Manager for Phase I and II ESAs: conducted and managed environmental site assessments for real estate transactions throughout the Southeastern United States.
- Project Manager for UST Closure Assessments: conducted and managed UST closure assessments throughout the State of Alabama.
- Project Manager for NPDES Permitting: supervised compliance for industrial facilities and construction sites throughout Jefferson and Shelby Counties in the State of Alabama.
- Project Manager and supervisor for NPDES Permitting: supervised compliance for over 40 industrial facilities and construction sites throughout Jefferson and Shelby Counties in the State of Alabama. Also, supervisor for inspection of 700 outfalls in Jefferson County for Jefferson County during 1995.
- Project Manager for preliminary investigation on possible contaminated facility that was Alabama Underground Storage Tank (AUST) trust fund eligible.
- Project Manager for an Emergency Response incident at a facility in Bessemer, Alabama.
- Responsible for compilation and implementation of a Confirmatory Sampling Workplan at a RCRA facility located in Jefferson County, Alabama.
- Responsible for preparation of an Asbestos Abatement Plan to be implemented at an off-shore oil drilling platform.

EMPLOYMENT HISTORY:

Project Engineer, Gallet & Associates, Inc. Birmingham, Alabama
1991- 1/98; Engineering Aide, 1990-1991

Environmental Engineer, U.S. Pipe and Foundry Company – North Birmingham Plant,
2/98 – 11/99

Engineer, Environmental Engineers, Inc., Odenville, Alabama
1/1999 - Present


EDUCATION

Bachelor of Science in Civil Engineering, University of Alabama, Tuscaloosa, 1991

CERTIFICATIONS:

Professional Engineer certification - Alabama, 1997
Professional Engineer certification - Georgia, 2000
Professional Engineer certification - Tennessee, 2003
Professional Engineer certification - South Carolina, 2003
Professional Engineer certification - North Carolina, 2005
Professional Engineer certification - Mississippi, 2005
Professional Engineer certification - Texas, 2005
40-Hour OSHA trained, 1995
AHERA Inspector/Management Planner certification, 1998
AHERA Asbestos Abatement Project Designer, 1999
Lead-Based Paint Inspector/Risk Assessor certification, 2007

Appendix B




Environmental Engineers, Inc.

Subject:
Phase I Environmental Site Assessment
Proposed MSWIN 30410 C Hickory Flat Communications Facility
Hickory Flat, Benton County, Mississippi
Environmental Engineers, Inc. Project No.: JSE01P1016

Appendix B
1974 Aerial






Environmental Engineers, Inc.

Subject:
Phase I Environmental Site Assessment
Proposed MSWIN 30410 C Hickory Flat Communications Facility
Hickory Flat, Benton County, Mississippi
Environmental Engineers, Inc. Project No.: JSE01P1016

Appendix B
1992 Aerial





Environmental Engineers, Inc.

Subject:
Phase I Environmental Site Assessment
Proposed MSWIN 30410 C Hickory Flat Communications Facility
Hickory Flat, Benton County, Mississippi
Environmental Engineers, Inc. Project No.: JSE01P1016

Appendix B
1996 Aerial



ep. 14, 2006




Environmental Engineers, Inc.

Subject:
Phase I Environmental Site Assessment
Proposed MSWIN 30410 C Hickory Flat Communications Facility
Hickory Flat, Benton County, Mississippi
Environmental Engineers, Inc. Project No.: JSE01P1016

Appendix B
2006 Aerial





Environmental Engineers, Inc.

Subject:
Phase I Environmental Site Assessment
Proposed MSWIN 30410 C Hickory Flat Communications Facility
Hickory Flat, Benton County, Mississippi
Environmental Engineers, Inc. Project No.: JSE01P1016

Appendix B
2009 Aerial



Appendix C

FirstSearch Technology Corporation

Environmental FirstSearch™ Report

Target Property: HICKORY FLAT

CORNERVILLE ROAD

HICKORY FLAT MS 38633

Job Number: JSE01P1016

PREPARED FOR:

Environmental Engineering, Inc.

11578 US Highway 411

Odenville, AL 35120

11-12-10



Tel: (407) 265-8900

Fax: (407) 265-8904

Environmental FirstSearch Search Summary Report

Target Site: CORNERSVILLE ROAD
HICKORY FLAT MS 38633

FirstSearch Summary

Database	Sel	Updated	Radius	Site	1/8	1/4	1/2	1/2>	ZIP	TOTALS
NPL	Y	10-21-10	1.00	0	0	0	0	0	0	0
NPL Delisted	Y	10-21-10	0.50	0	0	0	0	-	0	0
CERCLIS	Y	08-31-10	0.50	0	0	0	0	-	0	0
NFRAP	Y	08-31-10	0.50	0	0	0	0	-	0	0
RCRA COR ACT	Y	09-14-10	1.00	0	0	0	0	0	0	0
RCRA TSD	Y	09-14-10	0.50	0	0	0	0	-	0	0
RCRA GEN	Y	09-14-10	0.25	0	0	0	-	-	0	0
RCRA NLR	Y	09-14-10	0.25	0	0	0	-	-	0	0
Federal Brownfield	Y	10-01-10	0.50	0	0	0	0	-	0	0
ERNS	Y	10-21-10	0.15	0	0	0	-	-	0	0
Tribal Lands	Y	01-01-96	1.00	0	0	0	0	0	1	1
State/Tribal Sites	Y	10-01-10	1.00	0	0	0	0	0	0	0
State Spills 90	Y	NA	0.25	0	0	0	-	-	0	0
State/Tribal SWL	Y	07-27-07	0.50	0	0	0	0	-	0	0
State/Tribal LUST	Y	10-01-10	0.50	0	0	0	0	-	2	2
State/Tribal UST/AST	Y	10-01-10	0.25	0	0	0	-	-	0	0
State/Tribal EC	Y	10-01-10	0.50	0	0	0	0	-	0	0
State/Tribal IC	Y	10-01-10	0.25	0	0	0	-	-	0	0
State/Tribal VCP	Y	10-01-10	0.50	0	0	0	0	-	0	0
State/Tribal Brownfields	Y	10-01-10	0.50	0	0	0	0	-	0	0
State Other	Y	01-01-07	0.25	0	0	0	-	-	0	0
Federal IC/EC	Y	11-04-10	0.50	0	0	0	0	-	0	0
- TOTALS -				0	0	0	0	0	3	3

Notice of Disclaimer

Due to the limitations, constraints, inaccuracies and incompleteness of government information and computer mapping data currently available to FirstSearch Technology Corp., certain conventions have been utilized in preparing the locations of all federal, state and local agency sites residing in FirstSearch Technology Corp.'s databases. All EPA NPL and state landfill sites are depicted by a rectangle approximating their location and size. The boundaries of the rectangles represent the eastern and western most longitudes; the northern and southern most latitudes. As such, the mapped areas may exceed the actual areas and do not represent the actual boundaries of these properties. All other sites are depicted by a point representing their approximate address location and make no attempt to represent the actual areas of the associated property. Actual boundaries and locations of individual properties can be found in the files residing at the agency responsible for such information.

Waiver of Liability

Although FirstSearch Technology Corp. uses its best efforts to research the actual location of each site, FirstSearch Technology Corp. does not and can not warrant the accuracy of these sites with regard to exact location and size. All authorized users of FirstSearch Technology Corp.'s services proceeding are signifying an understanding of FirstSearch Technology Corp.'s searching and mapping conventions, and agree to waive any and all liability claims associated with search and map results showing incomplete and or inaccurate site locations.

***Environmental FirstSearch
Site Information Report***

Request Date: 11-12-10
Requestor Name: Chad Stinnett
Standard: AAI

Search Type: COORD
Job Number: JSE01P1016
Filtered Report

Target Site: CORNERSVILLE ROAD
HICKORY FLAT MS 38633

Demographics

Sites: 3	Non-Geocoded: 3	Population: NA
Radon: 0.2 - 0.8 PCI/L		

Site Location

	<u>Degrees (Decimal)</u>	<u>Degrees (Min/Sec)</u>	<u>UTMs</u>
Longitude:	-89.207711	-89:12:28	Easting: 297563.158
Latitude:	34.607597	34:36:27	Northing: 3831547.846
Elevation:	472		Zone: 16

Comment

Comment:

Additional Requests/Services

Adjacent ZIP Codes: 0 Mile(s)	Services:
--------------------------------------	------------------

<u>ZIP Code</u>	<u>City Name</u>	<u>ST</u>	<u>Dist/Dir</u>	<u>Sel</u>

	<u>Requested?</u>	<u>Date</u>
Fire Insurance Maps	Yes	11-12-10
Aerial Photographs	No	
Historical Topos	No	
City Directories	No	
Title Search/Env Liens	No	
Municipal Reports	No	
Online Topos	No	

***Environmental FirstSearch
Sites Summary Report***

Target Property: CORNERSVILLE ROAD
HICKORY FLAT MS 38633

JOB: JSE01P1016

TOTAL: 3 **GEOCODED:** 0 **NON GEOCODED:** 3 **SELECTED:** 0

Map ID	DB Type	Site Name/ID/Status	Address	Dist/Dir	ElevDiff	Page No.
TRIBALLAND		BUREAU OF INDIAN AFFAIRS CONTA BIA-38633	UNKNOWN MS 38633	NON GC	N/A	N/A
LUST		LAWSON SIMPSON GROCERY 5482/CLOSED	HIGHWAY 5 WEST HICKORY FLAT MS 38633	NON GC	N/A	N/A
LUST		GADD OIL COMPANY 7724/CLOSED	UNITED STATES HIGHWAY 78 HICKORY FLAT MS 38633	NON GC	N/A	N/A

Environmental FirstSearch Descriptions

NPL: EPA NATIONAL PRIORITY LIST - The National Priorities List is a list of the worst hazardous waste sites that have been identified by Superfund. Sites are only put on the list after they have been scored using the Hazard Ranking System (HRS), and have been subjected to public comment. Any site on the NPL is eligible for cleanup using Superfund Trust money.

A Superfund site is any land in the United States that has been contaminated by hazardous waste and identified by the Environmental Protection Agency (EPA) as a candidate for cleanup because it poses a risk to human health and/or the environment.

FINAL - Currently on the Final NPL

PROPOSED - Proposed for NPL

NPL DELISTED: EPA NATIONAL PRIORITY LIST Subset - Database of delisted NPL sites. The National Oil and Hazardous Substances Pollution Contingency Plan (NCP) establishes the criteria that the EPA uses to delete sites from the NPL. In accordance with 40 CFR 300.425.(e), sites may be deleted from the NPL where no further response is appropriate.

DELISTED - Deleted from the Final NPL

CERCLIS: EPA COMPREHENSIVE ENVIRONMENTAL RESPONSE COMPENSATION AND LIABILITY INFORMATION SYSTEM (CERCLIS)- CERCLIS is a database of potential and confirmed hazardous waste sites at which the EPA Superfund program has some involvement. It contains sites that are either proposed to be or are on the National Priorities List (NPL) as well as sites that are in the screening and assessment phase for possible inclusion on the NPL.

PART OF NPL- Site is part of NPL site

DELETED - Deleted from the Final NPL

FINAL - Currently on the Final NPL

NOT PROPOSED - Not on the NPL

NOT VALID - Not Valid Site or Incident

PROPOSED - Proposed for NPL

REMOVED - Removed from Proposed NPL

SCAN PLAN - Pre-proposal Site

WITHDRAWN - Withdrawn

NFRAP: EPA COMPREHENSIVE ENVIRONMENTAL RESPONSE COMPENSATION AND LIABILITY INFORMATION SYSTEM ARCHIVED SITES - database of Archive designated CERCLA sites that, to the best of EPA's knowledge, assessment has been completed and has determined no further steps will be taken to list this site on the National Priorities List (NPL). This decision does not necessarily mean that there is no hazard associated with a given site; it only means that, based upon available information, the location is not judged to be a potential NPL site.

NFRAP – No Further Remedial Action Plan

P - Site is part of NPL site

D - Deleted from the Final NPL

F - Currently on the Final NPL

N - Not on the NPL

O - Not Valid Site or Incident

P - Proposed for NPL

R - Removed from Proposed NPL

S - Pre-proposal Site

W – Withdrawn

RCRA COR ACT: EPA RESOURCE CONSERVATION AND RECOVERY INFORMATION SYSTEM SITES - Database of hazardous waste information contained in the Resource Conservation and Recovery Act Information (RCRAInfo), a national program management and inventory system about hazardous waste handlers. In general, all generators, transporters, treaters, storers, and disposers of hazardous waste are required to provide information about their activities to state environmental agencies. These agencies, in turn pass on the information to regional and national EPA offices. This regulation is governed by the Resource Conservation and Recovery Act (RCRA), as amended by the Hazardous and Solid Waste Amendments of 1984.

RCRAInfo facilities that have reported violations and subject to corrective actions.

RCRA TSD: EPA RESOURCE CONSERVATION AND RECOVERY INFORMATION SYSTEM TREATMENT, STORAGE, and DISPOSAL FACILITIES. - Database of hazardous waste information contained in the Resource Conservation and Recovery Act Information (RCRAInfo), a national program management and inventory system about hazardous waste handlers. In general, all generators, transporters, treaters, storers, and disposers of hazardous waste are required to provide information about their activities to state environmental agencies. These agencies, in turn pass on the information to regional and national EPA offices. This regulation is governed by the Resource Conservation and Recovery Act (RCRA), as amended by the Hazardous and Solid Waste Amendments of 1984.

Facilities that treat, store, dispose, or incinerate hazardous waste.

RCRA GEN: EPA/MA DEP/CT DEP RESOURCE CONSERVATION AND RECOVERY INFORMATION SYSTEM GENERATORS - Database of hazardous waste information contained in the Resource Conservation and Recovery Act Information (RCRAInfo), a national program management and inventory system about hazardous waste handlers. In general, all generators, transporters, treaters, storers, and disposers of hazardous waste are required to provide information about their activities to state environmental agencies. These agencies, in turn pass on the information to regional and national EPA offices. This regulation is governed by the Resource Conservation and Recovery Act (RCRA), as amended by the Hazardous and Solid Waste Amendments of 1984.

Facilities that generate or transport hazardous waste or meet other RCRA requirements.

LGN - Large Quantity Generators

SGN - Small Quantity Generators

VGN – Conditionally Exempt Generator.

Included are RAATS (RCRA Administrative Action Tracking System) and CMEL (Compliance Monitoring & Enforcement List) facilities.

CONNECTICUT HAZARDOUS WASTE MANIFEST – Database of all shipments of hazardous waste within, into or from Connecticut. The data includes date of shipment, transporter and TSD info, and material shipped and quantity. This data is appended to the details of existing generator records.

MASSACHUSETTES HAZARDOUS WASTE GENERATOR – database of generators that are regulated under the MA DEP.

VQN-MA = generates less than 220 pounds or 27 gallons per month of hazardous waste or waste oil.

SQN-MA = generates 220 to 2,200 pounds or 27 to 270 gallons per month of waste oil.

LQG-MA = generates greater than 2,200 lbs of hazardous waste or waste oil per month.

RCRA NLR: EPA RESOURCE CONSERVATION AND RECOVERY INFORMATION SYSTEM SITES - Database of hazardous waste information contained in the Resource Conservation and Recovery Act Information (RCRAInfo), a national program management and inventory system about hazardous waste handlers. In general, all generators, transporters, treaters, storers, and disposers of hazardous waste are required to provide information about their activities to state environmental agencies. These agencies, in turn pass on the information to regional and national EPA offices. This regulation is governed by the Resource Conservation and Recovery Act (RCRA), as amended by the Hazardous and Solid Waste Amendments of 1984.

Facilities not currently classified by the EPA but are still included in the RCRAInfo database. Reasons for non classification:

Failure to report in a timely matter.

No longer in business.

No longer in business at the listed address.

No longer generating hazardous waste materials in quantities which require reporting.

ERNS: EPA/NRC EMERGENCY RESPONSE NOTIFICATION SYSTEM (ERNS) - Database of incidents reported to the National Response Center. These incidents include chemical spills, accidents involving chemicals (such as fires or explosions), oil spills, transportation accidents that involve oil or chemicals, releases of radioactive materials, sightings of oil sheens on bodies of water, terrorist incidents involving chemicals, incidents where illegally dumped chemicals have been found, and drills intended to prepare responders to handle these kinds of incidents. Data since January 2001 has been received from the National Response System database as the EPA no longer maintains this data.

Tribal Lands: DOI/BIA INDIAN LANDS OF THE UNITED STATES - Database of areas with boundaries established by treaty, statute, and (or) executive or court order, recognized by the Federal Government as territory in which American Indian tribes have primary governmental authority. The Indian Lands of the United States map layer shows areas of 640 acres or more, administered by the Bureau of Indian Affairs. Included are

Federally-administered lands within a reservation which may or may not be considered part of the reservation.
BUREAU OF INDIAN AFFIARS CONTACT - Regional contact information for the Bureau of Indian Affairs offices.

Tribal Lands: *MS BCI* CHOCTAW INDIAN TRIBAL LANDS - database of Mississippi Choctaw Indian tribal land boundaries. The database includes information on boundary name and acreage.

State/Tribal Sites: *MDEQ* CERCLA/UNCONTROLLED SITES FILE LIST - database of information on both CERCLA sites as well as facilities defined as a site, facility, plant, or location where hazardous or toxic wastes have been released to the environment and, due to existing regulations, there is no Federal program which can handle the problem.

State/Tribal SWL: *MDEQ* SOLID WASTE LANDFILLS LIST - database of active and closed rubbish sites; active, inactive and closed municipal solid waste landfills; waste tire facilities and transfer stations.

State/Tribal LUST: *MDEQ* MISSISSIPPI UNDERGROUND STORAGE TANK RELEASE TANK SITES - database of all sites with either a suspected release or confirmed releases.

State/Tribal UST/AST: *MDEQ/EPA* MISSISSIPPI UNDERGROUND STORAGE TANK REGISTERED TANK SITES - database of underground storage tank facilities, tanks, and owners.
TRIBAL LAND UNDERGROUND STORAGE TANKS - database of underground storage tanks that are reported to be on Native American lands.

State/Tribal EC: *MDEQ* BROWNFIELD INVENTORY Subset - database of CERCLA/uncontrolled sites file list that have engineering controls.

State/Tribal IC: *MDEQ* BROWNFIELD INVENTORY Subset - database of CERCLA/uncontrolled sites file list that have institutional controls.

State/Tribal VCP: *MDEQ* CERCLA/UNCONTROLLED SITES FILE LIST (SUBSET, VOLUNTARY EVALUATION PROGRAM)- Uncontrolled Site Voluntary Evaluation Program, which allows accepted parties the opportunity to participate in a program that will expedite the evaluation of site information. An uncontrolled site is a site, facility, plant, or location where hazardous or toxic wastes have been released into the environment and there is no federal environmental program which can handle the problem.

State/Tribal Brownfields: *MDEQ* BROWNFIELD INVENTORY - database of CERCLA/uncontrolled sites file list.

RADON: *NTIS* NATIONAL RADON DATABASE - EPA radon data from 1990-1991 national radon project collected for a variety of zip codes across the United States.

State Other: *US DOJ* NATIONAL CLANDESTINE LABORATORY REGISTER - Database of addresses of some locations where law enforcement agencies reported they found chemicals or other items that indicated the presence of either clandestine drug laboratories or dumpsites. In most cases, the source of the entries is not the U.S. Department of Justice ("the Department"), and the Department has not verified the entry and does not guarantee its accuracy. All sites that are included in this data set will have an id that starts with NCLR.

Environmental FirstSearch Database Sources

NPL: *EPA* Environmental Protection Agency

Updated quarterly

NPL DELISTED: *EPA* Environmental Protection Agency

Updated quarterly

CERCLIS: *EPA* Environmental Protection Agency

Updated quarterly

NFRAP: *EPA* Environmental Protection Agency.

Updated quarterly

RCRA COR ACT: *EPA* Environmental Protection Agency.

Updated quarterly

RCRA TSD: *EPA* Environmental Protection Agency.

Updated quarterly

RCRA GEN: *EPA/MA DEP/CT DEP* Environmental Protection Agency, Massachusetts Department of Environmental Protection, Connecticut Department of Environmental Protection

Updated quarterly

RCRA NLR: *EPA* Environmental Protection Agency

Updated quarterly

ERNS: *EPA/NRC* Environmental Protection Agency

Updated annually

Tribal Lands: *DOI/BIA* United States Department of the Interior

Updated annually

Tribal Lands: *MS BCI* Mississippi Band of Choctaw Indians

Updated when available

State/Tribal Sites: *MDEQ* Mississippi Department for Environmental Quality

Updated quarterly

State/Tribal SWL: *MDEQ* Mississippi Department for Environmental Quality

Updated annually

State/Tribal LUST: *MDEQ* Mississippi Department for Environmental Quality, Office of Pollution Control, Groundwater and Solid Waste Division

Updated quarterly

State/Tribal UST/AST: *MDEQ/EPA* Mississippi Department for Environmental Quality

Updated quarterly

State/Tribal EC: *MDEQ* Mississippi Department for Environmental Quality

Updated quarterly

State/Tribal IC: *MDEQ* Mississippi Department for Environmental Quality

Updated quarterly

State/Tribal VCP: *MDEQ* Mississippi Department for Environmental Quality

Updated quarterly

State/Tribal Brownfields: *MDEQ* Mississippi Department for Environmental Quality

Updated quarterly

RADON: *NTIS* Environmental Protection Agency, National Technical Information Services

Updated periodically

State Other: *US DOJ* U.S. Department of Justice

Updated when available

Environmental FirstSearch
Street Name Report for Streets within .25 Mile(s) of Target Property

Target Property: CORNERSVILLE ROAD
HICKORY FLAT MS 38633

JOB: JSE01P1016

Street Name	Dist/Dir	Street Name	Dist/Dir
Cornersville Rd	0.21 SE		
Lagoon Rd	0.21 SE		




Environmental FirstSearch

1 Mile Radius
ASTM Map: NPL, RCRCOR, STATE Sites



CORNERVILLE ROAD, HICKORY FLAT MS 38633



Source: 2005 U.S. Census TIGER Files

- Target Site (Latitude: 34.607597 Longitude: -89.207711)
 - Identified Site, Multiple Sites, Receptor
 - NPL, DELNPL, Brownfield, Solid Waste Landfill (SWL), Hazardous Waste
 - Triballand.....
 - Railroads
- Black Rings Represent 1/4 Mile Radius; Red Ring Represents 500 ft. Radius






Environmental FirstSearch

.5 Mile Radius
ASTM Map: CERCLIS, RCRATSD, LUST, SWL



CORNERVILLE ROAD, HICKORY FLAT MS 38633



Source: 2005 U.S. Census TIGER Files

- Target Site (Latitude: 34.607597 Longitude: -89.207711) 
- Identified Site, Multiple Sites, Receptor   
- NPL, DELNPL, Brownfield, Solid Waste Landfill (SWL), Hazardous Waste 
- Triballand 
- Railroads 
- Black Rings Represent 1/4 Mile Radius; Red Ring Represents 500 ft. Radius




Environmental FirstSearch

.25 Mile Radius

ASTM Map: RCRA GEN, ERNS, UST, FED IC/EC, METH LABS



CORNERVILLE ROAD, HICKORY FLAT MS 38633



Source: 2005 U.S. Census TIGER Files

- Target Site (Latitude: 34.607597 Longitude: -89.207711)
 - Identified Site, Multiple Sites, Receptor
 - NPL, DELNPL, Brownfield, Solid Waste Landfill (SWL), Hazardous Waste
 - Triballand.....
 - Railroads
- Black Rings Represent 1/4 Mile Radius; Red Ring Represents 500 ft. Radius






Environmental FirstSearch

.25 Mile Radius
Non-ASTM Map: No Sites Found



CORNERVILLE ROAD, HICKORY FLAT MS 38633



Source: 2005 U.S. Census TIGER Files

- Target Site (Latitude: 34.607597 Longitude: -89.207711) 
- Identified Site, Multiple Sites, Receptor   
- NPL, DELNPL, Brownfield, Solid Waste Landfill (SWL), Hazardous Waste 
- Triballand..... 
- National Historic Sites and Landmark Sites  
- Railroads 

Black Rings Represent 1/4 Mile Radius; Red Ring Represents 500 ft. Radius

Appendix D

GENERAL CONDITIONS
Environmental Services

Payment Terms – Payment is due upon receipt of our invoice. If payment is not received within 30 days from the invoice date, Client agrees to pay a finance charge on the principal amount of the past due account of one and one-half percent per month, and all cost of collection, including attorney fees. If one and one-half percent per month exceeds the maximum allowed by law, the charge shall automatically be reduced to the maximum legally allowable.

In the event Client requests termination of the services prior to completion, a termination charge in an amount not to exceed thirty percent of all charges incurred through the date services are stopped plus any shutdown costs may, at the discretion of Environmental Engineers, Inc. (Consultant) be made. If during the execution of the services, Consultant is required to stop operations as a result of changes in the scope of services such as requests by the Client or requirements of third parties, additional charges will be applicable.

General Nature Of Environmental Services – The Consultant's basic services comprise the specific environmental activities set forth in Proposal. The consultant will access the site pursuant to the scope of services set forth in Proposal. Consultant agrees to strive to perform the services set forth in the Agreement in accordance with generally accepted professional practices, in the same or similar localities, related to the nature of the work accomplished, at the time the services are performed. Consultant makes no warranties whatsoever, whether express or implied, regarding the services to be performed by it hereunder. Consultant's services are intended to solely benefit the client.

Scope of the Consultant's Basic Services – The environmental services shall consist of those tasks enumerated in the Proposal to this Agreement. The scope of work outlined in the Proposal represents a minimum program at this time. As the results of the investigation become known, other tests and/or sampling may be recommended to the Client for written approval as Additional Services. In general, an increased frequency of sampling and testing will improve the opinions reached in the Consultant's report. Because geologic and soil formations are inherently random, variable, and indeterminate in nature, the professional services rendered by the Consultant and opinions provided with respect to such services under this agreement (including opinions regarding potential cleanup costs), are not guaranteed to be a representation of actual site conditions or contamination or costs, which are also subject to change with time as a result of natural or man-made processes. Consultant will provide Client with a written ("Report") concerning the services performed. The Report will present such findings and conclusions as the Consultant may reasonably make with the information gathered in accordance with this Agreement. In preparing the Report, Consultant may review and interpret certain information provided to it by third parties, including government authorities, registries of deeds, testing laboratories, and other entities. Consultant will not conduct an independent evaluation of the accuracy or completeness of such information, and shall not be responsible for any errors or omissions contained in such information. The report and other instruments of services are prepared for, and made available for the sole use of, the Client, and the contents thereof may not be used or relied upon by any other person without the express written consent and authorization of the Consultant.

Additional Services of the Consultant – If mutually agreed in writing by the Client and the Consultant, the Consultant shall perform or obtain the services of others to perform the activities enumerated in the Proposal to this Agreement. Additional Services are not included as part of Basic Services and will be paid by the Client as provided in Payment Terms.

Services Excluded by the Consultant – Services not expressly set forth in writing as Basic or Additional Services and listed in the Proposal to this Agreement are excluded from the scope of the Consultant's services, and the Consultant assumes no duty to the Client to perform such services. The services to be performed by the Consultant shall not include an analysis or determination by the Consultant as to whether the Client is in compliance with federal, state, or local laws, statutes, ordinances, or regulations. The Consultant's services shall not include directly or indirectly storing, arranging for or actually transporting, disposing, treating or monitoring hazardous substances, hazardous materials, hazardous wastes or hazardous oils. The Consultant's services shall not include an independent analysis of work conducted and information provided by independent laboratories or other independent contractors retained by the Consultant concerning the Consultant's services provided to the Client. Unless otherwise specifically listed in the Proposal, the Consultant's services exclude testing for the presence of asbestos, mold, polychlorinated biphenyls (PCBs), radon gas, any airborne pollutants, underground mines or sinkholes.

Responsibilities of the Client – The Client shall provide all information in the possession, custody, or control which relates to the site, its present and prior uses, or to activities at the site which may bear upon the services of the Consultant under this Agreement, including, but not limited to, the following: (i) a legal description of the site, including boundary lines and a site plan; (ii) identification of the location of utilities, underground tanks, and other structures and the routing thereof at the site, including available plans of the site; and (iii) a description of activities which were conducted at the site at any time by the Client or by any person or entity which would relate to the services provided by the Consultant. The Client shall be fully responsible for obtaining the necessary authorizations to allow the Consultant, its agents, subcontractors and representatives, to have access to the site and buildings thereon at reasonable times throughout contract performance by the Consultant. Consultant will take reasonable precautions to minimize damage to the site from use of equipment, but unavoidable damage or alteration may occur and Client hereby releases and indemnifies Consultant and agrees to assume responsibility for such unavoidable damage or alteration. To the extent required by law, Client agrees to assume responsibility for personal and property damages due to Consultant's interference with subterranean structures such as pipes, tanks, and utility lines that are not correctly shown on the documents provided above by Client to Consultant. The services, information, and other data required by the Section to be furnished by the Client shall be at the Client's expense, and the Consultant may rely upon all data furnished by the Client and the accuracy and completeness thereof.

Client understands and agrees that the discovery of certain conditions by Consultant may result in economic loss to Client/property owner and/or regulatory oversight. Client agrees that Consultant is not responsible or liable for any loss resulting from a decrease in the market value of the property described in the Proposal. Client further agrees that Consultant is not responsible or liable for any costs associated with corrective or remedial actions necessary at the site. Unless included in Proposal, Client also agrees that Consultant is not responsible for disclosures, notifications, or reports that may be required to be made to third parties (including appropriate government authorities).

Consultant's Insurance – Consultant shall obtain, if reasonably available, (1) statutory Workers' Compensation/Employers Liability coverage; (2) Commercial General Liability; (3) Automobile Liability; and (4) Professional Liability insurance coverage in policy amounts of not less than \$1,000,000. Consultant agrees to issue certificates of insurance evidencing such policies upon written request.

Limitation of Responsibility – CLIENT HEREBY AGREES THAT TO THE FULLEST EXTENT PERMITTED BY LAW THE CONSULTANT'S TOTAL LIABILITY TO CLIENT FOR ANY AND ALL INJURIES, CLAIMS, LOSSES, EXPENSES, OR DAMAGES WHATSOEVER ARISING OUT OF OR IN ANY WAY RELATING TO THE PROJECT, THE SITE, OR THIS AGREEMENT FROM ANY CAUSE OR CAUSES INCLUDING BUT NOT LIMITED TO THE CONSULTANT'S NEGLIGENCE, ERRORS, OMISSIONS, STRICT LIABILITY, BREACH OF CONTRACT, OR BREACH OF WARRANTY SHALL NOT EXCEED THE GREATER OF THE TOTAL AMOUNT PAID BY THE CLIENT FOR THE SERVICES OF THE CONSULTANT UNDER THIS CONTRACT OR \$50,000.00, WHICHEVER IS GREATER. If Client prefers to have higher limits on professional liability, Consultant agrees to increase the limits up to a maximum of \$1,000,000.00 upon Client's written request at the time of accepting Proposal provided that Client agrees to pay an additional consideration of four percent of our total fee, or \$1,000.00, whichever is greater. Client and the Consultant agree that to the fullest extent permitted by law the Consultant shall not be liable to Client for any special, indirect or consequential damages whatsoever, whether caused by the Consultant's negligence, errors, omissions, strict liability, breach of contract, breach of warranty or other cause or causes whatsoever. To the fullest extent permitted by law, Client agrees to defend, indemnify, and hold Consultant, its agents, subcontractors, and employees harmless from and against any and all claims, defense costs, including attorney's fees, damages, and other liabilities arising out of or in any way related to the services to be performed by Consultant hereunder, Consultant's reports or recommendations concerning this Agreement of Consultant's presence on the project property, provided that Client shall not indemnify Consultant against liability for damages to the extent caused by the negligence or intentional misconduct of Consultant, its agents, subcontractors, or employees.

Disputes Resolution – All claims, disputes, and other matters in controversy between Consultant and Client arising out of or in any way related to this Agreement (other than a result of Client's failure to pay amounts due hereunder) will be submitted to "alternate dispute resolution" (ADR) such as mediation and/or arbitration, before and as a condition precedent to other remedies provided by law. If a dispute at law arises related to the services provided under this Agreement and that dispute requires litigation as provided above, then: (a) Client assents to personal jurisdiction in the State of Consultant's principal place of business; (b) The claim will be brought and tried in judicial jurisdiction of the court of the county where Consultant's principle place of business is located and Client waives the right to remove the action to any other county or judicial jurisdiction; and (c) The prevailing party will be entitled to recovery of all reasonable costs incurred, including staff time, court costs, attorney's fees, and expert witness fees, and other claim-related expenses.

Discovery of Unanticipated Pollutants Risks – If, while performing the services, pollutants are discovered that pose unanticipated risks, it is hereby agreed that the scope of services, schedule, and the estimated project cost will be reconsidered and that this contract shall immediately become subject to re-negotiation or termination. In the event that the Agreement is terminated because of the discovery of pollutants posing unanticipated risks, it is agreed that Consultant shall be paid for total charges for labor performed and reimbursable charges incurred to the date of termination of this Agreement, including, if necessary, any additional labor or reimbursable charges incurred in demobilizing. Client also agrees that the discovery of unanticipated hazardous substances may make it necessary for Consultant to take immediate measures to protect health and safety. Consultant agrees to notify Client as soon as practically possible should unanticipated hazardous substances or suspected hazardous substances be encountered. Client authorizes Consultant to take measures that in Consultant's sole judgment are justified to preserve and protect the health and safety of Consultant's personnel and the public. Client agrees to compensate Consultant for the additional cost of working to protect employees' and the public's health and safety.

Disposition of Samples and Equipment – No samples of unpolluted soil and rock will be kept by Consultant longer than thirty (30) days after submission of the final report unless agreed otherwise in the event that samples and/or materials contain or are suspected to contain substances or constituents hazardous or detrimental to health, safety, or the environment as defined by federal, state, or local statutes, regulations, or ordinances. Consultant will, after completion of testing (1) return such samples and materials to client, or (2) reach an agreement in writing to have such samples and materials properly disposed in accordance with applicable laws. Client agrees to pay all costs associated with the storage, transport, and disposal of samples and materials. Client recognizes and agrees that Consultant is acting as a bailee and at no time assumes title to said waste. All laboratory and field equipment contaminated in performing the required services will be cleaned at Client's expense. Contaminated consumables will be disposed of and replaced at Client's expense. Equipment (including tools) which cannot be reasonably decontaminated shall become the property and responsibility of Client. All such equipment shall be delivered to Client or disposed of in a manner similar to that indicated for hazardous samples. Client agrees to pay the fair market value of any such equipment which cannot reasonably be decontaminated.

Reports, Recommendations, and Ownership of Documents – Reports, recommendations, and other materials resulting from Consultant's efforts are intended solely for purposes of this Agreement; any reuse by Client or others for purposes outside of this Agreement or any failure to follow Consultant's recommendations, without Consultant's written permission, shall be at the user's sole risk. Client will furnish such reports, data, studies, plans, specifications, documents, and other information deemed necessary by Consultant for proper performance of its services. Consultant may rely upon Client-provided documents in performing the services required under this Agreement; however, Consultant assumes no responsibility or liability for their accuracy. Client-provided documents will remain property of Client. All reports, field notes, calculations, estimates, and other documents which are prepared, as instruments of service, shall remain Consultant's property and Consultant shall retain copyrights to these materials. Consultant will retain all pertinent records relating to services performed for a period of six years following submission of a report during which period the records will be made available to Client at all reasonable times.

Termination – This Agreement may be terminated by either party by seven (7) days written notice in the event of substantial failure to perform in accordance with the terms of the Agreement by the other party through no fault of the terminating party. If this Agreement is terminated, it is agreed that Consultant shall be paid for total charges for labor performed to the termination notice date, plus reimbursable charges.

Force Majeure – Neither party to this Agreement will be liable to the other party for delays in performing the services, nor for the direct or indirect cost resulting from such delays that may result from labor strikes, riots, war, acts of governmental authorities, extraordinary weather conditions or other natural catastrophes, or any cause beyond the reasonable control or contemplation of either party.

Severability and Survival – Any element of this Agreement later held to violate a law shall be deemed void, and all remaining provisions shall continue in force. However, Client and Consultant will in good faith attempt to replace any invalid or unenforceable provision with one that is valid and enforceable, and which comes as close as possible to expressing the intent of the original provision. All terms and conditions of this Agreement allocating liability between Client and Consultant shall survive the completion of the services hereunder and the termination of this Agreement.

Assignment – Consultant shall not delegate any duties, nor assign any rights or claims under this Agreement, nor sub any part of the work authorized, without prior consent of Client.

Appendix L



ENVIRONMENTAL ENGINEERS, INC.

11578 US Highway 411, Odenville, Alabama 35120

Environmental, Remediation, and Geological Consultants

November 23, 2010

Mr. Mark M. Orman
Benton County Chancery Clerk
P.O. Box 246
Ashland, MS 38603

Subject:

Proposed MSWIN 30410 C Hickory Flat Communications Facility
Hickory Flat, Benton County, Mississippi
Environmental Engineers, Inc. Project No.: JSE01P1016

Dear Mr. Orman:

Pursuant to the requirements of the March 2005 Nationwide Programmatic Agreement for Review of Effects on Historic Properties for Certain Undertakings Approved by the Federal Communications Commission (NPA) and Section 106 of the National Historic Preservation Act (NHPA) we are requesting comment on behalf of Towers of Mississippi, the State of Mississippi, and the Federal Emergency Management Agency regarding impact to historical or cultural sites listed on, or eligible for listing on the National Register of Historic Places (NRHP) by construction of a wireless communications tower in Benton County, Mississippi.

The site is depicted on the United States Geological Survey 7.5-minute Topographic Quadrangle "Hickory Flat, Mississippi," dated 1982. The site is located in the southwest ¼ of the northwest ¼ of Section 33, Township 5 South, Range 1 East, Benton County, Mississippi, at latitude 34° 36' 27.350" north and longitude 89° 12' 27.761" west (Figure 1). The site consists of a proposed 100-foot by 100-foot lease area with three associated guy anchor easements, and a proposed access road located off of Cornersville Road in Hickory Flat, Mississippi 38633. The site consists of land covered in scrub vegetation with a few scattered hardwood saplings up to three inches in diameter at breast height (dbh), and the site slopes moderately down to the west. The proposed facility access road follows an existing gravel road and extends west from Cornersville Road for approximately 1,300 feet. Proposed activities consist of construction of a 450-foot guyed communications tower and associated compound, enclosing the compound in a fence, placement of support equipment within the compound, and covering the compound with gravel. I have included the portion of the USGS topographic map depicting the proposed site location for your review.

Environmental Engineers, Inc. appreciates the opportunity to provide this information. Please reference the Environmental Engineers, Inc. project number (JSE01P1016) in correspondence regarding this site. Please provide comment within thirty days of the date of this letter. Thank you for your time and assistance and we look forward to your response. Please call me at (205) 629-3868 or email me at cstinnett@envciv.com if you have any questions or comments. You can also send a response to us via facsimile at (877) 847-3060.

Sincerely,

ENVIRONMENTAL ENGINEERS, INC.

Chad Stinnett
Senior Project Scientist

Attachments: Site Location Map

Phone: (205) 629-3868 • Fax: (877) 847-3060

9622 7738
2025 E000 0620
0707

U.S. Postal Service
CERTIFIED MAIL RECEIPT
(Domestic Mail Only. No Insurance Coverage Provided)

For delivery information visit our website at www.usps.com

OFFICIAL USE

Postage	\$	11/23/10 Postmark Here
Certified Fee		
Return Receipt Fee (Endorsement Required)		
Restricted Delivery Fee (Endorsement Required)		
Total Postage & Fees	\$ 5.34	JSE01D1016

Sent To: Mr. Mark M Orman
 Street, Apt. No., or PO Box No.
 City, State, ZIP+4

PS Form 3800, August 2005 See Reverse for Instructions

SENDER: COMPLETE THIS SECTION	COMPLETE THIS SECTION ON DELIVERY
<ul style="list-style-type: none"> Complete Items 1, 2, and 3. Also complete item 4 if Restricted Delivery is desired. Print your name and address on the reverse so that we can return the card to you. Attach this card to the back of the mailpiece, or on the front if space permits. 	<p>A. Signature <input checked="" type="checkbox"/> Mark M Orman <input type="checkbox"/> Agent <input type="checkbox"/> Addressee</p> <p>B. Received by (Printed Name) MARK M. Orman</p> <p>C. Date of Delivery 11/23/10</p> <p>D. Is delivery address different from item 1? <input type="checkbox"/> Yes If YES, enter delivery address below: <input type="checkbox"/> No</p>
<p>1. Article Addressed to: Mr. Mark M. Orman Benton County Chancery Clerk P.O. Box 246 Ashland, MS 38603</p>	<p>3. Service Type <input checked="" type="checkbox"/> Certified Mail <input type="checkbox"/> Express Mail <input type="checkbox"/> Registered <input type="checkbox"/> Return Receipt for Merchandise <input type="checkbox"/> Insured Mail <input type="checkbox"/> C.O.D.</p> <p>4. Restricted Delivery? (Extra Fee) <input type="checkbox"/> Yes</p>
<p>2. Article Number (Transfer from service label)</p>	<p>7010 0290 0003 5707 7738</p>

Ripley Southern Sentinel, 1701 City Avenue North

Account:		Ad ID:	544023
Name:	CHERYL JOHNSON	Description:	1349 LEGAL NOTICE
Company:	ENVIROMENTAL ENGINEERS, INC.	Towers of Mississi	
Address:	11578 US HWY. 411	Run Dates:	11/11/10 to 11/11/10
	ODENVILLE, AL 35120	Class:	1401
Telephone:	(877) 852-9589	Orig User:	JLD
		Words:	156
		Lines:	47

Ad Amount Due:

\$21.72

Notes:

1349

LEGAL NOTICE

Towers of Mississippi, the State of Mississippi, and the Federal Emergency Management Agency (FEMA) are requesting comment regarding construction of a 450 guyed communications tower to be located off of Cornersville Road, Hickory Flat, Benton County, Mississippi, at latitude 34° 36' 27.4" north and longitude 89° 12' 27.8" west.

We are also requesting comment, in accordance with Section 106 of the National Historic Preservation Act (NHPA), regarding potential impacts to historical or archaeological properties listed on, or eligible for listing on the National Register of Historic Places (NRHP), by the proposed communications tower.

All comments should be submitted within 30 days of the publication of this notice referencing project ISE01P1016 and sent to the attention of Mr. Henry Fisher, Environmental Engineers, Inc., 11578 U.S. Highway 411, Odenville, AL 35120. Mr. Fisher may also be reached via email at towerinfo@envciv.com, via telephone at (205) 629-3868, or via facsimile at (877) 847-3060.

Publish dates: 11/11/10